
THE NATIONAL METALWORKING WEEKLY October 16, 1952

AT WIS PAGE 2

SILENT SOLDIER FOR DEFENSE



On the Korean front . . . on American farms . . . in factories geared defense needs . . . New Departure Ball Bearings are worthy warriors. In an almost endless variety of applications, New Departures rease accuracy, permit higher speeds and resist all loads. They also duce maintenance and aid in simplifying design problems. New sparture application engineers will be glad to apply their skill and perience to your particular problem. They are available for everying from new design jobs to improvement of existing installations. The Great Ball of New Departure is the symbol of engineering

NOTHING ROLLS LIKE A BALL C

NEW DEPARTURE



tower service. It meets a long-felt need for a compact, heavy dury enough reducer that will operate continuously. tower service. It meets a tong-tell need for a compact, heavy duty speed reducer that will operate continuously, at high speeds and for look populate. neavy duty speed reducer that will operate continuously, at high speeds and for long periods. It is inherently quiet in high speeds and for long periods. It is inherently quiet in high speeds and for long periods. It is inherently quiet in high speeds and for long periods. nign speeds and for long periods. It is innerently quiet in operation. Extreme conditions of heat and humidity do not appearance. operation. Extreme continuous or near and numerity do not affect it. It carries high thrust loads itself to appear a manufacture of affections. affect it. It carries nigh thrust loads and night radial loads without loss of efficiency. It lends itself to rugged mounts without loss of efficiency of its design it is easily in the simplicity of its design. without loss of emciency. It tends fiself to rugged mounts ing, and due to the simplicity of its design, it is easily in stalled serviced and adjusted in the field.

Every CU drive is run in and pretested under load before stalled, serviced and adjusted in the field. Every CU arive is run in and prefested under load before it leaves the factory. Thousands of units now in use provide its reliability in all classes of service—in the oil fields. in its reliability in all classes of service—in the oil fields, in industry in air conditioning everage in communications. its remanify in an classes of service—in the off neigh, in industry, in air conditioning systems in commercial and public buildings—in short wherever there's a cooling naustry, in air conditioning systems in commercial and public buildings—in short, wherever there's a cooling tower you can depend on CI

Write for Bulletin 135 for full description of Type CU, Ask also for free literature on other Cleveland units.

Cleveland Warm & Co. 2352 Fact 20th Creek tower, you can depend on CU.

Ask also for free literature on other Cleveland units. The Cleveland Worm & Gear Co., 3252 East 80th Street,

Affiliate: The Farval Corporation, Centralized Systems of Ultrate: The Farrar Corporation, Centralized Systems of Lubrication. In Canada: Peacock Brothers Limited. Cleveland 4, Ohio.





They're So Easy to Machine!

For a circular steel blank, the machine shop is the first real test. Can it be rough-cut easily? Finished up smoothly and fast? Or will it cause the machinist all sorts of trouble?

Naturally, much depends on what's inside the blank. If it's a Bethlehem circular forging, it's solid metal all the way through. Your machinist will always be cutting in firm, homogeneous steel. No danger of running into flaws after costly preliminary cuts have been taken.

You might ask, "How can we be sure? How are these blanks different from any others?"

First of all, they're made from steel selected with extra care. Second, they're made by a special, exclusive process that forges the steel and rolls it too — thereby insuring compactness of metal, uniform density, and just the right grain structure.

Use these blanks in making gears, crane and sheave wheels, brake wheels, tire molds, turbine rotors, flywheels, and many other heavy-duty products. They range in size from approximately 10 to 42 in. OD, and are available untreated or heat-treated. Booklet 216, sent free upon request, will give you the full story.

BETHLEHEM STEEL COMPANY, BETHLEHEM, PA.

On the Pacific Coast Bethlehem products are sold by Bethlehem Pacific Coast Steel Corporation, Export Distributor: Bethlehem Steel Export Corporation





BETHLEHEM ROLLED-AND-FORGED CIRCULAR PRODUCTS

the Iron Age - DIGES1

Vol. 170, No. 15 October 16, 1952

CONTENTS

*	Starred	Home	-	dinastad		opposite	-
_	Statted	items	are	aigestea	on	opposite	page.

EDITORIAL

Out With Controls	1
NEWS OF INDUSTRY	
*Special Report: TV Sales Channels Clear	37
Conservation: Catalysts Catch Waste Heat	39
*Construction: Economical Prestressing	40
*Materials Handling: 4-Wheeled Cost Cuts	41
*Transportation: Barge Shipments Rise	43
*International: The Blockbuster Missed	44
Production: Heavy Press Headaches	45
Research: Jets Zoom on Afterburner Production: More Wear on Cinder Pots	46
Controls Are Earnings Key to Price Aid?	49
Defense Contracts	50
Personnel: Iron Age Salutes	89
Iron Age Introduces	91
Clearing House	152
NEWS ANALYSIS	
Newsfront	35
*Automotive Assembly Line	54
*This Week in Washington	59
*Washington News: Nicaro Plants Pay Off	61
West Coast Report	63
*Machine Tool High Spots	64
Canadian Comment	67
TECHNICAL ARTICLES	
*Form-Quench Armor Plate In Hydraulic Press	97
*High Speed Screw Slotter Cuts Several Heads	100
*AISE Seeks Key To More and Better Steels	102
*Titanium Our No. 1 Problem Metal	105
*Moly Based Ceramic Used At High Temperature	114
Technical Briefs	116
MARKETS & PRICES	
*The Iron Age Summary—Steel Outlook	121
Market Briefs	123
Nonferrous Markets	124
Iron and Steel Scrap Markets	128
Comparison of Prices	132
Steel Prices	134
REGULAR DEPARTMENTS	
Dear Editor	9
Fatigue Cracks	11
Conventions and Meetings	13
Free Publications	69
New Equipment	75
INDEX OF ADVERTISERS	168

THE IRON AGE, published every Thursday by the CHILTON CO. (INC). Chestnut & 56th Sts., Philadelphia 39, Pa. Entered as second class matter, Nov. 5, 1932, at the Post Office at Philadelphia under the act of March 3, 1879. 38 yearly in United States, its territories and Canada; other Western Hemisphere Countries. \$15, other Foreign Countries. \$25 per year. Single copies. \$56. Annual Review and Metal Industry Facts Issue, \$2.00. Cables: "Tronage." N. T.

NEWS AND MARKETS

TV OUTPUT PICTURE HAS NO INTERFERENCE - P. 37

There's not a smudge of pessimism on the television industry's production picture. Inventories have been shed as sales improved. Manufacturers are rising to expectations of many new markets and greater buying interest. Many expect that next year will see 6 million video sets made—a fat gain over '52.

WILL BARS BOOST USE OF PRESTRESSING? — P. 40 Labor costs here have made it difficult to use prestressed concrete in America. Structural steel shortages aroused new interest in technique but it still took many manhours and much quality wire to tension cables. Now a new method known as the Lee-McCall system uses special bars and shows great promise.

WHAT MATERIALS HANDLING TRUCKS TO USE—P. 41
To successfully adapt materials handling equipment a plant must know its facilities. This equipment falls roughly into three categories: the lift truck, the tow truck or tractor, and the light crane. Fork trucks are versatile and speedy and come in many models for varying industrial jobs and needs.

BIG LOAD OF BARGES HAS GOTTEN BIGGER—P. 43
Barge traffic on the Mississippi climbed 8 pct in 1951 over
the figure for the previous year. The Tennessee River moved
into a pace-setting position with a claim of a 50 pct hike in
water shipments over 1950. Barge owners were calling the drop
in petroleum shipments a trend bound to continue.

DID WORLD WAR II BOMBING K.O. INDUSTRY?—P. 44
Survey of German industrial centers shows mass bombings only 2.5 pct effective. But safety of industry in the last war has no bearing on atom bomb era. Only 20 A-bombs needed to match the explosive power of all bombs dropped on Germany by Allies during World War II.

NAVY SEES NEED FOR NEW CARRIER PROGRAM-P. 59

The Navy Dept. may ask Congress early in '53 for the right a launch a huge new carrier building project. The Navy will argue larger and heavier carriers are needed for modern plants and new war needs. Much more steel will go into these ships which are larger than those constructed for World War.

of the WEEK in metalworking

ENGINEERING & PRODUCTION

MARKETS & PRICES

FORM-QUENCH PLATES IN HYDRAULIC PRESS—P. 97 Armor plates from 1/4 to 3 in. thick are formed and rapidly and uniformly quenched in the dies of a 2500-ton Fastraverse hydraulic press. Plates to 70 x 200 in. can be handled. Unit is located between hardening and draw furnaces with handling done on roller conveyers. Pressure can be varied as needed.

DETROIT ASSEMBLY LINES RUN AT FULL SPEED—P. 54
New passenger car and truck output is reminiscent of free market boom days. Industry sources are confident production will hit the half million mark this month. This would make October the best month since May, 1951. Paradoxically enough, these records are being set in spite of changeovers to new models.

FASTER SCREW SLOTTER CUTS SEVERAL HEADS—P. 100
A high speed screw slotter—20 times faster than conventional machine—can slot all standard sizes and head shapes. Round head screws require no deburring. Saws have longer life per grind than those on conventional equipment. Reduction of slotting costs have been estimated at 50 pct.

NICARO NICKEL PLANT IS PAYING DIVIDENDS—P. 61 Iron Age was told by GSA that a soon-to-be-issued report will show the millions spent in reactivating the Nicaro nickel plant are yielding good results. Preliminary figures indicate the plant is nearing an output rate of 15,000 tons and 12 furnaces are operating. The plant is now 8 pct more efficient.

AISE SEEKS KEY TO MORE AND BETTER STEELS—P. 102
Steelmaking engineers and executives attending their annual
Iron and Steel Exposition at Cleveland had one thought in
mind—how to get more and better steels from the country's
steelmaking machinery. Highlight of the reports on technical
progress was Jacques Sejournet's paper on steel extrusion.

STEEL FOR WESTERN DEFENSE EXPANSION EASES—P. 63
Steel supplies for defense-connected expansion in the West
Coast area should catch up with demand during the first quarter of '53. Issuance of NPA certificates in the area hit a new
low last week, coming to only 2 pct of the national average.
Mills see peak demand in the first quarter, then easing.

PART II—TITANIUM OUR NO. 1 PROBLEM METAL—P. 105
Titanium castings containing from zero to 0.015 C have been made by skull melting methods. New alloy powders soon to be available promise to help solve some of the difficulties in melting homogenious alloy ingots. Price of sponge made by magnesium reduction may fall.

HOW GOOD IS THE NPA TOOL INVENTORY?—P. 64 NPA's inventory of 30,000 machine tools left over from World War II is helping to break some of the tool shortage bottlenecks. But most critical needs must be met by new production. Evaluation of the inventory varies. Bright future seen for tool replacement business.

MOLY BASED CERAMIC OPERATES AT 2700° F—P. 114 A hybrid molybdenum based metal ceramic recently developed withstands thermal shock, resists oxidation, operates at temperatures about 2700° F. The material, known as D-1922, is made using powder metallurgy techniques. It can be turned, drilled, filed, cut in the pre-fired or "green" condition.

EXPECT EASING BUT STEEL MARKET'S TIGHT—P. 121Although steelmakers and users expect easier steel supply in first part of 1953, there is strong demand for record production. A freight car shortage is stalling some urgent deliveries. District sales offices report new tightening. Some mills are shortening their long-range scrap commitments.

NEXT WEEK—MADEOVER MACHINES FOR FAST START Pressed for delivery of new Army CD-80 tank transmissions Buick engineers scrounged up idle machinery from Army reserves, sorted over old fixtures. Inventive engineers came up with machines that got shipments moving. Setups weren't always ideal but many production bugs are being ironed out early.

U. S. LEAD PRICES FOLLOW BRITISH DECLINE—P. 124
Decline of lead prices on the London Metal Exchange last week
pressured American producers into slashing prices 1¢ to 14.80¢,
St. Louis. Demand remained low in spite of the dip. A further
drop may be in order, particularly if British prices remain at
current levels of about 135/8¢, New York delivery.

13

op

Something NEW in Selective Heat Treating . . .

LIQUID FLAME HEATING

This radically new but commercially proven application of the world renowned Ajax Salt Bath Furnace offers industry many unique advantages over any other method for selectively heating the rim or edges of circular objects, hardening teeth on gears or sprockets, and any other products that require peripheral heating.

The technique of operation is simplicity itself: Either a neutral type salt bath or a carburizing bath, heated by the internal electrode system, is maintained automatically at the required specific temperature. A number of the parts, such as gears, to be selectively heated can be mounted on a shaft within a suitable fixture which is placed over the salt bath. Only that portion of the periphery to be heated (such as the teeth) is immersed in the bath. The work is then rotated and heating is extremely rapid due to conduction by the intimate contact with the liquid salt.

Teeth of four 12" dia. gears, SAE 4140 steel, weighing 36 lb. each, being liquid flame hardened. Conventional carburizing bath operated at 1550 F. Total time cycle 4 minutes, followed by oil quench. Resultant tooth hardness 52 RC with tough core of only 36 RC.

COMPARE THESE ADVANTAGES . . .

with those possible from gas flame

1 FAST AND UNIFORM HEATING

Spood of heating approximates the rate at which the work conducts heat. The hot "carry-over" layer of salt clinging to heated pertion supplements heating, assures uniformity.

2 NO OVERHEATING

Since no temperature "head" is employed, overheating of the work is impossible.

3 NO OXIDATION, SCALING, OR DECARBURIZATION

The surface of work heated is protocted from air throughout entire operation due to the layer of liquid salt clinging to the revolving surface.

4 FLEXIBILITY

When not used for "Liquid Flame Heating", the salt both is available for conventional heat treating uses.

5 LESS COSTLY

Entire operation, both as to temperature and timing, is automatic using unskilled labor. Large batches of work can be treated simultaneously, effecting important economies over a piece-by-piece operation.

SEE IT DEMONSTRATED AT THE PHILADELPHIA METAL SHOW! BOOTH BUL OCTOBER 28-24

HERE'S PROOF

Let us treat sample batches of your work without obligation in the Ajax Metallurgical Service Laboratory. Better still, come see it done yourself! Reprint No. 73 sent on request.

Associate companies: Ajax Electric Furnace Corp. · Ajax Engineering Corp. · Ajax Electrothermic Corp.

A AX electric SALT BATH furnace

OVER 4,000 INSTALLATIONS . . . more than all other salt baths combined

AJAX ELECTRIC CO., INC., 904 Frankford Ave., PHILADELPHIA 23, PA.

Morgan Equipment at the FAIRLESS WORKS U. S. Steel Co.

It has been our pleasure to work with U. S. Steel Company for a good many years. During that time the company has entrusted us with the designing and building of 22 continuous rolling mills of various kinds.

Now at the Fairless Works we are building two more—a 10 stand skelp mill and an 18 stand horizontal-vertical continuous bar mill.

A total of 52 Morgoil Bearings are used — in 2 high and 4 high mills. In addition, five Morgan Ejectors will be used on the reheating furnaces.

MORGAN CONSTRUCTION CO.

English Rep., International Construction Co., 56 Kingsway, London W. C. 2, England

MORGAN

151.

ROLLING MILLS · WIRE MILLS · AIR EJECTORS · GAS PRODUCERS MORGOIL BEARINGS . REGENERATIVE FURNACE CONTROLS



Keep these shapes in mind

It will pay you to keep in mind the many advantages of special-shaped Armco Steel Tubing when you design or redesign your products. Tubing is pleasing to the eye. It may be the means of giving your product that extra "sales appeal."

Chances are good we can supply this mechanical tubing in any shape you require. Getting made-to-order shapes can help you eliminate or greatly reduce many costly fabricating operations. It also helps step up production.

Besides these shop savings, tubular parts give your products the most efficient section for structural requirements under many types of loading conditions.

This means lightweight, high-strength products at low cost.

RANGE OF SIZES

RMCO

When bending, flanging, expanding, beading, upsetting or swaging operations are necessary, you'll find Armco Tubing will do all that you ask of it. Sizes range from 1/4" to 3" O.D., wall thicknesses from .028 to .083.

Send for catalogs on Armco Steel Mechanical Tubing. A helpful new booklet tells "How to Fabricate Armco Steel Tubing"-gives you all the details you need. Just fill in the handy coupon, attach it to your company letterhead, and mail it today.

send me complete data

ARMCO STEEL CORPORATION 4262 Curtis Street, Middletown, Ohio

- Catalog on Armco Steel Mechanical Tubing.
- "How to Fabricate Armco Steel Tubing."



Armco Steel Corporation

4262 Curtis Street, Middletown, Ohio "ants and Sales Offices from Coast to Coast Editorial, Advertising and Circulation Offices, 100 E. 42nd St., N. Y. 17, N. Y.

GEORGE T. HOOK, Publisher TOM C. CAMPBELL, Editor

EDITORIAL STAFF

Managing Editor George F. Sullivan Technical Editor Darwyn I. Brown News-Markets Editor Wm. V. Packard Asst. Technical Editor W. G. Patton Machinery Editor F. C. Beaudet Asst. News Editor Theodore Metaxas News-Markers Earlor w.m. V. Eckard Asst. Technical Editor W. G. Patton Machinery Editor E. C. Beaudet Asst. News Editor Theodore Metaxas Associate Editors: H. W. Yan Camp, F. J. Winters, R. L. Hatschek, W. B. Olson, G. G. Carr; Assistant Editors: E. C. Kellogg, J. J. Obraut; Art Director: Carl Cerminaro; Regional Editors: K. W. Bennett, Chicago; R. D. Raddant, Detroit; J. B. Delaney, Pittsburgh; T. M. Rohan, San Francisco; G. H. Baker, A. K. Rannells, R. M. Stroupe, Woshington; Editorial Assistants: L. Brass, M. Persone, C. M. Walker; Correspondents: F. L. Allen, Birmingham: N. Levenson, Boston; R. M. Edmonds, St. Louis; James Douglas, Seattle: Jack Adams, Los Angeles; F. Sanderson, Toronto; F. H. Harley, London, England; Chilton Editorial Board: Paul Wooton, Washington.

BUSINESS STAFF

Production Manager 8. H. Hayes Director of Research Oliver Johnson Mgr. Circul'n & Promotion C. T. Post Asst. Promotion Mgr. James A. Crites Asst. Dir. of Research Wm. Laimbeer

REGIONAL BUSINESS MANAGERS

B. L. Herman, Philadelphia; Stanley J. Smith. Chicago; Harry G. Mumm, Columbus; Peirce Lewis, Detroit; Paul Bochman, New England; Charles R. Lippold, Cleveland; R. Raymond Kay, Los Angeles; C. H. Oher. New York; J. M. Spackman, Pittsburgh; Harry Becker, European Representative.

REGIONAL OFFICES

REGIONAL OFFICES
Chicago 3, 10 S. LoSalle St.; Cleveland
14, 1016 National City Bank Bldg.; Columbus 9, 1849 Franklin Park South; Detroit 2, 103 Pallister Ave.; Los Angeles
28, 2420 Cheremoya Ave.; New England,
62 LoSalle Rd., W. Hartford 7; New York 17, 100 E. 42nd St.; Philadelphia
39, 56th 6 Chestnut Sts.; Pittsburgh 22,
814 Park Bldg.; San Francisco 3, 1355
Market St.; Washington 4, National
Press Bldg.; European, 111 Thorley
Lane, Timperley, Cheshire, England.

Circulation Representatives: Thomas Scott, James Richardson.

One of the Publications Owned and ublished by Chilton Co., Inc., Chest-ut & 56th Sts., Philadelphia 39, Pa.

OFFICERS AND DIRECTORS JOS. S. HILDRETH, President

Vice-Presidents: Everit B. Terhune, P. M. Fahrendorf, G. C. Buzby, Harry V. Duffy; William H. Vallar, Treasurer; John Blair Moffet, Secretary; George T. Hook, Maurice E. Cox, Tom C. Campbell, Frank P. Tighe, L. V. Rowlands

lands, Directors.
George Maiswinkle, Asst. Treasurer.
Indexed in the Industrial Arts Index and the Engineering Index.









Controlled

E

National Publications

Copyright, 1952, by Chilton Co. (Inc.)

FOUNDED 1853

Out With Controls

W E have had price controls but no wage controls during the defense buildup. Labor seems to have gotten more under socalled wage stabilization than it would have obtained without controls. That is understandable when the one-sided stand of the Administration is considered.

While industry has been "allowed" to have a small price adjustment, it has been castigated, insulted and maligned for insisting that much of the higher wage costs must come from higher prices. These price adjustments have been given reluctantly. They have been accompanied usually by a smear campaign on profits.

This week hundreds of small companies are being squeezed between ceiling prices and higher wage and material costs. A delayed and half-baked method of allowing an increase to take care of higher material costs is being ballyhooed as "fair treatment."

What is really happening is that these smaller companies—and many big ones as well—are being forced to grant the same wage pattern as did the basic industries but are not allowed higher prices to take care of this increase.

The whole wage-price control setup has been a sham. Some Administration people are trying to prove that controls have stopped inflation. That's a laugh. It has been increased production which has stopped or temporarily halted inflation.

But increased production has not given companies a fair profit after taxes. Only from profits can a company put aside money with which to buy new equipment necessary to meet higher wage costs and to boost output. Thus price controls can make it impossible for firms to have the means of successfully combating inflation while at the same time granting unusual wage hikes.

All controls should be thrown out now. There was no need for them in the beginning. They have no place in a democracy which prides and proves itself on low unit cost, high production, defense accomplishments and customer satisfaction.

Tom Campbell

Editor



Here's yard loading and unloading at its best. A full-revolving, self-contained steel derrick, specially designed for working in congested quarters. Compact in size it occupies a minimum of ground space yet its full-revolving feature permits servicing an unusually large area.

ha

an

the

de

in

tio

bu

the

AI

do

tel

pe

do

the

as

Sin

M:

em

top

su

tai

rea

cal

The Clyde Whirlette is completely self contained . . . only one foundation is necessary . . . no stiff-legs or guy wires are required. The operator positioned on the rotating structure with the hoist, swings with the machine and always has a good vision of the load and work.

Choice of electric or gasoline power. Manual or mechanical swing.

Capacities: 10,00 lbs. at 10 ft. radius 4,500 lbs. at 20 ft. radius 2,000 lbs. at 40 ft. radius

For complete information write for circular MP-49.

CLYDE HANDI-CRANE

If you have material handling problems at scattered locations in your yard, a tractor mounted, Handi-Crane is the ideal solution. It moves swiftly from one spot to another . . . has a hydraulically operated boom that swings a full 320° to allow precision load handling on either side . . . and other Clyde advantages that cut material handling time and save operating space.

2 SIZES, 4 and 5 TONS CAPACITY

Circular MP - 46

gives full details.





WHIRLEYS . DERRICKS . HOISTS . BUILDERS TOWERS . CAR PULLERS . HANDI-CRANES . ROLLERS

CLYDE IRON WORKS, INC.

ESTABLISHED 1899

DULUTH, MINNESOTA

Dear Editor:

Letters from readers

A Privilege?

ir:

We have been taking THE IRON AGE since it was founded. Every assue crosses my desk and I always burn first to your editorial for I enjoy every one of them and want to compliment you on the fine way you have of expressing your thoughts and the topics selected.

Referring to your editorial "A Privilege," have you ever thought of the thousands of Americans to whom the wonderful privilege of voting is denied year after year by our archaic voting laws? They were inaugurated in our horse and buggy days.

I am well aware that many restrictions should be placed on our voters, but I cannot reconcile the denial of the ballot to the thousands who have to move from state to state around election time. It is just very unfair. And the boy scouts are calling at our doors and the radio blares forth and television daily calls us citizens to be sure to vote to preserve our liberties.

We Americans surely are funny people. We turn everything upside down to get out the vote and at the same time permit legislation denying the vote to thousands of fine citizens who are exactly entitled to it as much as you or I.

J. P. CHENEY Director

S. Cheney & Son Manlins, N. Y.

Older Worker

Sir:

Your editorial of Sept. 11 relative to "The Older Worker" is to be commended for the thoroughness in which you handled it.

But where is it going to get us? Many symposiums have been held on employing the older worker, some government sponsored, but at long as top management keeps on advertising for engineers, factory managers, superintendents under 45 years, the best use of our manpower to maintain our way of life will never be realized.

It is time that top management caught up with the times and realized that the best brains of the country are in the age of over 45.

Take my own experience, a registered professional and industrial engineer, with an outstanding record metal manufacturing. After 6 years of industrial consulting, on trying to re-enter the metal manufacturing business as a works manager

or factory superintendent, I have been informed that at the age of 54, when I am actually at the height of my knowledge and experience—too old. And why? Retirement at the age of 65. I have been told by management consultants, having the responsibility of screening employees for executive positions, that top management expects 20 years service before they consider an executive employee profitable.

How ridiculous! Your last paragraph certainly hits the nail on the

J. HAAS

Norwalk, Conn.

Plastic Dies

I enjoyed your very enlightening article in the Sept. 18 issue on plastic prototypes. In the same issue, under Automotive News, I noticed an article on the use of phenolic plastic in the manufacture of metalworking dies.

While our operation and our production is probably too small to utilize plastic prototypes, it might be that plastic dies may hold an important answer in our stamping picture since our runs are, of necessity, short and production comparatively low.

I would certainly appreciate any technical information you can give me on the use of phenolic plastics in the manufacture of dies, whether such dies can be used for forming only or may be used for piercing, notching, etc.

> A. R. LEO Purchasing Agent

Money-Meters, Inc. Providence

Write to Mr. Lee Miller, Resolin, Inc., 5736 W. 96th St., Los Angeles, Calif., for more details on plastic dies.—Ed.

Tool Life Studies

Sir:

The Newsfront page of your Oct. 2 issue contained an item referring to tool life studies made by a researcher on the effect of the type of coolant used and manner in which it is applied to carbide milling.


Will you please inform me if the results of these studies are available to industry and if so, where they can be obtained.

H. A. SMITH
Head, Process Development
Arms Research and Development
Olin Industries, Inc.
New Haven, Conn.

A full technical article on the results of these studies will appear in our Oct. 23 issue.—Ed.



for Die-less Duplicating



See the complete line at



800TH **630**


National Metals Exposition October 20-24 Philadelphia

Or send for New 32 page Catalog

O'NEIL-IRWIN MANUFACTURING CO.

Experienced buyers look at the Pedigree

buyers of boxes, too





THE COCKER SPANIEL, American member of a family that traces back to the 14th century, is still a great favorite with sportsmen. Cockers are said to be so named because they were first used in hunting woodcocks. Affectionate and merry, they are perfect family pets.

FOR ASSURANCE OF Quality
FOR ASSURANCE OF Fair Price

M^{OST} corrugated containers *look* alike. But the difference shows up in performance.

The famous Union shield trade-mark is your assurance that every step in making the box, from

the forest to the finishing room, is handled by trained personnel in the largest Kraft pulp-tocontainer plant in the world.

It symbolizes seventy-five years of leadership in designing, engineering and producing paper packages... plus long experience as one of the nation's larger producers of Kraft container board.

You can rely on Union shield-marked boxes to give you quality and service at a fair price—not only this year but for years to come!

UNION Corrugated Containers UNION BAG & Paper Corporation



Principal Offices: WOOLWORTH BLDG., NEW YORK 7, N.Y.

Corrugated Container Plants: SAVANNAH, GA. . CHICAGO, ILL. . TRENTON, N. J. . JAMESTOWN, N. C. (Highland Container Co., Inc.)

Fatigue Cracks

by Charles T. Post

Cradle to Grave

What with all the noise incident o the national election campaigns, very few people noticed last week that union labor had reached its goal of buttoning up the last of he seven ages of man. For some 50 years, New York's millinery workers have been organized-that is, all except one key group. The baby bonnet workers retained their individuality.

That's all over now. You can think of them henceforth as Local No. 110 of the A.F.L. United Hatters, Cap and Millinery Workers, who have a contract with ten employers. The employers, bowled over separately, are about to form their own association, it is indicated.

If you thought the steel strike was bad, just imagine what the effect on the nation's morale would be if the baby bonnet industry were shut down for a few months, what with all those bald, pink little heads exposed to the elements. We know what's going to happen next: The employers and the union will get together to stimulate style changes. Little Patty Ann, neé 1952, will be in high style with a mauve Princess Eugenie model perched on top of her head. Baby brother Ned, a 1953 arrival, will be ostracized without a cerise cloche pulled down over his ears. No more hand-me-downs.

The babies are pretty well tied down as far as their bonnets are concerned, but just let the Boot and Shoe Workers try and move in on the bootie factories. They'll have a few kicks coming there, we'll wager.

Tippecanoe

Our friends have had to pick up the tab for most of our lunches lately, merely because we bet them that they can't remember the name of the Republican vice-presidential candidate who ran with Wendell Willkie. (Ans.: The late Sen. Mc-Nary of Oregon.)

We finally got our come-uppance when we tossed the challenge to a couple of young secretaries here in the office.

AGE

"Why, Mr. Post," they admonished, "we were only ten years old during that campaign."

With that, we quietly brushed back our white mane, picked up our cane, and hobbled silently

Ceiling Price

Sometimes we don't know how seriously to take the Office of Price Stabilization.

Ceiling Price Regulation 34, Territorial Supplementary Regulation 2, October 1, 1952, is headed "Recapping and Retreading Services in the Virgin Islands."

Why Walk?

Bob Hammerstein, Bushwick Iron & Steel Co., Inc., calls our attention to the appointment of Walker Way as advertising and merchandising director for Chrysler automobiles.

More appropriate is the news item from Albany, N. Y., that Robert G. Bacon has sold his home to Howard Hamm. The broker: Richard I. Bone.

By this time, we've had a chance to check the answers on some of the earlier problems, and the honor roll reads like the roster of an engineering society.

Solving the problem of picking the counterfeit from 12 silver dollars in three weighings are Owen T. Barker, Post Cereals Div., General Foods; E. A. Schwab, Emerson Radio & Phonograph Corp.; R. H. Schaller, Jones & Laughlin; Lewis D. Rice, Timken Roller Bearing Co.; R. L. Sites, New York City; Edward C. Varnum, Barber-Colman Co.; and M. P. Higgins, Sam C. Earley Corp.

Mr. Heilman's chickens were correctly counted by Clarke Redfield. Eclipse-Pioneer Div.; J. W. Mc-Murray, South Wind Div., Stewart-Warner; David A. Climan, Allied Chemical & Dye Corp.; P. Pozzi, American Flange & Mfg. Co.; Joseph Mancini, Portland Copper & Tank Works; Thomas B. Hudson, Jr., Albert Curry & Co.; Mr. Rice, Mr. Schwab; and Carl Schendel, Clark Controller Co.

The inverted cone problem was mastered by Mr. Varnum; A. E. Canfield. The Strong-Scott Mfg. Co.; T. V. Sikorski, Reliable Electric Co.; and Charles Pipenhagen, Jr., Capson Mfg. Co.

Because Charles G. Heilman's chicken problem was so successful, you may want to try another of his with a little different twist: What number of four digits, when multiplied by 9, gives a product the reverse of itself? Of 5 digits? Of 6 digits?

metalwash

WASHING MACHINES PICKLING MACHINES **QUENCH TANKS**

metalwash

We are proud to announce publication of **METALWASH** FINISHING ENGINEER. a quarterly magazine addressed to executives and engineers to whom new methods and new materials for finishing are subjects of daily concern.



Please write us if you would like to receive FINISHING ENGINEER regularly, starting with the first issue, October, 1952




MACHINERY CORPORATION 920 North Avenue Elizabeth 4, New Jersey

> REPRESENTATIVES IN PRINCIPAL CITIES

BICKFORD for big work...

This powerful Cincinnati Bickford Super Service Radial Drill was purchased to facilitate handling of "big work." It was the right machine for the job. In the complete line of Cincinnati Bickford Radial Drills, with their many outstanding features, is the right machine for you.

Write us for descriptive literature, or consult our Engineering Department on drilling needs.



Photos—Courtesy Worthington Corporation, Steam Turbine Division, Wellsville, N. Y.



Cincinnati 9, Ohio, U.S.A.

Conventions & Meetings

ct. 13-17—American Institute of Electrical Engineers, Fall General Meeting, Jung Hotel, New Orleans, Institute headquarters are at 33 W. 39th St., New York.

ct. 14-16—Seventh Annual Industrial Packaging & Materials Handling Exposition, Chicago Collseum, headquarters are at 20 W. Jackson Blvd., Chicago.

oct. 16-17—Gray Iron Founders' Society, inc., 24th annual meeting and convention, Hotel Cleveland, Cleveland.

Oct. 17-19—Metal Treating Institute, annual meeting, Hotel Warwick, Philadelphia, Institute headquarters are at 271 North Ave., New Rochelle, New York

Oct. 19-21—Conveyor Equipment Manufacturers Assn., Annual Meeting, The Greenbrier, White Sulphur Springs, West Virginia. Association headquarters, 1129 Vermont Ave., N. W., Wash., D. C.

Oct. 19-24—American Welding Society, 33rd National Fall Meeting, The Bellevue-Stratford Hotel, Philadelphia, Pa.

Oct. 20-22—American Institute of Mining and Metallurgical Engineers, Institute of Metals Div., fall meeting, Hotel Adelphia, Philadelphia. Institute headquarters are at 29 W. 39th St., New York.

Oct. 20-24—National Metal Congress & Exposition, Convention Hall, Philadelphia.

Oct. 20-24—National Safety Council, national safety congress and exposition, Chicago. Council headquarters are at 20 N. Wacker Dr., Chicago.

Oct. 21—Gas Appliance Manufacturers Assn., Industrial Gas Equipt. Div., Hotel Warwick, Philadelphia.

Oct. 22-24—Society of Automotive Engineers, Inc., National Transportation Meeting, Hotel William Penn, Pittsburgh. Society headquarters are at 29 W. 39th St., New York.

Oct. 23-24—Steel Products Warehouse
Assn., annual meeting, Waldorf-Astoria
Hotel, New York.


Oct. 24—Malleable Founders' Society,
Western Section Meeting, The Drake,
Chicago. Society headquarters are at
Union Commerce Bldg., Cleveland.

Oct. 24—Illinois Mining Institute, 60th Annual Meeting, Hotel Abraham Lincoln, Springfield, III.

Oct. 26-29—American Gear Manufacturers Assn., semi-annual meeting, Edgewater Beach Hotel, Chicago. Assn. headquarters are at Empire Bldg., Pittsburgh.

Oct. 27-30—American Gas Assn., annual convention, Atlantic City, Hotel Traymore, N. J. Assn. headquarters are at 420 Lexington Ave., New York.

fire can't hide from this "Nose"






Walter Kidde & Company, Inc.

1049 Main Street, Belleville 9, N. J.

Walter Kidde & Company of Canada, Ltd., Montreal, P. Q.

AGI





CONSTRUCTION



LIFTING



MINING



MANUFACTURING




LOGGING



QUARRYING



OIL & GA




TRANSPORTATION


THE IRON AGE

must deliver...

because "We always strive to make HERCULES Red~Strand Wire Rope better than we claim it to be..."



This is a primary principle of Leschen manufacture. It must give you Red-Strand wire rope that wears exceptionally long . . . delivers top tonnage. It must give you Red-Strand wire rope that saves workers' time . . . earns their complete trust.



You get manufacturing craftsmanship when you use Hercules* Red-Strand wire rope. Leschen management and workmen know wire rope inside and out—it's their only business. They know how to make it better. Generations of the Leschen family—and workmen's families—take pride in producing a product that will serve you better.



You get exactingly tested wire rope when you use Hercules Red-Strand. Every coil of wire that goes into Leschen rope is rigidly torsion-and tension-tested. Every rope is double-checked for accurate fabrication—diameter, length of lay, strand clearance, lubrication. During World War II, millions of feet of Leschen wire rope passed every test by the Armed Forces without a single reject.



You get individual attention to satisfy your exact needs. Every executive, representative and workman in the Leschen organization follows this 95-year-old policy. Records are kept on every length of wire rope made in the Leschen mill—to provide rechecks on every installation—and to help you get the best type and grade of wire rope for your specific application.

Try Hercules Red-Strand wire rope. Keep comparative records. You'll experience the difference. Next time, specify . . .

PREFORMED . ROUND STRAND . FLATTENED STRAND . NON-ROTATING . LOCKED COIL . SLINGS



LESCHE WIRE ROPE

Reg. U.S. Pat. Off.

AGE

A. Leschen & Sons Rope Co., St. Louis 12, Missouri In business only to make wire rope — better wire rope — since 1857.

DISTRIBUTORS IN ALL PRINCIPAL CITIES

"Tycol Acylkup keeps bearings running cool... does not emulsify with water"



That's right! Tycol Acylkup Grease withstands heavy unit pressures . . . resists emulsification with water. It is easily applied by grease gun or central system.

Further, Tycol Acylkup Grease contains a high grade paraffin base cylinder oil that steps up bearing efficiency and assures increased bearing life. Protection against wear is long-lasting.

Your nearest Tide Water Associated Office will be glad to give you complete information. Call or wire today.

INDUSTRIAL LUBRICANTS

Boston • Charlotte, N. C. • Pittsburgh Philadelphia • Chicago • Detroit Tulsa • Cleveland • San Francisco



SEND FOR A FREE COPY OF "TIDE WATER ASSOCIATED LUBRICANIA"



Here's how Herbrand metallurgists and designers used Republic Steel 3-Dimension Metallurgical Service to pick the best Republic Alloy Steel to do the job . . .

Improvements in machinability on high-speed automatic machines were important . . . better hardenability of the finished wrench sockets was required . . . and production costs had to be kept down.

Herbrand metallurgists called in the Republic Field Metallurgist. Told him their problem. He went into a huddle with the other two members of the Republic 3-Dimension Metallurgical team . . . the Mill Metallurgist and the Laboratory Metallurgist.

The answer was soon ready . . . the recommendation of a certain one of the many grades of Republic Alloy Steels that would give Herbrand the desired machining and heat-treating characteristics, every time, lot-after-lot, at the necessary low cost.

You, too, can achieve quality improvements like this in your products . . . a call will bring the Republic Field Metallurgist into your picture.

REPUBLIC STEEL CORPORATION

Alloy Steel Division • Massillon, Ohio
GENERAL OFFICES • CLEVELAND 1, OHIO
Export Department: Chrysler Building, New York 17, N.Y.



rgh

roit isco

AGE

... Combines the extensive experience and coordinated abilities of Republic's Field. Mill and Laboratory Metallurgists with the knowledge and skills of your own engineers. It has helped guide users of Alloy Steels in countless industries to the correct steel and its most efficient usage. IT CAN DO THE SAME FOR YOU,



Problem...

DESIGNING AND BUILDING A COMPLETE WIRE GALVANIZING SYSTEM . . .

For galvanizing wire, Wean Equipment designed and built the first packaged line ever installed at one

Wire machinery in the past always just seemed to accumulate, and be merged into a line that would produce the type and kind of wire desired. Many wire concerns pieced together complete lines, oftentimes fabricating the machinery in their own shops. This is because there was very little coordinated engineering in the field. There was actually no place to go to purchase an entire line from a single source.

Wean Equipment Corporation had established a high reputation for designing and building special machinery for the metals working industries. Complete lines that would automatically perform difficult operations were Wean's strong suit. With this in mind the Colorado Fuel and Iron Corporation asked Wean to design and develop a complete wire galvanizing line to be installed in their Minnequa works.

Solution

PACKAGED LINE THAT PRODUCED BETTER WIRE AT RECORD SPEEDS .

Wean had been experimenting with automatic wire machinery and had assembled perhaps the largest library of wire machinery information held by one company. By drawing on this knowledge it was only a matter of months until the first completely packaged wire galvanizing line was being installed. Today the line is capable of applying a quality coating at a speed of three miles per minute. For all practical purposes there has been no maintenance.


The line is something of a composite of the best features found in studying lines assembled by several leading wire producers. Thirty-six strands of wire are galvanized simultaneously. Each strand has a tandem payoff reel. When one reel has reached the payoff point an operator merely twists the lead of the coil on the second reel to the end of the coil on the first reel and continuous operation is maintained. The wire is acid pickled. It is then water rinsed



Plain wire leaves payoff reels. Note the two reels for each strand of wire. It immediately enters the



Lead annealing box where drawing compounds are 3. Cooling rack where wire is air cooled, and into a .
 burned off. It then goes onto a . . .





e that e dether naise

of the

embled

rty-six

ously.

/hen

op-

the

to a .

CING

7. Splice caller, a unique device that detects the temporary splice, warning operator, then into the . . .



8. Galvanizing furnace where zinc coating is applied.
The wire then goes through an . . .




 Asbestos wipe where excess zinc is removed, giving wire a uniform coating, and then into a . . .



6. Flux tank where flux is applied preventing oxidation




11. Take-up blocks where it is cailed and periodically



10. Cold water quench for cooling prior to handling



5. Acid pickle to clean off remaining scale. It then



The take-up spindles are constructed in a manner that perfectly recoils the wire at high speeds, but still allows a collector to unfasten the rough joint and take each original coil off separately.

It's this kind of problem-solving work that has given Wean Equipment Corporation a reputation as the nation's foremost designers and builders of special machinery. Next time you find yourself in need of answers—call in a Wean engineer. There's absolutely no obligation.



4. Water rinse for complete cooling. Wire then en-

MACHINERY TODAY IS THE BUSINESS OF THE



Now . . . 2 New

AO COVERGLAS GOGGLES

Fit Over Safety And Personal Glasses



Safety Goggles



NEW - 4 WAYS!

- 1. New Cup Size and Shape
- 2. New Lens Size and Shape
- 3. New Side Shields
- 4. New Easy Lens Replacement



QUICK FACTS

AO's newest development in eye protection—Chippers' and Welders' Coverglas Goggles—can be worn over practically every pair of personal glasses (even the biggest frames) and most types of safety prescription goggles with and without side shield.

Wider vision, too, because the lenses are larger and scientifically designed to give up to 20% more vision. Yet, with all these features the goggles weigh but a fraction of an ounce more than ordinary Coverglas goggles . . . cost only slightly more.

These goggles are the newest . . . and two of the greatest . . . developments since the advent of safety goggles. Get all the facts about these two outstanding Coverglas goggles from your AO Safety Products Representative. He can supply you.

- Lens easily replaceable from rear (not front) by means of a spring clamp—no tools needed
- Lightweight, brown plastic cups fit face snugly, won't conduct heat or electricity
- Light-tight side shields for welders (on No. 327 goggle) provide indirect ventilation
- Bridge—High-grade leather. Instant adjustment
- AO worker-lab tests show much greater field of vision and increased comfort
- All-rubber headband, easily adjustable
 "326" Chippers' Coverglas goggle supplied with regular Super Armorplate lenses. "327" Welders' Coverglas goggle supplied with regular Noviweld lenses and cover lenses.

AO's Industrial Vision Program Increases Production, Decreases Accidents. Write today for booklet''Improved Industrial Vision'' to 1011 Vision Park, Southbridge, Mass.

American Optical
SAFETY PRODUCTS DIVISION


SOUTHBRIDGE, MASSACHUSETTS • BRANCHES IN PRINCIPAL CITIES

NAMCO VERS-O-TOOLS and COLLAPSIBLE TAPS SET THE STANDARD

for continuous, high production on rocket tube threading

On this rocket job these Namco threading tools outperformed any other method—in time-saving, in sustained quality and in trouble-free operation. The procedures we helped work out for the first pilot installation have since been adopted as standard at ten other plants contracting for the same job.

Regardless of the type of threading work you are doing, may we show you how the same basic principle can be applied to save you time, money and materials—with Namco Vers-O-Tools and Collapsible Taps?



JOB FACTS


PART—Rocket Nozzle

MATERIAL—X 1117 Steel

OPERATION — Thread $4^3/_4$ " Diameter, 12 Pitch, Class 2 Fit

MACHINE—W.F. and John Barnes Drill

DIEHEAD—Namco Type DR $4\frac{7}{8}$ " Vers-O-Tool with 6 ground thread circular chasers



7

front)

eeded

nugly,

No.

tment field

"327"

h reg-

AG

JOB FACTS

PART—Rocket Motor Tube

MATERIAL—NEA-8620 Steel, heattreated to Rockwell C-28-30

OPERATION—Tap 43/4" Diame-

ter, 12 Pitch, Class 2 Fit MACHINE—Lehman Double-End


Tapper

TAP—Namco Type RST 5" Collapsible with 5 ground-thread circular chasers.


ASK FOR NEW CATALOG DT-52 ...

for complete information on Namco Vers-O-Tools and Namco Collapsible Taps, available with ground thread precision chasers.





Nameo Type DR Vers-O-Tool Die Head threading rocket nozzles on a W. F. and John Barnes Drill— Firestone Steel Products Division Plant, Akron, Ohio




Nameo Type RST Collapsible Tap tapping rocket motor tube on Lehman Double End Tapper—Firestone Steel Products Division Plant, Akron, Ohio

The NATIONAL ACME CO.

170 EAST 131st STREET . CLEVELAND 8, OHIO

Acme-Gridley Bar and Chucking Automatics:
1-4-6 and 8 Spindle • Hydraulic Thread
Rolling Machines • Automatic Threading Dies
and Taps • The Chronolog • Limit, Motor Starter
and Control Station Switches • Solenoids
Centrifuges • Contract Manufacturing



WITH CRUCIBLE TOOL STEEL CASTINGS

The steel part shown above used to be a production headache. A cam for a cotton picking machine, it was originally flame cut from SAE 8730 boiler plate, machined and heat treated. Other difficult steps included end-milling and finish-grinding the cam track. Rejections were high, because the cam often warped during heat treatment.

The problem was solved by casting the cam in Airkool®, a Crucible air-hardening tool steel. When the customer receives the casting from Crucible, all he has to do is finish it, mill the cam track and heat

treat. He doesn't have to finish grind - Airkool is non-deforming when properly hardened and tempered. Machining costs are way down and quality is up, since Airkool resists wear far better than the low alloy steel from which the part used to be made.

Crucible's casting facilities often make it possible to use wear- and abrasion-resisting tool steel for complicated machine parts. We may be able to help you just as we helped the cotton picking machine manufacturer. Get in touch with Crucible today!

first name in special purpose steels

CRUCIBLE

SAND CASTINGS

52 years of Fine steelmaking

CRUCIBLE STEEL COMPANY OF AMERICA, GENERAL SALES OFFICES, OLIVER BUILDING, PITTSBURGH, PA REX HIGH SPEED . TOOL . REZISTAL STAINLESS . ALLOY . MACHINERY . SPECIAL PURPOSE STEELS

Illiance 12-ton

OPEN HEARTH CHARGING MACHINE

• This photograph shows a new low-type 12-ton Alliance Charging Machine recently installed in one of the world's largest and most efficient steel producing plants.

This machine, designed and built by Alliance, world's largest builder of big cranes, has an unusually large number of exclusive new features that make charging operations easier and less costly.

Spring-loaded pitman that always keeps the trolley on the rails, providing ample traction for pushing scrap into the furnace and for the retraction of peel and box.

Box section bridge girder made of welded I-beams reinforced by diaphragms spaced at 3-ft. intervals.

Full length machinery deck plate located between the main and outrigger girders provides lateral stiffness and a safety platform for maintenance.

Stabilized, shock-absorbing wheels are held in contact with both upper and lower rails by means of springs, which reduces shock to the operator.

Four track-equalizer trucks, located at the corners on eight-wheel bridges, compensate for any irregularities in the track.

Finger-tip control provided by new type hydraulic lock rod.

All gears (including track wheel gears) are fully enclosed and run in oil.

These and many other Alliance features result in smoother overall plant operation.

Whenever it's a problem of handling heavy materials of any kind at your plant, contact Alliance . . . the world's most respected builder of big cranes.



Alliance

MACHINE COMPANY

World's largest builders of world's largest cranes

MAIN OFFICE


PITTSBURGH OFFICE 1622 OLIVER BUILDING, PITTSBURGH, PA. ALLIANCE, OHIO

LADLE CRANES . GANTRY CRANES . FORGING MANIPULATORS . SOAKING PIT CRANES . STRIPPER CRANES . SLAB AND BILLET CHARGING MACHINES • OPEN HEARTH CHARGING MACHINES • SPECIAL MILL MACHINERY • STRUCTURAL FABRICATION

PA EELS

AGE

RELIANCE Totally-Enclosed Dual-Cooled D-c. motors



for Wider Speed Ranges... Higher Ratings

New Reliance Dual-Cooled Motors provide dependable totally-enclosed, fan-cooled operation over wider speed ranges and higher ratings than were ever before possible . . . and this is accomplished with floor-space savings of up to 30%!

Dual-Cooled Motors are completely enclosed... have two separate cooling systems operating independently of the motor speed. One system circulates high-velocity air within the motor, that is cooled in the finned inner duct of the heat exchanger. This heat is dissipated in the other system by air sweeping through the fins of the outer duct.

The Dual-Cooled Motor is especially adaptable to Reliance adjustable-voltage V*S Drive and is available in ratings from 15 through 150 horse-power. Explosion-proof Dual-Cooled Motors are available through 100 hp., in conformity with Underwriters and Bureau of Mines specifications.

Whatever your application . . . get further details from the nearest Reliance Sales Office . . . or write for Bulletin C-2201.

RELIANCE ELECTRIC AND ENGINEERING CO.

1083 Ivanhoe Road, Cleveland 10, Ohla . Sales Representatives in Principal Cities

MACLEOD ABRASIVE BLAST

EQUIPMENT



1897

NEW! The Completely Automatic

MACLEOD "AUTO-BLAST" ABRASIVE BLAST CLEANING MACHINE


Self-Contained..Large Capacity..Can Give 24-Hours-A-Day Continuous Blasting If Required

A completely new Macleod engineering development. A double-chamber blast cleaning machine with a continuous blasting cycle-no shutdown time for reloading . . . greatly reduced labor costs.

The refilling cycle is entirely automatic and does not depend on outside sources-such as a synchronized timing device, or motor-driven pumps or valves. The automatic cycle unit is built into the machine and is not influenced by the type or rate-of-flow of the abrasive. No interchangeable abrasive controls are required and the number and diameter of nozzles is no problem.

The Macleod "Auto-Blast" machine can be used with rooms, tables, barrels, or special automatic devices.

MACLEOD BLAST CLEANING ROOMS



Available in standard sizes or in special sizes to meet individual needs. Equipped with removable air baffles for longer life. Can be furnished with slot for chain-fall hoist or with rails for blast cars. Macleod manual, semi-authomatic, and fully automatic blast machines with non-choke type conveyors and latest-design elevators are available for all sizes of rooms.

Write for additional information or send specifications for estimate.



Company

2236 BOGEN ST.

CINCINNATI 22, OHIO, U.S.A.

ESTABLISHED 1897

AG

"We expect a lot from





hese American Springs"



says UNDERWOOD CORPORATION, world famous typewriter manufacturer

U NDERWOOD is so quality-conscious that they use a spring-cushioned packing crate for every typewriter shipped out of the country.

"These cushion springs have to be good," says Underwood, "because we use no other protective cushioning. Spring failure might result in broken castings, and delicate adjustments would certainly be thrown out of kilter. It would entail the costliest of repair jobs."

But Underwood has been using essentially the same American Quality Springs for over 40 years, and complaints are so rare that they are negligible. This is real spring service, especially when you consider that the typewriter goes by truck and rail to a shipping port, then is loaded aboard a freighter, unloaded, then shipped by rail, truck or, in some countries, very

frequently donkey cart to some interior town.

As Underwood puts it, "The cushion springs must absorb unbelievably rough handling, jostling and drops. But we have a good reputation for damage-free arrivals."

Why not consider tough American Quality Springs like these for your product? We are prepared to furnish any size, any grade of steel, any quantity. And if you are contemplating a new design, call in our spring design engineers now. They've encountered just about every problem in the history of spring-making; and they'll be sure to give you a quality spring at a cost you never thought possible. Call your nearest District Sales Office or write to American Steel & Wire Division, Rockefeller Building, Cleveland 13, Ohio.



AMERICAN STEEL & WIRE DIVISION, UNITED STATES STEEL COMPANY, GENERAL OFFICES: CLEVELAND, OHIO COLUMBIA-GENEVA STEEL DIVISION, SAN FRANCISCO, PACIFIC COAST DISTRIBUTORS


TENNESSEE COAL & IRON DIVISION, FAIRFIELD, ALA., SOUTHERN DISTRIBUTORS . UNITED STATES STEEL EXPORT COMPANY, NEW YORK




U-S-S American Quality Springs

HNITED STATES STEEL

AGE



SURFACE GRINDING. For fast, cool cutting action Norton wheels, cylinders and segments are unbeatable. 32 or 38 ALUNDUM abrasive for hardened steels and CRYSTOLON abrasive for gray iron and non-ferrous metals.



O.D. GRINDING. Norton O.D. wheels in the abrasives, grain sizes and bonds for best results on every material are sure protection for big grinding machine investments.

NORTON BRINGS YOU

More types of abrasive products... for More savings...on More jobs

You'll find the right answers to every one of your grinding problems in the Norton line of abrasive products. First, because it is the world's most complete line — offering you more choices than any other. Second, because Norton Research — which has chalked up an impressive list of "firsts" in abrasive development and Norton's endless field testing — make sure that every Norton abrasive product will deliver top performance on the work it is designed for.

That's the combination of variety and efficiency that will cut time, labor and costs on every grinding job you do.

SEE YOUR NORTON DISTRIBUTOR

for practical help in any grinding application. He knows Norton products—what they will do and what they won't do—and you'll find that his aid in selecting the right ones for your jobs is a real short cut to better, lower cost grinding...NORTON COMPANY, Worcester 6, Mass. Distributors in all principal cities. Export: Norton Behr-Manning Overseas Incorporated, Worcester 6, Mass.

*Trade-Marks Reg. U.S. Pat. Off. and Foreign Countries



Making better products to make other products better


TOOL AND CUTTER GRINDING. Norton New-Process wheels have no equal for uniformity, identical wheel performance and long even wheel wear. 32 ALUNDUM* abrasive for carbon and alloy steel, CRYS-TOLON* abrasive for cemented carbides.



POLISHING AND LAPPING. ALUNDUM grain comes in surface treatments and grain sizes for best results on every polishing job. And precise sizing makes ALUNDUM and CRYSTOLON abrasives favorites for even the fussiest lapping jobs.




ROUGH GRINDING. On swing frames, floor stands or portable grinders, Norton wheels "hug that work," to cut time and costs. And Norton Reinforced Hub Wheels are the safest, most versatile ever made.



BARREL-FINISHING. ALUNDUM tumbling abrasive, being all aluminum oxide, cuts without glazing, and has the hardness and toughness to stand repeated use. It's the abrasive for real precision-finishing.






DISC GRINDING. Norton ALUNDUM and CRYSTOLON discs boost production and reduce down-time. They leave flat surfaces straight and smooth, with no excess heat to cause warpage.



INTERNAL GRINDING. Being identical in grinding action, Norton New-Process wheels can be changed without machine adjustments. That and uniform top performance make them valuable production boosters.



CUTTING-OFF. For wet or dry applications, high or low speeds, on any material, there's a Norton wheel in ALUNDUM or CRYSTO-LON abrasive that's "made to order" for fast, economical cutting off.

bs

AGI





WISCONSIN STEEL COMPANY, affiliate of INTERNATIONAL HARVESTER COMPANY

180 North Michigan Avenue, Chicago 1, Illinois

WISCONSIN STEEL

Although certain types of shaft jobs offer natural opportunity as bar machine work, with the exception of the CONOMATIC, seldom do they appear on multiple spindle bar automatics. In general, shaft jobs require a longer tooling area than do other types of bar work.

A glance at the frame design of the CONOMATIC explains why its tooling area is longer* than the tooling areas of other "automatics." And there are more tool positions* and more room* for tool setting for any type of job.


*You can have the figures

and


down 240 uscle. s into npact,

Bros.

THERE'S More THAN JUST "Elbow Room



Rear Side of Tooling Area




A Comparison of ALL Automatics is in favor of Cone



Conomatic CONE AUTOMATIC MACHINE COMPANY, INC. WINDSOR, VT., U.S.A.

October 16, 1952

AGE



No Job FOR A WEAKLING

Handling hot plate is no job for weaklings. This is why the Drever Company chose rugged, powerful Hygrade Drives on this Roller-Hearth Hardening Furnace. These sturdy units not only handle this tough job with ease, but with minimum maintenance.

Wherever you have a speed reduction problem where low cost and rugged dependability are essential, the Hygrade Line of Enclosed Worm Gear Drives offers a solution. Available in a wide range of ratios and h.p. capacities in horizontal and vertical types. Vertical drives are also available with wider low speed bearing span to accommodate long, unsupported output shaft extensions.

FOOTE BROS.



Maxi-Power Drives



ver Line-O-Power Drives



Foote Bros.-Louis Allis Gearmotors

Foote Bros. Gear and Machine Corporation Dept. M, 4545 South Western Boulevard Chicago 9, Illinois

Please send a free copy of Bulletin HGB on Foote Bros. Hygrade Worm Gear Drives.



ing Furnace, treating Carbon Steel and Armor Plate, built by DREVER COMPANY, PHILADELPHIA.

Name...

Company

Position Address

Cirv

Zone...


..State...

MAMMOTH NATCO

Drilling 50 Holes on 36" Bolt Circle

Natco Engineered
for
Quality Production

NATCO Model C4B Vertical HOLESTEEL drillers are at work for industry today... doing tough peacetime and defense assignments with a maximum speed and a minimum of down time. NATCO machines of all types... drillers, borers, tappers and facers are veterans of years of service... many NATCO's are now in operation over forty years.



THIS TANK TRANSMISSION PART FOR EXAMPLE

50 holes in this rear gear case are combination 2 diameter drilled in two minutes . . . 30 parts per hour . . . day in and day out . . . just one example of NATCO economical production.

MATCO Model C4A Very neat MOLESTEEL Defor 36 round hand orranged with SIIp Type Spindtry, Johnson by Abonglid by Changling one spindly piece or vertic valuerable spindly.



es on ardeneating I and uilt by PANY,

s why grade These ease,

where il, the ffers a d h.p. drives pan to nsions.

Ace

Call a Natco Field Engineer

to help you solve your problems in Drilling, Tapping, Boring and Facing



NATIONAL AUTOMATIC TOOL COMPANY, INC., Richmond, Indiana

Branch Offices

1809 Engineering Bldg., CRICAGO • 409 New Center Bldg., DETROIT 1807 Elmwood Äve., BUFFALO • 2902 Commerce Bldg., NEW YORK CITY

A man who can help you get STEEL!

In these days of great demand, the help of an experienced steel man is especially valuable. Did you realize that the services of such a man are available to you without cost or obligation? This man is your Ryerson steel service representative—a specialist in getting available steel to you quickly.

He cannot make steel, of course, but he does have up-to-the-minute information on our stocks at his finger tips. He does have years of steel experience that often enables him to recommend practical alternates when the steel you need is not on hand. And he does know every phase of Ryerson service from testing for quality to dependable delivery, including heat treating, sawing, shearing, flame cutting or otherwise preparing steel to your particular requirements.

He represents, and has the wholehearted support of, the largest steel-service organization in the world. Working closely with him are Ryerson engineers, metallurgists—authorities on carbon, alloy and stainless steels—ready for quick cooperation on unusual problems.

While we have thousands of tons of steel on hand for immediate shipment, it is spread among 15 plants from Boston to Seattle. And the recent steel



strike, plus continued heavy demand, has unbalanced our stocks badly as to sizes and types. We believe this is the situation throughout the industry.

But your Ryerson service man is always ready to assist you... ready to help you scour the country from coast to coast to get the steel you need. So, talk over your steel problems with him the next time he calls.

PRINCIPAL PRODUCTS

CARBON STEEL BARS—Hot rolled and cold finished

STRUCTURALS—Channels, angles, beams, etc.

PLATES—Many types including Inland 4-Way Safety Plate

SHEETS—Hot and cold rolled, many types and coatings

TUBING—Seamless and welded, mechanical and boiler tubes

ALLOYS—Hot rolled, cold finished, heat treated. Also tool steel

STAINLESS — Allegheny bars, plates, sheets, tubes, etc.

MACHINERY & TOOLS—For metal fabrication

RYERSON STEEL

JOSEPH T. RYERSON & SON, INC. PLANTS AT: NEW YORK . BOSTON . PHILADELPHIA . CINCINNATI . CLEVELAND . DETROI PITTSBURGH . BUFFALO . CHICAGO . MILWAUKEE . ST. LOUIS . LOS ANGELES . SAN FRANCISCO . SPOKANE . SEATTL



THE IRON AGE Newsfront

- ALUMINUM WINDOW SECTIONS WILL BE PRESSURE WELDED with a new machine now being designed. Pressures of about 20,000 psi will be used and welding requires no heat.
- A V-6 ENGINE FOR 1954 CARS IN THE LOW PRICE FIELD is being seriously considered by one major producer. While final decision has not been reached, the big inducement—economy of operation—will have a lot of weight.
- COAL'S FUTURE SHOWS STRONG SIGNS OF GROWTH even though it can't match recent spectacular increases in natural gas and oil. Manufacture of coke and electric power together account for about 46 pct of all coal consumption. The former use has increased 39 pct since 1940, the latter has doubled. Hydrogenation and liquid fuels are two bright spots.
- SHELL MOLDED REFRACTORIES HAVE BEEN TESTED as a mold material for titanium castings. A 4 pct resin mixed with either stabilized or fused zirconia gave best surface finish. Mold contamination is confined to extreme outer edge of cast section.
- SUBCONTRACTORS WILL GET LONG RUN ORDERS IF Defense Dept. has anything to say about it. Right now government officials say many prime contractors with 2-yr orders on books are subcontracting on a quarterly basis. Some primes say frequent change in specs make this more realistic method. Defense officials admit specs sometimes change twice a quarter.
- STEEL CAPACITY OF 138 MILLION TONS BY 1960 is predicted by an industry economist. Projections for 1960: Population, 171 million; employed, 68 million; national income, \$318 billion; disposable income, \$265 billion; gross national product, \$375 billion. He believes population growth, defense spending, higher national income will support this capacity.
- CRANKSHAFT MACHINING MAY SOON BE COMPLETELY AUTOMATED. It's one of the few auto industry jobs not yet on a full mechanical handling basis. An industry engine plant is installing new equipment for a completely automatic crankshaft line.
- ELECTRIC POWER FROM ATOMIC ENERGY IS NOT JUST AROUND THE CORNER. It's still a long way down the road. Biggest users of electric power now are the A-plants themselves. A \$1.2 billion A-plant recently announced will have power stations with capacity 25 pct greater than requirements for New York City.
- CHEMICAL DETECTION METHODS CAN'T KEEP UP WITH AEC demands for purity.

 That puts a premium on new methods, spectrographic research.

 Hanford works recently called for carbon with impurity of no more than 1/100th of one part per billion.
- STEEL ROLLING MILL SPEEDS OF 9000 fpm are getting plenty of attention from mill designers who want to increase productivity. But some present mills designed for 6000 fpm are only run at 4800 rpm. Big headaches are chatter, lubrication waves, tears and maintaining roll contact.

RO



in Stainless

Brilliance is often honored with special degrees and other ribbon tied, hand lettered salutations. But this B.A. stands for Bright Annealed and to many stainless fabricators it is as important as money in the bank. You see, CMP Bright Annealed Stainless Cold Rolled Strip beat a costly problem by providing a mirror-like finish on chromenickel grades, even in dead soft temper. And that is a big money saver because it can practically eliminate or substantially reduce expensive polishing and finishing.

To find out how Thinsteel Bright Annealed Stainless Strip can improve your production or lower end-product costs write or phone us today. We'll be glad to arrange a sample order for your own comparative test. With labor costs up, a potential saving in your finishing costs is more important than ever before, and worthy of your investigation NOW.



the Cold Metal Products co.

YOUNGSTOWN I. OHIO

New York • Chicago • Indianapolis • Detroit • St. Louis • Los Angeles • Cleveland

LOW CARBON, HIGH CARBON (Annealed or Tempered) STAINLESS AND ALLOY GRADES, ELECTRO ZINC COATED ARE AVAILABLE FROM:

THE COLD METAL PRODUCTS CO. of CALIFORNIA, 6600 McKinley Avenue, Los Angeles Phone: PLeasant 3-1291

THE KENILWORTH STEEL CO., 750 Boulevard, Kenilworth, New Jersey Phones: N. Y., COrtlandt 7-2427; N. J., UNionville 2-6900

PRECISION STEEL WAREHOUSE, INC., 4425 W. Kinzie, Chicago • Phone: COlumbus 1-2700

f

at

th

th

tu

31

19

on

ma pla

du rea "at

00



VIDEO: Producers Tune In on Brisk Demand

Improved consumer demand and hope for new markets opening up starts TV industry pushing for output . . . Inventories show sheer reduction . . . Are prices going up?—By T. Metaxas

There's not a smear of pessimism marring the clarity of the television industry's production picture these days. Jammed-up inventories in factory and distributor warehouses that backed up to short circuit production have shrunk to lean levels. And improving consumer demand is getting good reception from manufacturers who are pushing production to the hilt.

The end of this third quarter saw a total of 3.7 million TV units made—despite the steel strike's curbing some operations. The fourth quarter will see another 1.5 million sets produced to bring 1952's total to between 5.3 and 5.5 million—or roughly comparable to the 5.4 million sets made last year.

Wears Off—In 1951, production figures were kept respectable but at the expense of overloading inventory. This has been rapidly shed this year as sales improved. Factory inventory for the week ending Sept. 26 was 172,631 sets. Stack this up against the 715,313 units crammed in factory warehouses in August, 1951.

Because of inventory manufacturers cut back August '51 output to a wan 146,705 units. Manufacturing tempo this August ran at 319,769 units and the industry was just warming up. For a 5-week estimated September period production may climb to 719,000 sets.

The industry is confident that 1953 production will rise higher on the granite base of many new market areas opening up and replacement sales quickening. Production next year is expected to reach 6 million sets. Some add an "at least" to this figure and modify


it with "defense requirements permitting." But generally, manufacturers see an improving materials supply.

One major TV producer plans to make 50 pct more sets in this quarter than in the same period last year. Next year this firm plans to produce 80 pct more sets than this year. Other companies are rising to the same great market expectations. Admiral Corp. states its sales are running 20 pct higher than in the same '51 period. Westinghouse claims output

is running 35 pct over the comparable 8 months last year.

Industry Peppy—Some firms say they must hunt for enough materials to keep this production momentum going. One company reported it could use more alloy steel kinescopes on which the glass face of the picture tube is bonded. It is experimenting on use of cold-rolled steel instead of alloy. However, sufficient materials are flowing to the industry to keep it peppy and permit ambitious plans.

Most TV makers would like to fan their freshening market. It will be with reluctance that they raise prices in months to come. But the story is the same one



heard in many industries: Higher costs of metals, materials, freight, and labor must force prices up even in competitive markets.

So far most producers have held a firm rein on prices. A few have raised price tags on some models, usually the more expensive sets. Though the price hike is seen inevitable, this industry has, from the perspective of crowding more value into their product, been actually lowering prices. Big screen sets with new electronic improvements are selling at prices equivalent to those paid for early midget-screen video.

New Stations—Much of the industry's sales optimism for next year is founded on Federal Communications Commission's licensing new stations following lifting of its freeze. Thousands of applications, many conflicting, are on the FCC docket. The Ultra High Frequency stations will supplement already allocated Very High Frequency stations. When a station is opened in a virgin area it means a new TV market. When one joins a sole station in an area, market potential is invigorated.


A buying rush greets opening up of a new video area, Company records show dealers hasten to stock up on sets weeks before a new station hits the airwaves. It has been shown that an area with a single station may have sluggish buying interest. When another station moves in, sales jump.

Before 1952 is out, 15 new stations should be operating. Assuming that FCC accelerates its approval rate, 1953 should see this number multiply several times.

Replacement—TV manufacturers lay important stress on the replacement market. It's estimated that 50 pct of TV owners have screens less than 16 in. Millions of sets owned are 4 or more years old. There's no doubt that a strong replacement market is showing up already.

The industry is broadening already established or "saturated" areas by heightening the reception power of its sets. General Electric claims its current models are 267 pct more sensitive than previous ones. Thus the limits of a TV area are pushed outwards. Need for monstrous and expensive antennas is eliminated.

Retailers in many of these "saturated" areas (in larger cities where stations appeared almost overnight years ago) are growling about sales. The boom passed and they have settled down to a



staid market. Because of TV's comparative recency no great backlog of very old sets has yet formed to provide a vital replacement market.

New York City, one of the first and heaviest video areas, was sampled for retailer sales sentiment. Most stores said a traditional seasonal uplift was helping business but the area was still giving discounts off list price to move sets. One distributor said that retailers were generally sour on the market, sometimes unjustifiably so, and were offering up to 25 pct discount, depending on the model. There was also some tightness in availability of some popular models.

Larger Screens — Trade-in allowances on old sets were described as overly generous and selling them as reconditioned would not balance out the deficit. Replacement business was a factor here but not a substantial one. One of the large chain appliance stores told IRON AGE sales this year would edge out last year's but that dollar volume would probably be slightly less be-

cause of trade-ins and discounts.

SI

ge

19

tri

ma

ha

ste

egt

Ele

of

ma

mil

1.3

for

til

shi

mei

195

dur

how

ster

of s

stea

abo

sch

wer

that

stril

men

fron

ing

equi

the

felt

1953

wate

tran

expe

ent :

1953

strik

tran

for

tors

of c

while

tion,

up t

repor

Octo

Go

Es

B

L

I

Manufacturers and retailers report customer preference has steadily been focused on larger and larger screens. The 21-in. screen set has climbed in popularity and is threatening to unseat the 17 incher. Retailers say customers first walk to the ranks of 21-in. sets but that pocketbooks frequently march them over to the 17-in. screens. More 17-in. sets are being sold but the sales trend points to larger screens.

More production difficulties are imposed on manufacturers because of the popularity of the 21-in. sets. They have more parts, take more assembly line time.

Color Coming—The great blurb of publicity accorded advent of color television actually slowed both replacement and new sales as customers shied away on the assumption any set now on the market would be made obsolete. These apprehensions are wearing away. The industry feels that color TV may start at a piddling level in 1954 or 1955. But real commercial development will take years.

Color sets now need up to 50 tubes as against the average 20 used in black and white. Color video will be more expensive and advertisers won't back the movement in mass for some time.

When color does finally arrive the industry feels it will be an electronic system rather than the mechanical one offered by CBS.

Loaded for Bear—Most intensive research of the industry is trained on UHF developments. Manufacturers are loaded for bear and are ready to capture new UHF markets as they spring up.

The industry feels it should not have to strain too hard to meet growing demand. A few fears were expressed that while assembly line producing receivers could stand any fast gait, a hindrance to quick market development may be handling orders for station broadcasting equipment.

38

STRIKE LOSS:

More than 2 million kw generating capacity scheduled, lost for '52.

About 2.5 million kw of new generating capacity scheduled for 1952 will not materialize. The electric power industry was having materials troubles before the steel strike and the prolonged stoppage has aggravated its difficulties.

Taking stock of the effects of the steel strike on electric power equipment and expansion, the Electric Power Survey Committee of Edison Electric Institute estimates that in addition to the 2.5 million kw lost this year, another 1.3 million kw expansion slated for 1953 will not be completed until 1954.

Despite this gloomy outlook, shipments of heavy power equipment during the first 7 months of 1952 approach the total shipped during all of 1951. This indicates how much manufacturers have stepped up their operations in spite of shortages.


Losses Vary — Manufacture of steam turbine-generators during the first 7 months of the year was about 10 pct less than originally scheduled. Most of these delays were caused by materials problems that developed before the steel strike. For other equipment, shipments have fallen off 20 to 35 pct from scheduled rate.

Because of the long manufacturing cycle, delays in production of equipment resulting directly from the steel strike will not be fully felt until late 1952 and all through 1953. Steam turbine-generator, water-wheel generator, boiler and transformer manufacturers still expect to meet most of their present schedules for 1952.

Estimates of shipment losses for 1953 resulting from the steel strike run from zero in the case of transformers up to 15 or 20 pct for large steam turbine-generators and boilers.

Government has been informed of critical boiler situation and, while it acknowledges the condition, has done nothing to speed up the flow of needed materials, reports EEI.

Catalysts Recover Heat From Wastes



CATALYSTS: Cross-section shows alumina and platinum coated porcelain rods in Houdry unit.

Savings to industry of hundreds of millions each year through converted wastes are forecast on the basis of experiments with Eugene F. Houdry's waste burning catalyst at Sun Oil Co.'s Marcus Hook, Pa., refinery.


The catalysts, made by Mr. Houdry's Oxy-Catalyst, Inc., received wide mention when installed at Enamelstrip Corp.'s Allen-

town, Pa., plant earlier this year (The Iron Age, June 26, 1952, p. 61.) Sun Oil has made a partial installation on one petroleum-cracking unit at Marcus Hook, and reports savings of \$27,500 per year. This will jump to over \$80,000 when the installation is completed.

Further applications at Sun's Marcus Hook and Toledo refineries should save the company an estimated \$500,000 annually.

Waste carbon monoxide and hydrocarbons are burned in the platinum-alumina catalyst as they escape from petroleum-cracking reactors. Most of the heat generated (80 pct) is carried off by molten salt in pick-up tubes to make steam. Balance is used to boost heat of flue gas driving a gas turbine. Sun expects to triple the heat saving of 7.5 million Btu per hr when a second reactor on the cracking unit is equipped with catalysts.

Cost of the Sun installation was limited virtually to the cost of the catalyst itself—\$25,000, because the company was able to adapt previously built plant and equipment. More representative is a unit planned for another large eastern refinery. Total cost would be \$107,000, with an estimated annual saving of 20.6 million Btu per hr—equivalent to \$120,000 worth of steam each year.




SALVAGE: Houdry units create 7.5 million Btu per hr on this Sun Oil Co. reactor.

PRESTRESSING: Will Bars Boost Use?


Newly-formed firm marketing special tensioning bars to replace wire in prestressed concrete . . . Cuts labor time, costs . . . Competitive with reinforced concrete—By G. G. Carr.

Construction engineers used to just look wistful when prestressed concrete was mentioned. Tensioning steel reinforcements to give concrete greater permanent compression than the tensile stresses it will carry under load solves a lot of problems. It's been widely coldworked alloy steel bar, plus a new anchorage device, in place of wire. It is now being marketed here by the recently formed Stressteel Corp.

Anchorage units consist of a long-tapered thread engaged with a nut of matching thread. This



IN USE: Above, components of a Stressteel tensioning unit. Below, jack has elongated bar, and anchor nut is ready to be run home.



used in materials-short Europe. But labor costs here put it out of reach for most contractors.

Post-Korea structural steel shortages brought new interest in the technique, in spite of the expense. (THE IRON AGE, Apr. 24, 1952, p. 91.) But it still took 130 to 150 manhr per ton to install and tension the cables. And high quality wire is expensive, too.

New Way — A new method, known as the Lee-McCall system, could change this picture radically. Developed in England, the system calls for use of a special develops 100 pct of the ultimate bar strength. Nut bears against a steel plate which distributes terminal forces at a safe unit loading at the ends of the prestressed member.

First application in the U. S. was made by the Preload Corp. in 1951 on the 17,422-ft trestle sections of the Pinellas-Manatee Crossing over Tampa Bay. Preload found it the only way to make prestressed design competitive with reinforced concrete on this job. The company told THE IRON AGE it is now using the system successfully in other designs.

Easier—Placing, stressing and anchoring of prestressing wire is necessarily a complex, lengthy and costly process. One bar can do the work of several high tensile wires. Stressteel claims that a bar 11/8 in. in diam does the work of 22 wires each of 0.196 in. diam.

Prestressing bars need no special handling. Similar in size and shape to reinforcing bars, they are familiar to construction workers. All the worker has to do is place them in the form.

th

ex

ha

fir

cos

ha

tur

uci

ha

kn

pla

clin

of

wh

wh

har

day

tion

rou

help

trav

tow

forl

mu

thei

spa

sma

be r

fall

The

trac

lift

tile.

DOW

that

lift

tails

abou

price

mod

ing

of th

Oct

F

N

Stressteel says its bars may be placed, stressed and anchored with only 25 to 45 manhr per ton, against 130-150 manhr per ton for wire. The company claims that labor savings alone will exceed the cost of the bars on many jobs.

Cheaper—Bars run 18¢ to 23¢ per lb, depending on length. On the Tampa Bay bridge job winning bid was \$140,000 lower than the low bid for reinforced concrete. Estimates for prestressing with wire ran \$225,000 more than bar prestressing.

Following the successful Tampa Bay application, a group of Canadian and American businessmen formed Stressteel Corp. to produce and sell the tensioning units in this country. Units are presently being imported from England, but negotiations for a plant in Pennsylvania are almost complete.

Manufacturing will consist of coldworking 92-60 bars, alternately stressing and relieving the steel to reach a minimum ultimate stress of 145,000 psi. Details of the process are so far confidential. Bethlehem will be a chief supplier, but U. S. Steel is also reported as interested.

Specifications — Physical properties of the prestressing bar, in addition to the minimum ultimate stress, are:

Minimum stress at 0.7 pct elongation: 130,000 psi Minimum stress at 0.3 pct elongation: 75,000 psi Elongation in 10 in.:

For 145,000 psi ultimate stress...... 6½ pct
For 155,000 psi ultimate stress..... 5½ pct
Modulus of elasticity........25-27 million psi

EQUIPMENT: How to Move Materials

Materials handling is open field for producers seeking way to cut costs... Must adapt equipment to plant, process... Facts on fork trucks, tractor, crane—By K. W. Bennett.

The more times a product and its components are handled the higher the costs of manufacturing. That explains the interest in materials handling equipment and why more firms are exploring this field as a cost-cutting means.

To successfully adapt materials handling equipment the manufacturer must know his plant, his product, and his process. The materials handling sales engineer will want to know physical dimensions of the plant, elevator capacity, ramp inclines, loading area capacity, etc.

Type of Load—That's just part of the job. He must also be told what type of load is carried and by what method; the number of units handled per load transfer and per day; the weight per load transfer and per day; the number of locations to be visited; distances and routes, etc.

i-

n

S

9-

1 -

nt

11-

of

ne

te

of

al.

er,

as

m-

ill

ate

pi

psi

pct n pri

GE

Several rules of thumb may prove helpful to buyers. A lift truck is good for about 200 to 300 ft of travel. Beyond that a tractor or a tow truck may be more feasible. A fork truck, having a load lift of as much at 17 ft, may be better if there is plenty of vertical storage space. For cramped loading areas small hand trucks and stackers may be most suitable.

Materials handling equipment falls roughly into three classes: The lift truck, the tow truck or tractor, and the light crane.

Fork Trucks — The hydraulic lift trucks, or fork trucks are versatile, speedy, and powerful. A handpowered hydraulic lift is available that has a capacity of 750 lb. It will lift this load 52 in. The unit retails at around \$236.50, which is about the bottom of the lift truck price range. There are several models of this type available, ranging up to a 1000 lb capacity fork of the "walker" type with an 80 in.

lift, battery powered, selling for \$687.50

Another builder lists forks with up to 7500 lb lifting capacity and these will lift their load to 140 in. Lighter models offer 3000 lb capacity with a lift of 146 in. They are



LOADING: Fork truck with special rig stacks auto frames on freight car.

available in both gasoline and diesel powered models.

They range from 4950 to 9635 lb in weight. One walker model offers capacities to 3000 lbs, will lift to a 130 in. height. Yet even in the heavy-duty sizes the units have a body length of only 65 in. The fork adds another 34 in. On a level stretch, some fork trucks will move at speeds up to 23 mph.

The gap between the 1000 lb and 3000 lb capacity in the previously listed fork trucks is filled by a line offering fork trucks with lifting capacities from 2000 lb to 16,000 lb, with lifting heights ranging from 9 ft to 17.5 ft, and speeds of from 9 to 23 mph.

Accessories make the fork truck the most versatile member of the materials handling team. Available are scoops, clamps, rams, fork extensions, load safety racks, side shifters, brick and concrete forks, clam shells. They pick up anything from bundles to foundry sand.

Mobile Crane—A blood relative of the original fork-truck-with-crane - attachment is the mobile crane. The cranes are not large. One model offers 10,000 lb capacity, has an electric motor. Another crane has a possible boom elevation of 19 ft, is gasoline powered and has four forward and four reverse speeds. It has a load lifting capacity of 10,000 lb.


The boom is locked in one of five positions before the hoist is begun. This unit weighs 11,400 lb, and has a 152 in. turning radius. These are widely adaptable but have proved most successful in loading or unloading gondolas, flat cars, etc.

Tractor—The third member of the materials handling team is the tow truck or tractor. Some small plants have rigged their fork trucks as tractors with the addition of a trailer hitch, but the fork lift is not designed for such a job and might be wasting its versatility if a portion of its time is used in long, straight hauls.

Straight pulls of 200 ft or more are the province of the tow truck, material handling specialists have indicated.

Hand Lift Trucks—The hand lift trucks, next on the scale, run from around \$420 to \$1790. They have load capacities of 4000 to 6000 lb. Where material is bulky but light, and floors smooth enough, the operator can link together several of these hand trucks to form a train. The hand lift trucks are also available with a fork for use with standard pallets.

The tow truck, like the fork lift, is offered in number of powered walkers, with the operator walking in front or behind, steering with a "T" handle. One variation, available in walker models or a conventional tow truck, has a removable, packaged power plant. Diesel, electric, or gasoline powered tow trucks are offered with tow capacities of 700 to 20,000 lb at speeds of 2.5 to 15 mph.



JHE experience of many blue chip manufacturers have shown that there are three important profit sources in every American installation: (1) American-reduced chips bring \$4 more per ton on scrap market (2) Up to 50 gallons of recovered cutting oil per ton of reduced turnings (3) less storage easier handling.

Let American show you how you can turn your

scrap into profit.

WRITE for Bulletin: "Metal Turnings Crusher."



1439 MACKLIND AVE., ST. LOUIS 10, MO.

Expansion-

Brass Plant for West Coast

The West Coast now has another brass and bronze ingot smelting plant. It was opened this week by H. Kramer & Co., Chicago, at 631 S. Aviation Blvd., El Segundo, Calif. Of course, the plant has the latest equipment to prevent smogin conformance to strict local reg-

The plant is located on a 23-acre site, containing production facilities, laboratory, and offices. Included in the equipment are two 66-ton reverberatory, two rotary type, and a number of tilting furnaces, a cupola, and a radiator sweater.

B

ha

WE

in

SD:

be

fiel

lin

tio

rue

ing

mo

line

der

nov

fro

upp Oc.

An innovation for a plant of this type is a quantometer, self-reading spectrograph. Smog equipment consists of a dust collector to gather up zinc oxide and other waste particles.

Contract for Titanium Research

The Air Force has awarded a contract to Ryan Aeronautical Co., San Diego, for research and development of titanium. Work for the Air Force is to determine the best means of processing titanium for use in conjunction with exhaust

Niagara River Blast Furnace

Niagara River Steel Corp. has been granted a certificate of necessity permitting accelerated amortization on 85 pct of a \$40.3 million pig iron-coke plant in the Buffalo area.

This is the second largest certificate approved by Defense Production Administration in its latest listing.

Approval covers one complete blast furnace, a battery of 55 coke ovens, and by-product facilities

Location is between the Niagara River and Erie Canal near Buffalo.

Directors of the firm include A. F. Freez of Colorado Fuel & Iron Corp.; George Carvlin, a vice-president of Koppers Co., Inc.; Wiley Moor, Sr., of U. S. Oil. Pure Oil. and Eastern Airlines; and Louis M. Lean, a Philadelphia banker.

BARGES: Shipment Curve Goes Up

Inland waterway cargoes increase steadily since 1930 . . . Demand for space rises . . . But petroleum shipments decline . . . Operators try for more efficiency—By K. W. Bennett.

What barge men have called the Big Load" was getting bigger. Barge traffic on the Mississippi had climbed 8 pct in 1951 over the figure for the previous year. In 1952, the Tennessee moved into pace-setting position, with an announced 50 pct increase in water shipments over the previous year.

The figures seemed good. They sustained the rising curve in water shipping rates that can be traced at least as far as 1930. But beneath the curve, other movements were beginning to take shape in inland waterways planning.

Distrust—Contract carriers were watching petroleum, once a mainstay in Mississippi River shipping, with something more than distrust. In a period when most commodities, both bulk and packaged, were calling for more shipping space, oil carriers were lowering rates, paying upkeep on additional idle barges. A few barge owners were calling the petroleum fall-off a definite trend and one that could be expected to continue.

Their reasons: Opening of oil fields closer to the ultimate user, as in Montana and Dakota, pipeline expansion, too much competition.

Similarly, barge owners were ruefully studying rising costs and reinspecting their equipment, moving toward semi-integrated tows, more powerful engines, triplescrew power boats, more streamlined barge shapes.

Efficiency—Two moves are underway to increase barge efficiency. The old overhang is being eliminated on many barges now on the ways. Thus the sheer of the bow and stern will extend from the bottom of the barge to the top, eliminating the bow-wave that would pile up before the bluff upper portion of the barge as it

was pushed up-river against rough water.

Second move for more efficient utilization of power is the semiintegrated tow. Two barges are sheared off, made straight at one end. These are then pushed together to form one long "barge" of two separate, watertight sections.

One barge operator estimated the actual increase in towing efficiency at about 20 pct.

And barge operators, with increasing demands for shipping space are beginning to check their terminal facilities. In the South, docks seem good. Along the Ohio and to the East, facilities are adequate or better. Chicago is however, a particularly sore spot,

with only three major barge terminals for public use.

Integrated Tows — The Federal Government, through federal barge lines, has been seeking to offer rapid service to smaller shippers, people who would ship less than carload lots. Their best known tow for this purpose is the Harry S. Truman, Chicago to New Orleans, a fully integrated barge tow that leaves Chicago every Tuesday and arrives in New Orleans 1 week later.

The fully integrated tow consists of 11 barges, aggregating 1200 ft in length. It moves swiftly, allows for a variety of small cargoes. Private barge operators are not sanguine over the future of the fully integrated tow, however. They feel it is expensive to operate, difficult to manage economically. It will be a considerable time before the integrated tow is adapted

STEEL: Finished Shipments Totals in July

As reported to the American Iron And Steel Institute
CURRENT MONTH
TO DATE THIS YEAR

STEEL					Pct of Total			S		Pct of Total
PRODUCTS	Carbon	Allov	Stain- less	Total	Ship- ments	Carbon	Allov	Stain-	Total	Ship- ments
Ingots	44,801	8,145	458	53,404	3.8	361,624	144,107	10,790	516,521	1.5
Blooms, slabs, billets		0,110		00,101	0.0	40.1100.	,	,		
tube rounds, sheet										
hars, etc.	56,916	9 349	523	66,788	4.7	848,019	267,810	9,664	1,125,493	3.3
Skelp	46			46		53,388			53,388	0.2
Wire rods	12,893	78		12,971	0.9	350,563	7.567	3,188	361,318	1.1
Structural shapes	28,403	372		28,775	2.0	2,045,220	29,679	37	2,074,338	8.0
Steel piling	962			962	0.1	112,964			112,964	0.3
Plates	99,851	5,710	1.189	106,750	7.5	3,515,179	184,350	14,110	3,713,639	10.8
Fails-standard	1,935			1,935	0.1	669,068	130		669,198	1.9
Fails all other	1.421			1,421	0.1	61,797	48		61.845	0.2
Joint bars	422			422		56,773			58,773	0.2
Tie plates	789			789	0.1	187,956			187,958	0.6
Track spikes				346	0.1	47.906			47,906	0.1
Wheels	12,213	131		12,344	0.9	184,590	352		184,942	0.5
Axies	1.042	131		1.042	0.1	83.069	152		83,221	0.2
Bars - het rolled	94.031	35.047	1,235	130,313	9.2	3,025,252	991,692	24,371	4.041.315	11.8
Bars-reinforcing	35,486	33,041	1.230	35,486	2.5	883,319	931,032	24,311	883,319	2.6
Bars-celd finished	35,242	9,311	1,470	46,023	3.3	804.053	172,351	25,859	1.002.263	2.9
Tool steel		4,868		5,533	0.4	12,246	60,238		72,484	0.2
6 1 - 1		4,000	4	27.667	2.0	1.207.479	208	7	1,207,694	3.5
		1 000	1						800,188	2.3
Oil country goods		1,668		31,300	2.2	731.030	69,158			
Line pipe				55,369	3.9	1,549,860	119		1,549,979	4.5
Mechanical tubing		9,026	255	27,911	2.0	341,395	149,379	3,649	494,423	1.4
Pressure tubing		586	168	10,125	0.7	187,704	20,048	5,704	213,456	0.6
Wire-drawn	64,427	1,318	520	66,265	4.7	1,288,183	28,003	15,561	1,331,747	3.9
Wire-nails, staples				11,681	0.8	349,061		20	349,081	1.0
Wire-barbed, twisted.	4,053			4,053	0.3	124,476			124,476	0.4
Wire-weven fence				12,197	0.9	193,585			193,585	0.6
Wire-bale ties				998	0.1	44,069			44,069	0.1
Blackplate	17,212			17,212	1.2	485,882			485,882	1.4
Tin & terneplate-										
het dipped	39,464			39,464	2.8	651,661			651,661	1.9
Tinplate-electrolytic	85,112			85,112	6.0	1,444,453			1,444,453	4.2
Sheets-het rolled	122,291	4,005	994	127,290	9.0	2,959,150	108.820	14,378	3,082,348	9.0
Sheets celd rolled	207,533	2,290	2,688	212,509	15.0	3,818,406	40,461	54,701	3,913,568	11.4
Sheets-galvanized	56,254			56,254	4.0	959,353	40		959,393	2.8
Sheets-other coated	8,640			8,640	0.6	111,136			111,136	0.3
Sheets-enameling	1,110			1,110	0.1	75,761			75,761	0.2
Electrical sheets, strip.	1.025	17,893		18,918	1.3	41,102	268,114		309,216	0.9
Strip hot rolled	35,074	168	1	35,243	2.5	876,639	14.953	2.089	893,681	2.6
Strip—cold rolled	52,148	1,151	5,705	59,004	4.2	818,473	10,672	68,474	897,619	2.6
TOTAL	1,287,351	111,116	15,205	1,413,672	100.0	31,561,844	2,567,851	252,602	34,382,297	100.0

During 1951 the companies included above represented 96.5 pct of the total output of finished rolled steel products as reported to the American Iren and Steel Institute.

BOMBINGS: Plants Were Still There

German industry's survival under World War II bombings no assurance in A-bomb era . . . Air raids on German plants were only 2.5 pct effective . . . Damage claims overrated.

Charred remnants of the Hiroshima and Nagasaki bombings merely suggest the destructive impact of atomic war. The A-bomb's potential makes the blockbuster obsolete.

Little consolation can be gained from the fact that mass bombings of the last war were ineffective in knocking out industry. Despite the much-publicized 1000 plane raids, survey of German industrial centers after the war proves industry can withstand this type of attack. When the Allies took over in 1945, German iron, steel and coal industries were still physically capable of operating at 92 pct of capacity.

Damage Overrated-A top gov-

ernment official told THE IRON AGE that Allied bombings of German industry were only 2.5 pct effective. Damage claims were vastly overrated. For example, when Air Force photographs showed a steel mill with its roof blown off, the plant was scratched as being completely destroyed. Investigation after the war showed that in most of these plants, machinery and furnaces were virtually unscathed.

These reports should not give U. S. industry a false sense of security, however. Only 20 atom bombs would be needed to equal the explosive force of all the bombs rained on Germany throughout World War II.

Instances of industry's ability to survive strategic bombings durthe last war are numerous. Frankfurt was leveled by Allied attacks. Yet in the nearby suburb of Hoeschst, a large chemical plant was untouched. Amid the ruins of Essen, the gigantic Krupp war plants, so vital to Germany, were hardly damaged.

Plants Survived - When the Russians marched into Leuna, they found a plant covering nearly 11 million sq ft completely intact and still capable of continued production of synthetic gasoline, rubber and explosives. The French found the giant Mauser armament plant unharmed, it is authoritatively reported.

Particularly invulnerable to air attacks was the steel industry. The Ruhr section alone was the bull's-eye of 271 raids by a total of 97,000 bombers, carrying 287,-000 tons of explosives. Result: Five openhearth and bessemer furnaces and nine strip mills were destroyed. Of many blast furnances in the area, only two of them were put out of operation, IRON AGE's European correspondent reports.

to

di

di

DI

m

th

al

20

yo

ag

fir

Ne

Po

20

ch ar

pla

fre

pla

be

is

int

12

0

Many other plants were similarly unharmed by mass bombings. Reports indicate Huettenwerke Haspe plant in West Germany suffered only 9 pct damage. Deutche Edelstahlwerks, one of Germany's leading steel alloy producers, had only 11 pct of its plant knocked out. Huettenwerk Geisweid, manufacturers of cast and armor steel, lost 4 pct of its capacity. Hoesch Dortmund, gun makers, suffered damage to 7 pct of its plant; Ruhrstahl Hattingen. 3 pct Gutehoffnugshuette Oberhausen, chain and tank producers, 3 pct, and August Thyssen A. G., 9 pct.

Production Rose - Allied destruction of Germany's ball bearing plants created many headlines. But German tank production in 1944 rose 4 pct above the level of the previous year. Aircraft output was upped 6 pct.

In August, 1944, one of the heaviest bombing months of the

STEEL: Post-Strike Output Rises

As Reported to the American Iron & Steel Institute

	Openha	arth	Bessen	ner	Electr	ric	Tota	I	Ontordated	No.
	Net	Pet	Net	Pct	Net	Pct	Net	Pct	Calculated Net Tons	weeks
1951	Tons	Cap.	Tons	Can.	Tons	Cap.	Tona	Cap.	Weekly	Month
January	7.846.657	101.4	431,725	90.4	570.084	88.8	8,848,466	99.9	1,997,396	4.43
February		99.3	362,112	75.6	507.302	87.5	7.770.407	97.2	1.942.602	4.00
March		104.2	408,926	85.6	606,358	94.5	9.076.630	102.5	2.048.901	4.43
1st Quarter		101.7	1.186,763	84.2	1,683,744	90.4	25,695,503	100.0	1.998.095	12.86
April	7 859 828	104.9	392,472	84.9	584.668	95.7	8.845.979	103.1	2.062.000	4.29
		104.4	408.650	85.6	618,511	96.4	9.100,155	102.8	2.054.211	4.43
May										
June		102.4	403,001	87.1	589,898	94.9	9,662,348	101.0	2,019,195	4.29
2nd Quarter		103.9	1,204,123	85.9	1,803,077	95.7	26,608,482	102.3	2,045,233	13.01
1st 6 months .		102.8	2,370,886	85.0	3,486,821	93.0	52,303,985	101.1	2,021,801	25.87
July	7,706,078	99.8	411,599	86.4	566,818	88.5	8,684,495	98.3	1,964,818	4.42
August	7,894,965	89.5	436,822	91.5	607,308	94.6	8,739,095	98.7	1,972,708	4.43
September		102.4	404,726	87.7	601.830	97.0	8,660,357	101.2	2,023,448	4.28
3rd Quarter	23,054,844	100.5	1,253,147	88.5	1.775.958	93.4	26.083.947	99.4	1.986.592	13.13
9 months	69.501.122	102.0	3,624,033	88.2	5,262,777	93.1	78.387,932	100.5	2,009,947	39.00
October		103.8	458,128	95.9	635.037	98.9	9,121,886	103.0	2.059.118	4.43
Nevember		103.5	411.954	89.1	636,553	102.4	8.799.352	102.6	2.051.131	4.29
December		102.2	396,831	83.3	608.017	94.9	8.890.678	100.6	2.011.486	4.42
4th Quarter	23,665,396	103.1	1,266,913	89.4	1,879,607	98.7	26,811,916	102.1	2,040,481	13.14
2nd 6 months.		101.8	2.520.060	89.0	3,655,563	96.0	52,895,863	100.7	2.013.546	26.27
		102.3	4,890,946	87.0	7,142,384	94.5	105,199,848	100.9	2.017.642	52.14
1952										
January		100.7	407,298	89.3	625,696	89.7	9,136,117	99.3	2,062,329	4.43
February		102.4	382,712	89.8	571,432	87.6	8.657.210	100.7	2.091,114	4.14
March	8,401,140	104.4	378,861	83.1	624,190	89.5	9,404,191	102.2	2,122,842	4.43
1st Quarter	24,207,329	102.5	1,168,871	87.4	1,821,318	89.0	27, 197, 518	100.7	2,092,117	13.00
April	7,101,199	91.1	323.006	73.2	566.937	83.9	7,991,142	89.7	1.862.737	4.29
May		90.6	318.642	89.9	594.089	85.2	8,204,598	89.2	1.852.053	4.43
June		18.6	22,862	5.2	169,702	25.1	1.639.491	18.4	382,166	4.29
2nd Quarter		67.0	664.510	49.6	1,330,728	65.0	17.835.229	66.0	1,370,888	13.01
1st 6 months	40.047.320	84.8	1.833.381	68.5	3,152,046	77.0	45.032.747	83.4	1.731.363	26.01
July		16.8	2,000	0.4	277.371	39.8	1.626,958	17.7	368,090	4.42
August ¹		94.4	309.361	67.8	589,438	84.5	8,498,687	92.4	1.918.440	4.43
September ²	8.011.000	103.0	352,000	79.9	671,000	99.6	9.034.000	101.6	2.111.000	4.28
3rd Quarter ²		71.1	663.361	49.1	1.537.809	74.4	19,159,645	70.3	1,459,227	13.13
9 months ²	57.005.795	80.2	2,496,742	62.0	4,689,855	76.1	84,192,392	79.0	1,640,071	39.14
Note Percentag										
net tons besseme	er and 144,89	net ton	s electric ingo	ts and s	teel for castin	gs, total	1,999,034 net	tons;	based on ann	uai ca-
pacities as of Jar	1. 1, 1951 as	follows:	Openhearth	91,054,0	020 net tons,	besseme	er 5,621,000 ne	t tons, e	electric 7,554,	630 net
tons, total 104,22										
102,926 net tons										
annual capacities										
net tons, total 10			open		.,,				,	
1 Revised.			ures, subject	to revie	inn					

war, German steel production hit 2.087 million tons compared with 1,901,260 tons in August, 1939.

It was not until after the fall of 1944 that German war production began to buckle. This was the period when the Allies, after establishing air bases in France, shifted from mass, strategical night bombing of industrial centers to sneak fighter-bomber attacks. In this second phase of the air war, transportation and communication lines were the main targets and destruction from the air was deadly.

Shift Targets—With Mustangs, Lightnings, Spitfires, and Tempests hedgehopping from France to destroy railroad stations, highways and canal locks, the massive German war machine creaked to a standstill. Iron, coal, steel and armament output withered when supply lines were smashed. As a result, German war production during the first 2 months of 1945 dropped off almost 55 pct from the previous year.

e

st

e

y

18

k

st

ts

n

et

n.

r-

S.

6-

ıg

20

in

of

it

he

he

The surprising ability of German industry to survive repeated mass bombings is largely due to the bomb resistant construction of the plants, which stood up under all but direct hits. In one case a 2000-lb bomb dropped within 100 yd of a blast furnace without damaging it.

Industry must remember, however, that A-bombs would be infinitely more destructive.

New Auto Plant in Barcelona


The building of the new Sociedad Espanol de Automoviles de Turismo (SEAT) plant in the Free Port Zone of Barcelona is rapidly going ahead. Machinery and machine tools for the factory have arrived.

This new motor car factory is to operate initially as an assembly plant with components imported from FIAT in Italy. Later on it is planned that all components shall be manufactured in Spain. SEAT is confident that the plant will go into production on time in about 12 months.

Special Problems for Heavy Press

Building heavy presses of unprecedented size to spur rearmament airplane production poses some thorny problems. Shown in the accompanying photograph is the scale model of a 35,000-ton forging press to be used by Air Force contractors to forge single pieces of aircraft structural members.

Size of the 6-ft man standing at floor level indicates the massiveness of the press being made by E. W. Bliss Co., Canton, Ohio. This



ICEBERG EFFECT: Line indicating floor level shows how much of the giant forging press will go underground. Size of 6 ft man indicates towering size.

firm is also building a 25,000-ton press for the Air Force.

To install the 35,000-ton giant a pit 100-ft deep must be dug for its base. And engineers must make certain the pit's location can support the tremendous weight.

Instead of very heavy castings Bliss is using weldments. There has been trouble in procurement of such heavy plate. Requirements run up to 17-in. thick plate, huge slabs of steel by any yard-stick. Welding sections together becomes an around-the-clock operation—once started welding cannot halt until the job is completed. It is estimated this will take 2 months.

Large size of the sections made it necessary to build a special normalizing furnace in the yard of the Bliss plant. Weight of the sections ranges up to 260 tons.


Transporting such bulk and weight calls for much ingenuity. Bliss will be working on a ¾ in. clearance to move the sections on the Pennsylvania Railroad. The firm has turned over to the railroad designs of special flat cars.

The eight tie rod forgings of the press weigh 74 tons each, are 50 in. in diam and 74 ft long. These tie rods are held in place by eight nuts weighing 1 ton each.

The press will have a 300 in. per min rate of rapid travel while press speed will be from 30 to 150 in. per min.

American press designers gave themselves a workout in planning these heavy presses on drawing boards. A prime consideration always had to be whether a part on the board could be transported on existing facilities once fabrication was completed.

WILLIAMS-WHITE PRESS SPEEDS STOVE PRODUCTION



WILLIAMS-WHITE 600-Ton Hydraulic Press forming broiler pan racks for electric ranges. Inexpensive, lightweight and quickly made Masonite dies are used as forming blocks to make possible short runs or quick changes in design.



Whatever your production plans may be, there is a WILLIAMS-WHITE custom designed machine to help you do the job better, faster and more economically. Presses, shears, punches, rolls, benders, hammers or bulldozers . . . designed and built to meet your specifications.



Write for Free Catalog of typical production machines Remember . . .

Getting in the

Scrap today

means more Steel

70morrow!

MAKERS OF QUALITY PRODUCTION TOOLS FOR NEARLY 100 YEARS

WILLIAMS-WHITE & CO.

JETS: Afterburners For

Planes need added burst of speed . . . Afterburners burn excess oxygen, do the job.

b

ba

Jar

bur

bur

ma ma

fro

ter

tur

In

act

noz

bre

mig

jet

per

wot

Oc

Afterburners give modern jets the quick power they need to zoom off a carrier deck or make a quick getaway from danger. Essentially a ram-jet engine hooked to the tail of a turbojet, an afterburner is a flaming tailpipe which feeds upon the unburned oxygen in the jet stream.

In piston engines air and fuel are mixed in about 16 to 1 ratio and rammed into cylinders. In turbojets the ratio is 60 to 1. Only about a fourth of the air, or oxygen, is burned in the combustion chambers. Rest is used to dilute the mixture and keep temperatures down. This unconsumed oxygen in the jet stream supports combustion of the afterburner.

Double the Thrust—From a tube no bigger than an elongated barrel is released enough energy to virtually double the thrust of the most powerful jet engine when more speed is needed. Such a wedding is taking place between jet engines made by General Electric and Westinghouse and afterburners made by Ryan Aeronautical Co.

Since the afterburner consumes fuel like a flaming oil well and has no major moving parts, it sounds extremely simple. In theory, at least, it is. But engineers putting theory into practice have had to cope with a lot of new problems.

One problem was finding a way to ignite fuel in the afterburner (it was like trying to light a bonfire in a hurricane). Igniter plugs were provided.

Intense temperatures are necessary for desired thrust, and huge quantities of fuel are consumed in a short time. With flame temperatures running to 2650°F and melting points of afterburner metals at 2723°F it takes careful design to prevent the burner from smelting itself into a mass of useless fused metal.

ers For Added Thrust

Need Scarce Metals—Hand-inhand with design problems are metallurgical problems. Afterburners use large quantities of scarce metals—cobalt and nickelbase alloys. Some of these alloys must be formed quite slowly to prevent work-hardening. Some have to be annealed at higher temperatures than stainless steels and require special welding and form-



y

n

n

n

10

st

e is

d

rs

28

19

at

12

18

av

er

gs

01

in

11-

at

to

ne


ed

7

INSPECTION: Ryan supervisors Robert Chase and James Ring (left to right) confer with General Electric inspector James Donovan concerning a fuel-injecting cone for afterburners in the Ryan plant. From this assembly, fuel is injected into the jet stream, aft of the turbine wheel, to burn with the unburned oxygen in the afterburner. Only about one-fourth of the oxygen is burned in the combustion chamber and the rest can be burned in the afterburner for that added thrust.

ing techniques. Properties that make them heat resistant also make them hard to fabricate.

Future refinement may come from introducing the fuel for afterburning ahead of the turbojet turbine wheel instead of behind it. In this method the turbine wheel acts as a flameholder and turbine nozzles function as atomizers, thus breaking up the fuel. If this development proves successful, it might remove the resistance to the jet stream flow which injector and flameholders present. It would also permit a shorter tailpipe which would be well adapted to fast aircraft with swept-back wings.



STRUCTURAL STEEL

The structural steel experience and facilities of this 56-year old organization are available to you any time anywhere.



STRENGTH

The world's most widely used material has the ability to withstand enormous pressures and stresses.



UNIFORMITY

Precise specifications and constant chemical and physical tests assure unvaried uniformity.



ADAPTABILITY

Steel frame buildings readily lend themselves to new styles and changing needs which insures long life to structures.



FIRE SAFETY

Steel will not burn. There are no structures more inherently fire-safe than the modern skyscraper, built with a steel frame.



VERSATILITY

The great variety of standard shapes and dimensions enables structural steel to be used for any structural problem.



ERECTION SPEED

Steel frame construction proceeds swiftly because every member is a finished product ready to be placed in the structure.



SALVAGE

Because steel retains its strength and dependability, it can be economically removed for use in new structures and for scrap.



ECONOMY

All these factors combine in saving money for the investor and the owner.




Member American Institute of Steel Construction
General Offices, Pittsburgh, Pa. . . . Plant at Canonsburg, Pa.

DISTRICT OFFICES
NEW YORK N.Y. . CLEVELAND, OHIO
DETROIT, MICHIGAN


"Steel Permits Steamlining Construction with Safety, Endurance and Economy"



AIR rammers pack mold sand around the wooden pot pattern to form the core.



SILICA coat is applied after the two halves of the mold have been separated.





BLAST furnace slag at about 2930° F is emptied into finished pot for dumping.

Rougher Duty for Cinder Pots

Steel furnaces have been operating at above rated capacities as the industry tries to jack up its production. Output has increased, but so has wear on equipment. Particularly hard hit are cinder pots used to dump furnace slag.

High furnace operation causes more metal to remain in the slag which means more metal sticks to the pot bottoms. Extreme force is required to remove this metal which causes cinder pots to wear out prematurely.

To meet this problem, manufacturers of cinder pots, like the Mackintosh-Hemphill Co., Pittsburgh, Pa., are constantly trying to improve their product. The pot casting method used by this firm is typical of the industry.

After a wooden model of a cinder pot has been made, it is set in a casting pit. Mold sand is packed around the pattern. When the model is completely covered, the top half of the sand mold is lifted off, and the pattern is removed from the bottom half.

The two halves of the mold are then coated with a silica wash, oven-dried, and assembled. Molten steel is then poured into an opening in the mold to form the casting. After cooling, the casting is annealed.

MOLTEN steel is then poured from ladle into mold opening to form pot casting.

COPPER coating is sprayed on bottom of cinder pot to minimize metal sticking.



AFTER cooling, the cinder pot casting is cleaned before being annealed.



CINDER pots are annealed to relieve internal stress. Process takes 7 days.



el ea er lit po

hi

nu

fic ha

St

saiing un by Ra

COL

ear

ery ask to ing sid

rel ma pra of

to cos tio a sing

thr giv tur (

> ori Oc

PRICES: Seek Earnings Standards Rise

OPS blocks price relief based on pass-throughs . . . But may consider price hikes on basis of earnings standards . . . Surveys requested by small tool and oil country goods manufacturers.

Companies producing small tools will be surveyed by Office of Price Stabilization as a step toward determining whether the industry is eligible for price relief under earnings standard rules.

Spokesmen for the manufacturers have told OPS there would be little improvement in their profits position if they sought relief solely through pass-through of higher steel, copper, and aluminum costs. Biggest sources of difficulty are labor costs, reported to have increased as much as 15 pct on the basis of new contracts, and steeper freight rates.

On an industry-wide basis, OPS said, the only method of furnishing price relief to manufacturers under present controls policy is by using the earnings standard. Rather than forego the opportunity to gain a measure of relief, company spokesmen asked for an earnings survey.

As Units—Oil country machinery and equipment builders are asking Office of Price Stabilization to consider the possibility of having segments of the industry considered as units in an earnings study to determine whether price relief can be obtained.

An industry-wide study, some manufacturers say, would be impractical because of the diversity of production.

Beset by labor costs that amount to 50 pct or more of production costs, the industry urges that action be taken quickly to prevent a serious impairment of its earnings position. Allowable passthrough of higher materials costs give very little help to manufacturers, it is reported.

OPS says there's a possibility that a division of an integrated firm might qualify for individual price relief under General Overriding Reg. 29 if that division produces "essential" items. OPS is considering this possibility as an alternative to application of its earnings standard formula.

Some Hope—Aluminum castings producers see some hope of partial price relief if the government's standard formula is used and have asked OPS for an immediate earnings study.

Steadily increasing labor costs have beset the industry since the price-freeze date in 1951, spokesmen have pointed out. Labor costs in their field, they said, represent more than 40 pct of the selling price of castings and have increased between 15 and 20 pct in less than 2 years.

Total effect of higher costs of labor and other production elements has been a serious impairment of their earnings status.

Won't Bother—Valve manufacturers do not plan to ask OPS for an earnings survey at this time. They feel that application of the earnings standard formula would not be feasible in view of the complexity of industry operations.

This was the conclusion voiced



by spokesmen for manufacturers at a recent meeting with OPS officials. The group told agency representatives that wage increase settlements, plus higher costs of freight and certain materials, had seriously undercut the industry's earnings position.

OPS offered no hope that valve manufacturers would be granted a flat ceiling price adjustment to cover increased labor costs and suggested no approach to price relief except through use of the earnings standard.

Invitation—Federal price-setters say that if enough firms in the small pneumatic compressor industry request an earnings survey as a preliminary to price relief, there will be early consideration of the request.

Industry Controls This Week

Autos—Amend. 5, Rev. 1, CPR 1 changes procedure used by auto manufacturers in computing ceiling prices on new products.

Brass—Amend., M-82 enables distributors of brass mill products to sell and accept orders for increased amounts.

Construction—Dir. 8, Dir. 2, Dir. 5 and Amend. CMP Reg. 6, Amend., Del. 14 and Revoc. M-100 are designed to relax construction regulation and increase amounts of controlled materials that may be self-authorized for construction. Many of the control relaxations will not become effective until May, 1953.

Reports—Amend. 36, GCPR concerns reports filed by retailers, whole-salers, suppliers and small manufacturers. It delegates authority to OPS field offices to act on reports filed under Sect. 6 and applications filed under Sect. 7 GCPR.

Defense Contracts—Amend. 3, Rev. 1, GOR 2 makes it unnecessary for defense contractors and subcontractors to state their ceiling prices.

Steel—Amend. 1, CPR 156 defines more clearly "customary markup" and its use in computing prices of fabricated structural steel, miscellaneous and ornamental iron and vessel shop products for field assembly.

Government Inviting Bids

Latest proposed Federal procurements, listed by item, quantity, invitation No. or proposal and opening date. (Invitations for Bid numbers are followed by "B," requests for proposals or quotations by "Q."

Corps of Engineers, San Francisco.

Brace, cross arm, Sti, galv, 134 ea, 04-203-53-344, Oct. 20. 344, Oct. 20. Condulet, service head, iron, galv, 134 ea, 04-203-53-344, Oct. 20. Floodlight, aluminum, 184 ea, 04-203-53-344. Oct. 20. Switch, safety sheet steel, 320 ea, 04-203-53-344, Oct. 20.

Signal Corps Supply Agency, Philadelphia.

Handle axle steel, 9900 ea, 579-32D-B, Nov. 7. Maintenance kit for carburetor, 4900 ea, 654-32D-B, Nov. 7. Cap cover for fuel tank, 2820 ea, 554-32D-B, No. 7.

No. 7. Carburetor horizontal draft, \$300 ea, 554-32D-B, Nov. 7.

throttle control, 3470 ea, 554-32D-B,

Nov. 7. Adapter carburetor, 2980 ea, 554-32D-B, Nov. 7. Governor, 5870 ea, 554-32D-B, Nov. 7. Stator magneto flywheel type, 3660 ea, 55-32A-B, Nov. 7.

Transformer power p/o Sig, 3630 ea, 511-32C-B.

Nov. 7. Transformer, 1500 ea. 511-32C-B, Nov. 7. Bushing brass 7 neoprene, 21400 ea. 787-32D-B,

Nov. 5. Stamp mechanism time date and time indicator, 370 ea, 557-32A-B, Nov. 6. Cable grip kits, 265 ea, 685-32D-B, Nov. 6. Valve exhaust, 13000 ea, 571-32D-B, Nov. 6. Cap for connector, 3300 ea, 548-32B-B, Nov. 6. Jack assy, 5200 ea, 548-32B-B, Nov. 6. Recptacle assy, 2123 ea, 584-32B-B, Nov. 6. Spring, flat type, 45800 ea, 10017-32DQ, Nov. 7.

Navy Purchasing Office, Washington.

Calipers, 5014, 513Q, Oct. 23.

Ammunition component box mark 2, steel, 249996, 5735-O-B, Oct. 30.

Guns, spray, 4435, 6751-B, Oct. 24.

Renmers, 44300, 6752-B, Oct. 24.

Wrench sets, 54990 set, 6743-B, Oct. 30.

Nippers, 322425, 6745-B, Oct. 30.

Bureau of Ships, Washington.

Marine tank gage, 100, 548-622Q, Oct. 31.

Watervliet Arsenal, Watervliet, New York. Steel housing assy, 81MM mount mortar, 2600 ea, 53-33B, Nov. 3.

Screw elevating assy, 81 MM mount mortar, 3900 ea, 53-33B, Nov. 3.
Handwheel traversing assy, 81MM mount mortar, 4400 ea, 53-33B, Nov. 3.
Yoke assy, parts for 81MM mount mortar, 2300 ea, 53-33B, Nov. 3.
Leg assy, 81MM mount mortar, 2500 ea, 53-33B, Nov. 3.

33B, Nov. 3.

Steel plug, 81MM mount mortar, 5004 ea, 53-33B, Nov. 3.

Steel guide, 81MM mount mortar, 5004 ea, 53-33B, Nov. 3.

Steel nut, 81MM mount mortar, per drawings and specifications, 3000 ca, 53-33B, Nov. 3.

Aluminum bronze screw, 81MM mount mortar, 10000 ea, 53-33B, Nov. 3.

Quartermaster Depot, Philadelphia.

astener slide interlocking, 14473, 73B, Oct. 30. astener slide, 1000000 ea, 68B, Oct. 10.

General Stores Supply Office, Philadelphia. Hinges, spring, screen door, wrought brass, 7600 pr, 1-1172B, Oct. 21.

Rock Island Arsenal, Rock Island, Ill.

Sleeve, cable, 314000 ea, 11-070-53-156B, Oct. 23. Holder lathe tool, 4065 ea, 11-070-68-161B,

Handle baseplate assy, 4000 ea, 11-979-53-164B,

Oct. 29. Tools, 900 sets, 11-979-53-167B, Oct. 24. Sander electric portable, 2800 ea, 11-979-53-170B, Oct. 24. Wrench electric reversible, 2740 en, 11-979-53-179B, Uct. 24.

Springfield Armory, Springfield, Mass.

Mill cutters and saws, 348, 53-80B, Oct. 29. "5" cutters, 349 ea, 53-80B, Oct. 29. Taps, 680 ea, 53-80B, Oct. 29.

Contracts Reported Last Week

Including description, quantity, dollar values, contractor and address. Italies indicate small business representatives.

ness representatives.

Hoist assy, 30 ea, \$126,006, Red Lion Cabinet Co., Red Lion, Pa.
Relay, 12248 ea, \$61,485, Imco Mfg.
Corp., New York.
Starter assy, 640 ea, \$149,862, Bendix Aviation Corp., Teterboro, N. J.
Direct current relay, var, \$26,586, Herback & Rademan, Inc., Philadelphia.
Generators, 180 ea, \$198,161, Bendix Aviation Corp., Teterboro, N. J.
Maintenance parts for R5C spares, var, \$30,164, North American Aviation, Inc., Columbus, C. E. Bloomer.
Kit-modification, 220, \$75,680, General Electric Co., Philadelphia.

Maintenance parts, var, \$43,226, General Metals Corp., Burbank, Calif.
Maintenance parts, var, \$37,040, Bendix Aviation Corp., Teterboro, N. J.

Maintenance parts, var, \$31,039, B. F. Goodrich Co., Akron.

Coils, 1050 ea, \$28,512, General Electric b., New York.

Co., New York.

Circuit breakers, 2200 ea, \$65,032, General Electric Co., New York.

Rack, arm, M4 for Cal. .30 carbine, 17300 ea, \$245,141, Dakin Mfg. Co., Chi-

cago.
Stabilizer grenade rifle M23A1, MPT3, 7360, \$304,483, Slaymaker Lock Co., Lancaster, Pa.
Trailer, 560 ea, \$216,563, Strick Co.,

Trailer, 56 Philadelphia.

Switch for F6F-5K aircraft, 390 ea, \$44,-070, Kollsman Instrument Corp., Elm-hurst, N. Y.

Maintenance parts for PB4Y, var, \$52,-633, Consolidated Vultee Aircraft Corp., San Diego, Calif., H. N. May.

Connectors, wire, rope, 6000 ea, \$38,100, Maine Specialty Co., Portland, Me.
Accumulators & regulators, var, \$59,188, Bendix Aviation Corp., N. Hollywood, Calif., David Schlosser.

Calif., David Schlosser.

Maintenance parts for var aircraft, var, \$59,672, General Electric Co., New York.

Power panel, 124 ea, \$25,763, Federal Electric Prods. Co., Long Island City, N.Y.

Generators, var, \$108,904, General Electric Co., Philadelphia.

Relay, 964 ea, \$49,019, Electro-Switch.

Controls, Inc., Culver City, Calif.

Valve, var, \$68,483, Weston Hydraulics Ltd., N. Hollywood, Calif.

Switch, var, \$26,028, PM Industries, Inc., Stamford, Conn.

Parts for aviation armament. 583 ea, \$141,444, 125.

Parts for aviation armament, 588 ea, 41,414, E. L. Cournand & Co., Inc., New

-Construction

Steel Inquiries and Awards

Fabricated steel awards this week include the following:

- 4250 Tons, Amesbury and Newburyport,
 Mass., superstructure of continuous,
 multi-span, steel-truss bridge. Harris Structural Steel Co., New York,
 low bidder.

 360 Tons, Hayesville, Kansas, Rock Island
 Desired bridge, to American Bridge.
- Railroad bridge to American Bridge.

 225 Tons, White, Wis., Oglesbay Norton & Co. mine shaft sets to Worden-Allen Co.
- 200 Tons, Chicago, Greyhound Corp. garage to Joseph T. Ryerson & Son.
- Tons, Minneapolis, bridge U-9-0 Great Northern Railroad, to American Bridge.
- 145 Tons, Pierre, S. D., Bureau of Reclamation, Steel Towers Spec. Es-3794 to West Coast Steel Co.

d

b

P te cl

ar m

0

Fabricated steel inquiries this week include the following:

465 Tons, St. Johnsbury, Vt., WF beam bridge with approaches, grading, drainage. P. M. Stevens, St. Johns-bury, Vt., district engineer. Com-pletion date July 1, 1954.


Reinforcing bar awards this week include the following:

900 Tons, Indianapolis, sewage treatment plant to H. D. Tousley.
155 Tons, Chicago, Neal junior high school, to Powers Construction Co.

Reinforcing bar inquiries this week in clude the following:

360 Tons, Amesbury and Newburyport, Mass., superstructure of continuous, multi-span, steel-truss bridge. Har-ris Structural Steel Co., New York-low bidder.

100 Tons, St. Johnsbury, Vt., WF beam bridge, with approaches grading drainage. P. M. Stevens, St. Johns bury, Vt., district engineer. Com-pletion date July 1, 1954.



ARTISTIC LAYOUT: This striking view of a new overpass project, part of the San Francisco Bayshore Freeway, shows that steelwork is now 52 pct completed. About 4800 tons of structural steel, fabricated at Bethlehem's Pacific Works, will be used in the project. Design attempts to reduce number of column to minimum while making the supporting bents as attractive as possible.



If you're using obsolete, slow-poke methods of shearing, the Kling Double Angle Shear can help you save time and money. This modern compact machine is designed for high speed, high production shearing on both long and short run jobs. Many metal fabricating plants and steel warehouses have found the Kling Shear to be the workhorse of the shop. For instance, one machine will shear round bars and bar angles on the left side while the right side can be used for structural angles and flat bars. The machine is built with the speed and power to handle the bulk of your shearing requirements. For shops with considerable mitre shearing in our 60th

work, Kling Double Angle Shears can be mounted on a turntable to facilitate handling. Automatic hold downs and one-shot lubrication can be furnished when desired. Sizes to handle angles up to 8" x 8" x 11/2".

WANT TO CUT SHEARING COSTS?

Find out how this high-production machine, available in four sizes, can give you more cuts, cleaner cuts on your shearing operations. Write for more information and latest bulletin. Kling Bros. Engineering Works, 1322 North Kostner Avenue, Chicago 51, Illinois.

SEND FOR NEW BULLETIN 2345













Plate Bending Rolls

Guards and Automatic Hold-downs.

ic

ch CB

in-

and

ton

ar

ea1

in

m

in

in

om

GI



TRANSPORTATION

HOUSEHOLD APPLIANCES

ELECTRICAL EQUIPMENT

INDUSTRIAL EQUIPMENT

FARM

UMPLEMENTS

Lansing Stamping Co.

LANSING 2 ESTABLISHED 1914 MICHIGAN

Are you selling used machinery, tools, equipment or surplus materials?

Let an advertisement in The Iron Age help speed up the process by contacting the many buyers who look here for leads.

Industrial Briefs

Absorption - CARL HIRSCHMANN CO., Manhasset, N. Y., has completely absorbed Hauser Machine Tool Corp., also of Manhasset.

Larger Plant-HUEBEL MFG. CO., INC., has moved to a larger plant at 763 Lexington Ave., Kenilworth, N. J.

Expansion-A \$440,000 expansion of testing facilities has been scheduled for 1953 by the Army Ordnance Corps' Malta missile test station, operated by GENERAL ELECTRIC CO.

Plating Survey-NATIONAL ASSN. OF METAL FINISHERS, Washington, has mailed out questionnaires to over 3500 companies. Having received answers from 9.2 pct of those queried, the association asks that plants still holding questionnaires hasten to get them in.

Docks Dedicated-The new \$6 million Savannah State Docks of the GEORGIA PORTS AUTHORITY will be officially dedicated in ceremonies there on Nov. 11.

Warehouse Opened - UDYLITE CORP. has opened a new warehouse in Philadelphia.

Appointment-Korhumel Steel & Aluminum Co., Indianapolis, has been appointed distributor of tools manufactured by THE PARKER APPLIANCE CO., Cleveland.

Invention Award Plan - Competition plus an invention award plan have boosted output of ideas for new inventions 80 pct among engineers and scientists of WESTINGHOUSE ELECTRIC CORP., Pittsburgh.

Company Organized-Gordon D. Zuck. president, has announced the organization of VULCAN STEEL CON-TAINER CO., Birmingham, Ala.

Officers Elected-STEEL PRODUCTS WAREHOUSE ASSN. has elected the following officers for 1952-1953: President, Sy Goldberg; vice-president, Moe Weiner; and secretary-treasurer, Stuart Henderson.

Directors Chosen-The following officers have been chosen by PRESSED METAL INSTITUTE: Wallace F. Ardussi, president; Samuel P. Hull, vice-president; and Hunter Morrison, Jr., secretary-treasurer.

Salvage Method-Two research projects aimed at finding an economical method of salvaging tin and steel scrap from tin cans will be sponsored STEEL INDUSTRY MOBILIZATION COMMITTEE. One project will explore pyrometallurgical methods and another at Armour Research Foundation will work on chemical methods of recovery.

Opening-The new plant of ELEC-TROLIZING CO., has opened at 1406 E. 15th St., Los Angeles.

Atomic Laboratories - WALTER KIDDE NUCLEAR LABORATORIES has announced the establishment of new research facilities at 975 Stewart Ave., outside of Garden City, L. I.

New Warehouse-Increasing demand for brass and copper mill products in the middle Atlantic area, has caused the opening of a new warehouse in Philadelphia for BRIDGEPORT BRASS CO.

Establishment - AMERICAN BEAR-ING CO. has been established in Minneapolis by S. H. Friedman, formerly of Chicago.

Company Acquired-In order to diversify its manufacturing operations, H. K. PORTER CO., INC., Pittsburgh, has acquired Watson-Stillman Co., Roselle, N. J.

Machine Tool Service-A new demonstration center and machine tool service has been opened at 21 Prospect St., Newark, by KURT ORBAN CO.,


Alloys Available-High-nickel alloys, rolled to precision-tolerances and ultra-thin gages are now available from AMERICAN SILVER CO., INC., Industrial Div., Flushing, N. Y.

Formed-A new company, ECLIPSE FUEL ENGINEERING CO., of Canada, Ltd., has been formed to handle sales and service of "Eclipse" products in Canada. The new offices are at 705 Bloor St., West, in Toronto, Canada.

Opens Office - NORTH AMERICAN STEEL PRODUCTS CORP. has opened a New York office at 32 Broadway with Paul Katz as district manager.

When a high-strength steel is needed

for severe cold-formed shapes like these bumpers



al

el ed P

al

)6

S

rt.

nd in

ed in T

Rin in,

di-

ch,

erect

ys, ind ble

C.,

SE

an-

dle

od-

to,

AN

adan-

GE

Assembly Lines Run At Full Speed

Car, truck output reminiscent of free market boom days . . . Expect half million cars this month . . . Will be highest yet since May '51 . . . New models now ready—By R. D. Raddant.

Production lines in Detroit are moving at a rate that has automotive statisticians thumbing back through 1951 and 1950 record books to find comparable figures.

Soaring weekly totals of new cars and trucks running off assembly lines and onto haulaways are only by the record final 3 months of 1950 when 1,668,219 cars were built.

Cash Value—The figures themselves don't mean much unless translated into economics. The production surge means that the closProduction rates are even more remarkable in that they are being reached while model changeovers are in progress. Chrysler is now changing at all four divisions which virtually put a stop to output there.

Changeover Cuts—For example, Dodge output a week ago was just over 1000 against an average weekly output of more than 6000. De Soto was down to a token 150 for the week as was Chrysler. In spite of changing over, Plymouth kept production at a respectable 8000, avoiding the usual shutdown. Again these figures are from Ward's compilers.

Of the Big Three, Chrysler cars will be the first to show 1953 lines, all of which are now in production and have been seen at private showings or by enterprising "spies" who have penetrated security curtains

A sidelight of the production picture is the race between Ford and Chrysler for second place in the industry. Bitter battle between the two at National Production Authority hearings showed the prestige each attached to position.

Ford was destined for third under the quota system until the steel strike placed the issue back on a production basis rather than an allotment basis.

At the three quarter mark, Ford had a total of 668,178 against 654,-778 for Chrysler. It is now doubtful if Chrysler can climb back into second spot unless Ford change-overs cut output more than is seen.

Big Question—About the only blank space remaining in the 1953 automotive picture is the place where the figures will be written in on price tags.

Most of the picture—styling, power and engineering changes—has been pretty well filled in by this time. Security-minded automotive people are exceeding their usual reticence when price comes into the discussion.

One executive who is known for his frankness resorted to this dodge.

Automotive Production





reminiscent of the boom days of the free market rather than the controlled production of 1952.

Ward's Automotive Reports, the statistical bible of the industry, says that producers are "betting overtime" that 500,000 passenger cars will leave U. S. auto plants in October. If the half million mark is reached, it will be the first month it has happened since May, 1951, when 506,545 cars were built.

Taking it a step further, the industry may turn out about 1.3-million cars in the final quarter. If it does, it will be the second highest last quarter in history, surpassed ing months of the year will bolster the sagging earnings of the industry, both to the stockholders and to labor.

But with 400,000 units lost to the industry during the steel strike there is little chance that corporate profits will bring much cheer to stockholders, even before taxes. Early in the year production controls idled many thousands of automotive workers. The steel strike kicked them when they were down. At least they are now assured overtime—fattened paychecks through the end of the year and probably well into 1953.



t

n v-

c-

re

13-

el

rd

it-

to

n.

53

in

I

a NEW use for Tand W stampings

Progressive engineers and designers of new products recognize T & W's ability to produce stampings for light weight, strength and economy.



32" x 9"


55" x 59%"


2" - 0

TRANSUE & WILLIAMS

SALES OFFICES: NEW YORK, PHILADELPHIA, CHICAGO, DETROIT, INDIANAPOLIS, CLEVELAND

25" × 23"





when pressed for price trends at a ecent press conference.

"I can say that prices will be approximately the same," he said. And he refused to elaborate.

Cost More—Actually, there is little doubt that the 1953's will cost the buyer more. It is where the boost will be applied that is the question. List price is really a relative figure, principally because the average buyer is dependent on a trade-in allowance.

For example, list price may remain the same, but the dealer may give him less this year than he would for a comparable car a year ago.

In spite of increasing costs in both labor and materials that hit the auto industry in recent months, manufacturers are not anxious to boost prices more than is absolutely necessary. They had a taste of buyers' resistance only last spring.

Best guesses indicate that prices will go up from 5 to 7 pct on models that show radical changes; less on others.

Kaiser First With New Models

First of the auto producers to introduce its new models is Kaiser-Frazer.

The Kaiser Deluxe and Manhattan models show little departure from the present lines. Chrome moldings give better emphasis to the sweeping front-to-rear lines. Horsepower has been stepped up from 115 to 120 in the 6-cylinder Kaiser engine.

The Henry J series is slightly longer than its 1952 predecessor. Engine performance is improved by greater capacity in the oil flow.

Third Axle Boosts Truck Payload

Whenever a truck company comes out with something new these days, chances are the motivating factor is an increase in payload.

This is apparent in the third axle introduced by White Motor Co. for its trailer trucks. The third axle is called a "steering pusher" that steers in coordination with the tractor's front wheel.

	Automotive Proc	duction	
	(U. S. and Canada C	ombined)	
WEEK ENDING	CARS	TRUCKS	TOTAL
Oct. 11, 1952	108,555*	32,332*	140,887*
Oct. 4, 1952	111,169	31,600	142,769
Oct. 13, 1951	95,119	25,424	100,543
Oct. 6, 1951	. 88,485	24,383	112,868
*Estimated		Source:	Ward's Reports

SPORTS CARS:

Industry watches public reaction to Buick Skylark model closely.

Announcement that Buick will produce its highly publicized Skylark sports car in 1953 was somewhat less than a surprise in the automotive world. It was a foregone conclusion for several months.

Public reaction will be watched keenly by almost all competitors. After all, most of them are probing the potential market with sports car models of their own.

While the Skylark is definitely a

sports car, it has production features that make manufacture an easier problem than for most comparable cars. It is built on a standard Roadmaster convertible chassis. Price will be "less than \$6000," according to Ivan L. Wiles, Buick general manager.

At the same time, Chrysler stepped in as a potential sports car producer by showing a new "Special" at the Paris Automobile Show. Unlike the Skylark, the Chrysler is built by Ghia in Turin, Italy, and does not appear to be a production car at the moment.

THE BULL OF THE WOODS

By J. R. Williams



N

Cong thor new No will crea carr lar.

only but non-Se cons cour

Sma quire apie

rease rier Navy least (1 craft

(3 (4 ordn (5 sions

pacit

agai "othe

No

speed

failur Force of se

Octo

Navy May Seek Big New Carrier Project

Next Congress may get Navy request for building carriers . . . Jets need more deck room . . . How much steel will be needed . . . FTC will survey how nation spends money—By G. H. Baker.

Look for the Navy Dept. to ask Congress early next year for authority to embark upon a huge new carrier construction program.

Need for such a program, Navy will explain, is based on the increasing use of larger and heavier carriers. Jet aircraft, in particular, require larger carriers not only for launching and landing, but also for servicing and other non-flying purposes.

Seven Good Reasons — Such a construction program will, of course, require large quantities of steel. Some idea of the big jump in steel requirements can be gained from this comparison. Smaller World War II carriers required only 15.620 tons of steel apiece. Larger ones will need much more.

There are a number of sound reasons for moving into a big-carrier construction program. As Navy officials see it, there are at least seven:

- (1) Increased weight of air-
- (2) Need for increased fuel capacity, due to jets.
 - (3) Need for more catapults.
- (4) Need for more aviation ordnance space.
- (5) Increased over-all dimensions of modern aircraft.
- (6) Increase in aircraft landing speeds.
- (7) Need for better protection against torpedoes, bombs, and "other" weapons.

No Unification?—Congressional indignation is mounting over the failure of the Army, Navy, and Air Force to promote a higher degree of service unification. Feeling at

the Capitol is that Pentagon brass "talks" unification, but does little or nothing to drive it into effect.

One legislation proposal now being readied for presentation to the Senate and House for action early next year would spell the end of the Joint Chiefs of Staff power to determine broad military policies. Under the present set-up, it is argued. Army-Navy-Air Force brass has absolutely no incentive to end the wasteful duplication of functions among services.

Civilian Control—New proposal calls for the deciding of all policy matters by civilian officials. This would have the effect of banishing the Joint Chiefs of Staff from policy-making power. Their role in future policy matters would be purely advisory under the plan.

A House subcommittee headed by Rep. Herbert C. Bonner, D., N. C., points out that the present "2-hat" composition of the Joint Chiefs of Staff permits the military to act in the dual roles of "partisan" and "judge." Such a system only adds to the high cost of defense because of the constant jockeying for position among the competing military services.

How's Money Spent—New study of the nation's spending habits, affecting both business and the public alike, is getting under way at the Federal Trade Commission. The agency will seek to determine how the consumer's dollar is spent, and whether or not "overhead" is unnecessarily inflating prices.

Of each product sold in regular channels of distribution, what percentage of the dollar paid out goes for materials? For labor? For distribution? Profits? The answers, FTC predicts, will be useful in holding down prices.

Value to Many—The resulting data also will be useful to business firms, to trade associations, credit institutions, and to private investors. Individual companies, for example, could compare their costs with those of their industry as a whole, and thus derive some idea as to their relative efficiency. Furthermore, there is considerable demand for such data from labormanagement groups, by the government, by farmers, and by consumers.


Trend of Draft — The 47,000-man draft call that will confront industry's personnel chiefs in December is to be confined largely to 20 and 21-year-olds. Draft officials are prohibited from calling up 19-year-olds at present.

All of the 47,000 men are to be tagged for service in the Army.

Xmas Leave—New angle to be introduced into the December draft call requires local selective service boards to deliver the entire month's quota in the first 2 weeks of the month. This will permit the maximum number of personnel to go on Christmas leave. It will mean that the draftees as well as selective service officials will be able to "go home" for Christmas.



"Since Carlson had those stamps made he never uses a typewriter."



No single type of fire brick will satisfy all the requirements of every furnace. It usually takes a *combination* of brick types to insulate most effectively.

In this radiant tube furnace, for example, different type brick were used for lining and back-up insulation. The lining called for a brick that could withstand the reducing atmospheres as well as the constant "soaking heat" caused by thick furnace walls. With heavy floor loads, hot compression strength was important.

To meet all these demands, Armstrong's A-26 Fire Brick was used in the lining. This brick offers high resistance to reducing atmospheres and has the great compression strength needed. In addition, A-26's top temperature limit of 2600°F, allows a good margin of safety in this application.

For back-up insulation, five 21/2"-thick courses of Armstrong's A-20 Fire Brick were used. A-20's high

insulating efficiency helps reduce heat loss, cuts fuel costs, and makes for more even temperatures.

All six refractory types in the Armstrong Line are formulated to give you the proper balance of physical properties. All of these brick are strong yet light in weight, will stand up under mechanical abuse and severe thermal shock.

You'll find it pays to call on Armstrong whenever you're faced with a refractories problem. An experienced Armstrong engineer will be glad to advise you in choosing the best brick—or combinaion of brick—for your particular job. Chances are he can save you money and improve unit performance as well. Before you go ahead with your next furnace job, call your near-by Armstrong office or write Armstrong Cork Company, 4910 Mulberry Street, Lancaster, Pennsylvania.



ARMSTRONG'S INSULATING REFRACTORIES

NICKEL: Expect Good Nicaro Report

Early report from GSA will show Nicaro paying off better than during war . . . 12 furnaces now in full operation . . . Research on cobalt, better nickel recovery—By A. K. Rannells

General Services Administration will shortly release a report showing that the mult-million dollar investment in the Nicaro nickel project is paying off better today than during the war.

"On the basis of preliminary figures," GSA administrator Jess Larson told THE IRON AGE, "we are nearing our originally estimated output rate of 15,000 tons.

"With Nicaro's 12 furnaces now in full operation, the free world is guaranteed nickel supplies at a rate at least 10 pct larger than pre-Korea."

Until complete data is received this month, there is no basis for comparison with wartime operations. But there is no doubt, Mr. Larson says, that the restored plant is at least 8 pct higher in efficiency than during its best wartime per-

Reactivation of the plant, closed down early in 1947, began in January, 1951, when GSA contracted with the Frederick A. Snare Corp., builder of the original works, to restore the facilities to operating condition.

Cost Breakdown-Cost of the rehabilitation after being inactive more than 4 years amounted to slightly more than \$12 million. Thus the plant now represents a total investment (including original cost of \$32 million) of nearly \$45 million.

Reconstruction cost is split almost evenly between rehabilitation and modernization and improvement.

A breakdown of the bills shows that out of the total reactivation cost about \$5.7 million went into restoration and repair, \$2.9 million into improved and more modern equipment, and \$1.7 million nto new construction.

Overall cost of labor amounted to \$1.7 million, of which 2 pet is charged to overtime in hurrying up the job.

Research Work, Too-Included in the improvements is \$600,000 for construction of a pilot plant for recovery of cobalt. This plant will also test out the Karon process which, if it proves out, is expected to add to the recovery of nickel by 10 pct.

Work was completed and the plant went into full operation in mid-July. However, GSA says, this does not mean that it has been turning out nickel at full capacity. There have been many "bugs" resulting from long inactivity of machinery, training of workers and change over to new equipment.

But the coming report is expected to show that these have been worked out and that production from here on will be at the previously estimated rate-and perhaps more.

It had originally been intended to place operation of the reactivated plant back into the hands

of the Dutch-owned Mining Equipment Corp. of New York, the wartime operator.

However, the Dutch are now out of the picture. The plant is operated by the Nickel Processing Corp., owned jointly by National Lead Co. (60 pct) and Fomento Minerals Cubanos (Cuban capital), which bought out the interests formerly held by the N. V. Billiton firm in Holland.

U. S. Gets Output-All output by Nicaro is to go to the United States. Operation is on a fee basis which is expected to produce nickel oxide at about 40¢ per lb of contained nickel.

Rated capacity in 1942 was about 43 million lb of highgrade nickel oxide which would work out at about 32 million lb of contained nickel.

As stated, present operations indicate a production rate now of approximately 30 million lb. With operations going smoothly, and in view of improvements in equipment and efficiency, GSA confidently expects this to be increased considerably by end of the year.

Guided Missile Anti-Aircraft

Anti-aircraft units using the NIKE guided missile as primary armament probably will be organized and placed in positions of defense beginning next year, the Army has announced.

Tests on the NIKE have proved sufficiently successful to warrant conversion of conventional-type anti-aircraft battalions to the missile-firing type.

Personnel who will form cadres for the new battalions are undergoing tactical and technical training at the Guided Missile Center, Ft. Bliss, Tex., and White Sands Proving Ground, Las Cruces, N. M.

NPA Merges Two Divisions

Under the changing set-up at National Production Authority, the Tin, Lead, and Zinc division has been merged with the Miscellaneous Metals & Minerals division, headed by Erwin Vogelsang.



aetna-standard completes two-year expansion program

The two-year expansion program gives Aetna-Standad additional facilities to meet delivery schedules for tube mils. flat-rolled equipment, wire-drawing products, drawbenches and other machinery for the metal industry.

At the big Ellwood City plant . . . a new Roll Foundry features foundry handling equipment and many innovations. Additional assembly and machine shop capacity has been added, augmented by many new machine tools. Executive offices are now located in the Frick Building, Pittsburgh, Pa. . . . General Offices in Ellwood City.

Aetna-Standard recently completed 50 years of Creative Engineering service to the ferrous and non-ferrous industries and looks forward with confidence to another fifty.

40 CO RE SE RE SE RE CO CA AD THE CO

BUYS RUBBER & PLASTICS MACHINERY DIVISION OF

The facilities of the Warren, Ohio, plant will be used primarily for the production of machinery for the rubber industry. Aetna-Standard has purchased the patterns, drawings and some machinery of the rubber and plastic products division of the National-Erie Corporation, Erie, Pa., subsidiary of Bucyrus-Erie Company.

Aetna-Standard

THE AETNA-STANDARD ENGINEERING COMPANY . PITTSBURGH, PA.

Plants in Warren, Ohio . Ellwood City, Fonney Vania

ASSOCIATED COMPANIES

- Head Wrightson Machine Company, Ltd., Middlesbrough, England Great Britan, Finland, Sweden, Norway, Denmark, Union of South Africa, Northern and Southern Rhodesia.
- Aetna-Standard Engineering Company, 14d., Toronto, Ontario, Canada.
- M. Castellvi, Inc., New York, N. Y. Merico, Central and South America. Societe de Constructions de Montbard, Paris, France France, Belgium, Holland, Luss-bourg, Switzerland.
- Demag Aktiengesellschaft, Duisburg, Gern und Germany, Austria, Yugoslavia, Gre ce, Turkey, Egypt.
- Compagnia Italiana Forme Acciaio, Mileno, Italy Italy. Aetna-Japan Company, Ltd., Tokyo, Japan -- Japan.
- Hale & Kullgren, Inc., Akron, Ohio Re re-sentative for the Rubber Industry.
 - Designers and Builders to the Ferrous, Non-Ferroes, Leather and Rubber Industri

Defense Expansion Steel Easing?

Supply should catch up with western demand in first period 1953... NPA certificates for area hit new low... Mills see a peak early in year, then easing market—By T. M. Rohan.

Steel supply for expansion of defense-connected projects in the West will probably catch up with demand in the first quarter of 1953—several months ahead of the rest of the nation.

dard

nils,

ndry

ions.

been

utive

ı, Pa.

ative

Southern

y, Itd.,

Merico,

d. Paris.

Mil-no.

Japan -

- Rente

ustri

Issuance of National Production Authority certificates for the California - Arizona - Hawaii - Nevada area hit a new low last week with only \$2 million involving eight certificates out of the national figure of \$130 million for 90 certificates, or less than 2 pct. Early in the program, aircraft, oil and gas industries boosted the West's share of certificates to 22 pct of the national totals, but averages for the last few months have been 8 to 10 pct.

Slack Expected—Western mills are expecting the peak of expansion project requirements in the first quarter and see nothing in the national economy (short of war) which will take up the slack in the second half.

Steel requirements for defense production generally are less than for expansion. During the strike, for instance, defense requirements at Kaiser, lone major producer in operation, didn't exceed 15 pct. And western warehouses do less than 1 pct defense business.

Last week, however, the only immediate perceptible softening of demand was for reinforcing bars since there are so many western producers. Heavy rounds and plates from the East were still very much in demand for as far ahead as the order books have been opened.

Save Freight — U. S. Tin Co., which has a 5000-mile haul from Alaskan mines by way of New

York to final smelting in Texas, is looking for a shortcut. A pilot plant has been in operation at Seattle for a year to see if a final \$250,000 smelter there is economically feasible. Currently ore is mined at Lost River, Alaska, and partially concentrated there. Initial separation is done in New York and final smelting in Texas City. A Seattle spokesman last week said, "This is only in the discussion stage and no final verdict has been reached."

Northwest Power — Blue skies smiled down on the Northwest last week but got no return smile from industry. Over 1000 firms with 8000 kw connected power face a "brownout" unless rains come soon. In addition to the 395-ton daily loss in aluminum production due to cutoff of 388,000 kw interruptible power supply by Bonneville Power Administration, machine shops and foundries are



experiencing a fall-off in business because drought has closed down logging and the fishing season is over.

Bonneville reports last week showed since Sept. 1 stream flow has been lower than the worst recorded year of 1936-1937.

Planemaker Delivers - Transocean Airlines of Oakland, Calif. (THE IRON AGE, July 24, p. 54), delivered the goods last week with typical hustle and bustle. Its new plane assembly subsidiary, Western Sky Industries, turned over first production shipment of wing sections for the Douglas AD-6 Sky Raider only 11 months after formation of the company. Although ground was first broken Feb. 18, Western Sky now has 284 employees in a 60,000-sq-ft, \$1-million plant and \$8 million in subcontracts from Douglas.

Plant is of somewhat unique construction peculiar to aircraft assembly operations. Floor loads are light but the 6-in. concrete is poured over a 3-ft-deep compacted rock base. This is necessary for firm support of jigs up to 30 ft long whose maximum allowable variation in mating points is ±0.005 in. Constant weather is a major factor since abnormal temperature changes will throw these off.

Rosy Future—Nothing but prosperity greeted Commerce Secretary Charles Sawyer and three aides on a non-political, fact-finding swing through Colorado, Nevada, California, Utah, Oklahoma and Nebraska.

In California last week Mr. Sawyer said steel production would outstrip demand "by the end of 1953." Next major problem will be distribution, he said, pointing out formation 2 weeks ago of an Office of Distribution in the Commerce Dept. to "advise and help business" but without regulatory powers.

What's in the NPA Tool Inventory?

NPA's inventory of 30,000 left-over tools helps ease the tool shortage... But new production must fill most critical needs... Bright future for replacements—By E. C. Beaudet.

The net is gradually being drawn tighter around thousands of government-owned machine tools and related production equipment lying idle at various storage points throughout the country. For the first time detailed information on this equipment has been gathered and indexed in one central office in Washington.

The machine tool inventory center, officially known as the Production Equipment Central Inventory Group, has been operated by National Production Authority's Metalworking Equipment Div. since last May. During that time approximately 10,000 pieces of equipment have been added to the government's stockpile of tools left over from World War II.

Of these, 3258 pieces of equipment not in productive use have been allocated to military and defense-supporting manufacturers. Acceptances have averaged around 65 pct. Since September, 1951, over 10,000 tools have been allocated. Total number of tools now being carried in this central inventory comes to 30,000.

Don't Know—NPA wants military and defense supporting contractors to screen their records to find out if they can use any of the equipment now being held in inventory. It is believed some contractors do not know about the pool and as a result have not made use of needed tools that are available.

The inventory has been growing rapidly during the last few months and has been instrumental in breaking bottlenecks caused by inability to obtain certain machine tools. PECIG is claimed to have been particularly helpful in ex-

pediting such urgent programs, jet engines, shells and tanks. These efforts were aided by trained teams loaned by machine tool builders to NPA which inventoried the idle government equipment.

Wide Range — Available for allocation to military and defense supporting contractors are virtually every type and size of machine tool and related production equipment. These include general, single and special-purpose tools.

Admittedly, many of these tools are not suitable for defense production because of obsolescence or wear. However, a large number could be modernized and put into useful operation. Some sources believe that in the event of full-scale emergency about 90 pct of these reserve tools would be allocated.

No Cure-All—While some contractors find the central inventory



a source of relief to procurement problems, it cannot be expected to solve the shortage of critical machine tools. Of the 30,000 pieces of equipment in inventory, some officials claim at least 10,000 are not machine tools. Many are said to be items like chain hoists, conveyor equipment, etc. While these units have a close tie-in with production, they do not actually produce whole items or parts.

Furthermore, there's a notable scarcity of general purpose tools such as are listed in Exhibit D of M-41. This means demand for this type of equipment must still be filled by new production.

Not Giving All—Gradually, the services are turning over their idle tools to PECIG, but there is some feeling that they could dig up more tools for listing in the inventory if they wished. Service representatives refute such opinions and insist they are not keeping any items concealed.

The Air Force is proud of its progress in returning to inventory control a lot of machine tools from projects completed or phased-out because of budget changes. Some Air Force officers estimate 1500 machine tools have been recovered in recent weeks and that some of these are practically new. The Army and Navy have contributed much less to the inventory so far.

More Evidence - Along this same line, National Machine Tool Builders' Assn. recently estimated that addition of a provision to M-41, freezing non-rated orders 3 months before the required delivery month would help boost replacement business. NMTBA claimed such a provision might over the next 12 months release \$300 million worth of new machine tools for replacement of obsolete models in plants of non-defense manufacturers. And this would not interfere with required delivery of defense orders.



Photos and data courtesy of: Product Miniature Co., Inc., Milwaukee, Wisconsin

...another complex mold milling problem solved by the Rotary Head method

NOTICE the fineness of detail on this scale model! A Kearney & Trecker-Milwaukee Model 2D Rotary Head Milling Machine reproduced those details in the mold. No models or templates were used — the operator worked direct from blueprints. Workpiece material was oil-hardening tool steel.

e

d

0

le

of is

ie ir

ig

re ce

1)-

ts

ry.

ut

ne

00

ed

of

he

ed

ır.

nis pol ed to s 3 dereane ete ne ete

de-

GE

Work was done from exact scale reductions of the real tractor assembly prints—with only minor details eliminated. There were no delays in beginning, no extra operations. Blueprint dimensions were transmitted directly into metal and fine accuracy was possible because precise control of all operations is built right into the machine.


This exceptionally versatile machine can reproduce geometric shapes in both horizontal and vertical planes. If you have an unusual production problem,

it will pay you to investigate the Model 2D Rotary Head Milling Machine. Write for Bulletin D-20, Kearney & Trecker Corp., Milwaukee 14, Wisconsin.





Set-up for milling two halves of mold not changed until job is done. To insure faster, more accurate results.



Completed mold. Note wheel mold parts. Contours for hubs, spokes milled on Rotary Head machine.



Model 2D Rotary Head Milling Machine for fast accurate machining of production parts, dies, molds, etc.



When sirens scream and fire trucks roar through the streets to battle a blaze caused by a hydraulic line breaking in your die-casting plant, it's too late. Too late to prevent a fire. Too late to save lost production due to machinery and building damage. Too late, perhaps, to prevent injury or death to employes.

You can reduce the possibilities of such a disaster by switching to Monsanto Pydraul F-9...now. You can change to Pydraul F-9 simply by draining the hydraulic system and refilling with the Monsanto product.

Pydraul F-9 is Monsanto's nonflammable-type hydraulic fluid. Under test conditions, it does not flash or ignite when sprayed, dripped or flooded on molten metal heated to approximately 1,500° F., nor does it ignite or flash when sprayed, at 1,000 p.s.i., into the 6,000° zone of an oxyacetylene flame. Users say Pydraul F-9 has prevented fires in their plants.

In addition to increased safety, you get efficiency and economy when you switch to Pydraul F-9. The fluid has high resistance to mechanical shear and chemical breakdown. It is high in lubricity and does not corrode metals from which machines are constructed.

Investigate the increased safety, efficiency and economy of Monsanto Pydraul F-9 today. Contact the nearest Monsanto Sales Office or write for a copy of the 12-page, file-size booklet, "Pydraul F-9." MONSANTO CHEMICAL COMPANY, Organic Chemicals Division, 1700 South Second Street, St. Louis 4, Missouri.

DISTRICT SALES OFFICES: Birmingham, Boston, Charlotte, Chicago, Cincinnati, Cleveland, Detroit, Houston, Los Angeles, New York, Philadelphia, Portland, Ore., San Francisco, Seattle, Twin Cities. In Canada, Monsanto Canada Limited, Montreal. 0

th

st

Re

tie

ter

Mi

big

po

dr

He

fr

wil

00

Pydraul: Reg. U. S. Pat. Off.

PYDRAUL F-9



SERVING INDUSTRY ... WHICH SERVES MANKIN

Materials Controls Begin to End

Steel, copper, aluminum curbs already eased . . . Ottawa to retain standby powers, but plans to drop actual controls by Jan. 1 . . . Free building, inventory—By F. Sanderson.

It looks like the beginning of the end for materials controls in Canada. A number of key officials have returned to private life recently, and some curbs have already been relaxed.

Official Ottawa has been closemouthed, but has said that active controls will be off by year's end. Standby powers will be kept as long as the defense program lasts. This does not mean that industry will be able to get all of everything it wants, but it does remove the need for hunting licenses.

Free Steel—Controls on steel, copper and aluminum have recently been relaxed, and further easing should come soon. The two steel orders, SD 1 and 2, will probably be revoked by Jan. 1, freeing steel for inventory, construction.

Steel Div. now issues permits automatically for up to 200 tons of steel for building other than places of amusement and liquor stores, This may soon be upped to 500 tons. Canadian consumers may now buy up to 500 tons of U. S. steel without a permit.

Regional offices of the steel authority will close at the end of this month, leaving only a skeleton staff in Ottawa to close shop.

Ore Find—Exploration on Steep Rock Iron Ore Mines Ltd. properties should get a boost from a lucky break a few days ago. Cutters on the dredge at the Hogarth Mine for the first time bit into the big "A" orebody. Ore first to be exposed, assayed 54 pct Fe. A second dredge will go into action at the Hogarth site in a matter of days.

It hasn't been officially confirmed yet, but Inland Steel Co. will probably start another big

drilling program on the "C" orebody sometime this winter. About a dozen drilling rigs are reported lined up ready for work as soon as the ice is safe.

More Work—The "C" orebody is located in the northeast part of Steep Rock Lake. Inland made arrangements early in 1950 to explore the area, with an option to lease it for production. Surface diamond drilling was done in 1950-1951 by Inland's subsidiary, Caland Ore Co., but considerable more exploration is needed.

General feeling is that Inland will start a production program soon, even though it has another year in which to make up its mind. Plans call for about 3 million tons of ore per year.

In Production—Barvue Mines Ltd. will start producing zinc-silver concentrates at its property in Barraute Township, northwestern Quebec, within a few days. Initial output will be about 1000 tons daily. This will be built up to a minimum of 4000 tons by the end of the year. Cost of bringing the property into production will run a bit more than \$7 million. Orebody is 125 ft wide at the point mining will start, but average width is 103 ft. Length explored to

JAMAY S
LEMOVA DS
EST 1949

RAMPINS

LEMOVA DS
EST 1949

RAMPINS

date is 2500 ft. On the basis of extensive diamond drilling, ore reserves are estimated at 7,650,000 tons averaging 3.3 pct zinc and 1.2 oz silver per ton to 300 ft depth.

Through American Lead, Zinc & Refining Co., Barvue Mines has a contract with a subsidiary of United States Steel Co., covering the sale of 175,000 tons of zinc concentrate at a price of 17.5¢ (U.S.) per lb for zinc. The Barvue mill will have the largest initial capacity of any plant built in Canada.

Seaway Outlook—Canadian industry pins fresh hope for U. S. participation in the projected St. Lawrence Seaway project on the political make-up of next year's Congress. Results of next month's U. S. elections will be closely studied by seaway advocates in Canada and in the U. S. to determine what new appeals may be made for the project when the 83rd Congress convenes.

Although neither the Democratic nor the Republican party platforms contain any seaway planks—either pro or con—it is believed in Washington that the new Administration, regardless of its political character, will make a strong pitch to Congress for early U. S. entrance into the seaway.

But whether or not Congress will be any more inclined to approve U. S. entrance into a seaway agreement remains to be seen. Opposition interests, particularly those in eastern seaboard port and railroad circles, still protest.

How Much—Current U. S. seaway estimates contemplate that U. S. general cargo would account for about 9 million tons of the total 64.5 to 83.5 million tons which would be moved through the seaway each year. Canadian general cargo would account for another 4 million tons. Expressed in terms of revenue, this means that the U. S. would gain about \$10.7 million in tolls from general cargo, Canada would receive \$3 million.

KIN

AGE

ave money in outfitting your laboratory



With these two furnace shells and the one Lectromelt superstructure, your laboratory can handle almost any problem having to do with electric furnace operations. The superstructure can be shifted from one furnace to the other, as required, along with its electrical equipment.

The combination at the left is designed for small scale, batch smelting of ores and concentrates, melting of non-metallics, melting and refining of metallics. The furnace at the right can be used for continuous operations in experimenting on the

reduction of ores and melting of non-metallics.

Both furnaces can be employed with direct and indirect arcs. 50 KVA of power is available on low voltages and 100 KVA on high voltages.

Lectromelt engineers have been conducting continuing research for many years on electrothermic reductions, so they can help you put these laboratory furnaces to work proving new processes or improving the old ones. For Catalog No. 104 telling you about this service, write Pittsburgh Lectromelt Furnace Corp., 312 32nd Street, Pittsburgh 30, Pa.

Manufactured in . . . CANADA: Lectromelt Furnaces of Canada, Ltd., Toronto 2 . . . ENGLAND: Birlec, Ltd., Birmingham . . . AUSTRALIA: Birlec, Ltd., Sydney . . . FRANCE: Stein et Roubaix, Paris . . . BELGIUM: S. A. Belge Stein et Roubaix, Bressoux-Liege . . . SPAIN: General Electrica Espanola, Bilbao . . . ITALY: Forni Stein, Genoa.

HEG M U.S. PAT OFF.

MOORE RAPID WHEN YOU MELT ... LECTROMEL



FREE publications

These publications describe money - saving equipment and services... they are free with no obligation... just circle the number and mail the postcard.

Vibration control

Reduction of vibration from power-driven machinery results in increased productivity and decreased maintenance costs. Breakdown of equipment and damage to building structures from vibration can be eliminated by Westsorb absorbing felt designed for machine mountings. Tests have shown that Westsorb will not break down under repeated impact loads and it resists the harmful effects of oils, greases and acids. More information on Westsorb is contained in a new booklet. Western Felt Works.

Forgings, castings

For free copy circle No. 1 on postcard.

Two bulletins covering Henrichshutte Works' forgings and steel and iron castings are available from Davidson Steel Corp. The publications discuss the German firm's fabricating facilities and show typical forgings and castings made for specific applications. Davidson Steel Corp.

For free copy circle No. 2 on postcard.

Microscope in industry

The Electron Microscope at Work in Industry, issued by RCA Victor, describes in detail ten case histories in which the electron microscope has been used to solve problems of quality control, product improvement and development of new products in industrial labs. Included in the reports are applications of the microscope in the metal fabrication and automotive fields. Engineering Products Dept., RCA Victor Div.

For free copy circle No. 3 on postcard.

Processing equipment

Included in the new catalog covering the sheet metal designing and production facilities of the Burdett Mfg. Co. are ovens, heaters, air makeup units, spray booths and washers. One feature of the heating units is the fact that they may be equipped with the company's well-known Radiant Heat Burners. Burdett Mfg. Co.

For free copy circle No. 4 on postcard.

Finishing

Slanted for metalworking plant operators, Finishing Engineer, a new quarterly magazine published by Metalwash Machinery Corp., surveys operations involving cleaning, pickling and drying of metal parts. Featured in the first issue is a story on the Ford Motor Co.'s approach to mass production. Metalwash Machinery Corp.

For free copy circle No. 5 on postcard.

Turn Page

use postcard below

Postcard valid for 8 weeks only. Information may be secured subsequently by separate letters fully describing each item wanted, including company name.

FIRST CLASS PERMIT No. 36 (Sec. 34.9 P.L.&R.) New York, N. Y.

BUSINESS REPLY CARD

No postage necessary if mailed in the United States

POSTAGE WILL BE PAID FY

THE IRON AGE

Post Office Box 77 Village Station NEW YORK 14, N. Y.

Circ	le nu	mbers	for	Free	Publica	tions	or inf	orma	tion on	New	Equi	pmen	:	
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
16	17	18	19	20	21	22	23	24	25	26	27	28	29	30
31	32	33	34	35	36	37	38	39	40	41	42	43	44	45
46	47	48	49	50	51	E 20	E 10							
of you	E	int mo	re d	etails PR(on oth									low
PAG PAG	E	ant mo	re d	etails PR(on oth	er pr	oducts	adve	ertised	in thi	3 135	ue fill	in be	
PAG PAG PAG	E	me .	ore d	etails PR(PR(on oth	ier pr	oducts	adve	ertised	in thi	s iss	ue fill	in be	low
AG AG AG	E E	ME .	ore d	etails PR(PR(on oth	er pr	oducts	adve	ertised	in thi	s iss	ue fill	in be	low

Continued

Lubrication fittings

Specification sheets are available on Alemite Indirection fittings. Included in the types covered are hydraulic, button head, dot, flush, push and pin fittings. Alemite fittings have exact contours for wide sealing angle and are effectively protected from dirt. Alemite Div., Stewart-Warner Corp.

For free copy circle No. 6 on postcard.

Fork trucks

Step-by-step procedure for selecting a fork truck for your plant is clearly explained in a new leaflet put out by Baker-Raulang Co. By checking your truck requirements against specification chart in the folder it is a simple process to determine the model fork truck best adapted to your needs. Baker-Raulang Co.

For free copy circle No. 7 on postcard.

Riveting

An informative manual containing operating instructions for automatic rivet-setting machines has been prepared by Milford Rivet & Machine Co. Detailed information is given on the care and operation of rivet setters. There is also material on the operation and adjustment of the Horton non-repeat clutch and the care and operation of automatic spot-setting equipment. Milford Rivet & Machine Co.

For free copy circle No. 8 on postcard.

Cutting tools

Included in the Gairing catalog of standard cutting tools are interchangeable counterbores, back spotfacers, core drills, block-type boring tools and standard milling cutters. Specifications and general descriptions of all the tools are given. Gairing Tool Co.

For free copy circle No. 9 on postcard.

use postcard below

Postcard valid for 8 weeks only. Information may be secured subsequently by separate letters fully describing each item wanted, including company name.

Posto	ard va	lid 8 we	eks on	ly. Aft	er that u	INO BZ	letterhe	ad full	y descri	bing ite	m wan	ted.	10/1	6/52
Circ	le nu	mbers	for I	Free F	Publica	tions	or inf	ormat	ion or	n New	Equi	pment	t:	
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
16	17	18	19	20	21	22	23	24	25	26	27	28	29	30
31	32	33	34	35	36	37	38	39	40	41	42	43	44	45
46	47	48	49	50	51	52	53	54	55	56	57	58	59	60
PAG	E			PRC	DUCT									
PAG	E			PRC	DUCT									
PAG	E			PRC	DUCT									
PAG	E	ME .		PRC	DUCT	* * * * *				TITLE				
YOU	IR NA	ME .		PRC	DUCT					TITLE				
YOU CO.	IR NA	ME . Y	****	. PRC	DUCT					TITLE			*****	

FIRST CLASS PERMIT No. 36 (Sec. 34.9 P.L.&R.) New York, N. Y.

BUSINESS REPLY CARD

No postage necessary if mailed in the United States

POSTAGE WILL BE PAID BY

THE IRON AGE

Post Office Box 77 Village Station NEW YORK 14, N. Y.

Jet blade grinder

Manufacturers of jet blades and buckets will be interested in a new pamphlet describing Landis Tool Co.'s Jet Blade Contour Grinder. This unit has been designed to grind five surface elements of jet blades and buckets in one continuous operation. Surfaces that can be ground simultaneously with this grinder are: Platform radius, leading edge, external airfoil surface and trailing edge. Landis Tool Co.

For free copy circle No. 10 on postcard.

Automatic palletizing

Lamson Corp.'s automatic pallet loader, described in a new folder, palletizes up to 1800 cartons or cases per hr in predetermined patterns. The pallet loader is capable of forming an infinite number of pallet patterns, but the cabinet is designed to hold up to 18 patternforming cartridges. Also listed in the bulletin is engineering data on the standard pallet loader including size limits of pallets and number of cartons that can be handled. Lamson Corp.

For free copy circle No. 11 on postcard.

Arc welding

In the latest issue of Hobart Arc Welding News is an interesting article on the part arc welding plays in truck body building. In addition to other stories on arc welding, there is a brief section on Hobart welding equipment. Hobart Bros. Co.

For free copy circle No. 12 on postcard.

Capacitors

Sprague Electric Co. has just released a comprehensive catalog of its transmitter-type mica dielectric capacitors which conform with Joint Army-Navy Specification C-5. Designed as a reference for engineers and purchasing agents, the catalog contains helpful illustrations, engineering drawings and technical characteristics of each unit. Sprague Electric Co.

For free copy circle No. 13 on postcard.

Turn Page

where power
is part of
the product,
you're right with a
DELCO

er.

et u-

an nis idice Co.

let ler, or latble

of is ern-

OIL

ing

iber lled.

d.

Arc

ar-

lays

tion

ling, bart Bros.

rd.

t re-

g of

ctric with

ation

for

ents.

illus-

s and

each

ard.

When you need motors—to serve as a part of your product or to help you make your product—look to Delco for the motors that will serve you best.

Delco produces motors for practically every known purpose . . . and each Delco motor is *engineered* for the kind of work it has to do. It's made of the finest materials, and constructed to stand up longer under the roughest conditions.

So check on Delco. You'll find Delco motors fit your needs, and that Delco always delivers on time. For complete details, write to Delco Products, Dayton, Ohio, or call the nearest sales office listed below.

DELCO PRODUCTS

Division of General Motors Corporation

Dayton, Ohio

SALES OFFICES:

ATLANTA - CHICAGO - CINCINNATI - CLEYELAND
DALLAS - DETROIT - HARTFORD - PHILADELPHIA
ST. LOUIS - SAM FRANCISCO




TOTALLY ENCLOSED FAN-COOLED MOTOR



OPEN BALL-BEARING MOTOR



TOTALLY ENCLOSED MOTOR



EXPLOSION-PROOF MOTOR

DELCO FEATURES

MAKE

DELCO FINEST

Continued

Metal cutting

De Walt ME-I Metal Cutting Machine has been designed to speed up cut-off operations. The machine will cut off ferrous and nonferrous bar stock up to 3 in., light wall steel tubing up to 4 in., flat bar stock up to 1 x 4 in. and structural shapes up to 4 in. on a side. To assure complete operator protection, the entire cutting unit including the cutting mechanism is totally enclosed. DeWalt, Inc.

For free copy circle No. 14 on postcard, p. 69.

Chrome plating

Chromaster Model A-250 is an industrial hard chrome-plating unit designed for chrome-plating cutting tools, dies, gears, pistons and other machine parts and components. Chromasol, the chrome-plating solution used in the Chromaster, plates directly on industrial steels, cast irons and most nonferrous metals. With the Chromaster and Chromasol, normal life of most cutting tools and wear parts can be increased 3 to 10 times. More information is available in a new circular. Industrial Chrome Div., Ward Leonard Electric Co.

For free copy circle No. 15 on postcard, p. 69.

Drives, drill shafts

Econoflex drives and drill shafts are complete units that can be attached to any power source. There is an Econoflex drive unit for heavy, medium and light duty use. Also illustrated and described in a new folder are accessories such as angleheads, special hand pieces, bench stands and wheel guards. Elliott Mfg. Co. For free copy circle No. 16 on postcard, p. 69.

Slide rule

A slide rule for calculating weights of all flat sheet metal is available without charge from Dayton Rogers Mfg. Co. To determine the weight of a piece of sheet metal by slide rule, all that has to be known is the width of the sheet or strip and the pitch or number of lineal ft required for one to 100 pieces. Dayton Rogers Mfg. Co.

For free copy circle No. 17 on postcard, p. 69.



HORRIBLE EXAMPLE. These gun barrel blanks were shipped in wire-bound bundles which were improperly bundled and braced in the gondola. Results: barrel ends were damaged, and the entire shipment was in shambles. Many man-hours were required to recooper the bundles before they could be unloaded.



WISE SOLUTION. At the suggestion of a Signode fieldman, the next shipment was bundled by the tested and approved* method shown here-with heavy-duty Signode steel strapping. Results: Shipment received in perfect condition. Crane was able to unload car rapidly because each bundle was still intact, thus saving time and labor.

Do this now—to insure against similar losses...

First, send for a Signode fieldman! You will be under no obligation. His advice will be sound. It is based on experience-and backed by the engineering facilities of Signode! His tested and approved* recommendations are sure to result in improved packaging and shipping methods, and profitable economies in materials used, manpower and time. Write today for the services of a Signode fieldman!

> *Another exclusive service proved and tested for you

Steel Strapping Company 2623 N. Western Ave., Chicago 47, III.

This Seal means security in shipping

Offices coast to coast. In Canada: Canadian Steel Strapping Co., Ltd. Foreign Subsidiaries and Distributors World-Wide

Bundyweld Doodles

to jog a designer's imagination Compressor



parts

Working out a new part design? Then why not let Bundyweld Tubing and Bundy engineering skills help you get better-functioning parts, faster fabrication, lowered costs?

Condensers

Bundyweld performance qualities make it practical for a wide choice of applications. And, with their tested experience in designing and fabricating tubing parts, Bundy engineers can often point out ways to save you time, material, money. Write for a catalog today.

Bundy Tubing Company, Detroit 14, Michigan

Hydraulic Lines



Runners for Vacuum Cleaner

DOUBLE-WALLED FROM A SINGLE STRIP

Leakproof High thermal conductivity High bursting point High endurance limit Extra-strong Shock-resistant Ductile

Lightweight Machines easily Takes plastic coating Scale-free **Bright and clean** No inside bead Uniform I.D., O.D.

BUNDYWELD 15



d e 18 el

p

n-

n-

td.

9

11-

ıg er

u-

es

st

S.

a-

ıg

n-

r-

rd

69.

ts itre or se. a as

es.

ls.

69.

its ole

on

he

tal

be

01

of

00

69.

GE

single strip of oper-coated steel. Copper-cod Then it's



continuously rolled twice around later-ally into a tube of uniformthickness, and




passed through a fur-nace. Copper coat-ing fuses with steel. Result . . .





NOTE the exclusive patented Bundyweld beveled edges, which a smoother afford joint, absence of bead and less chance for any leakage.


Bundy Tubing Distributors and Representatives: Cambridge, 42, Mass.: Austin-Hastings Co., Inc., 226 Binney St. • Chattanooga 2, Temn.: Peirson-Deakins Co., 823-824
Chattanooga Bank Bidg. • Chicago 32, Ill.: Lapham Hickey Co., 3333 W. 47th Place • Elizabeth, New Jersey: A. B. Murray Co., Inc., Post Office Box 476 • Philadelphia 3, Penn.:
Rutan & Co., 1717 Sansom St. • Seattle 4, Wash.: Eagle Metals Co., 4755 First Ave. South
Toronto, Ontario, Canada: Alloy Metal Sales, Ltd., 181 Fleet St., E. • Bundyweld nickel and Monel tubing is sold by distributors of nickel and nickel alloys in principal cities.



Here's how the CARBOFRAX hearth and side baffles looked after 15 months service — practically like new. Since silicon carbide is among the hardest of man made products, a hearth like this can take even the toughest abrasive wear and show hardly any signs of it.

This pusher-type, semi-muffle furnace is used for general heat treating. It is oil fired, operates 5 days a week at temperatures from 1350 F to 2100 F. Alloy trays carry the small parts, larger castings (up to 30 lbs) rest directly on the hearth.

In one year CARBOFRAX refractories saved over 30 days downtime



This same heat-treating furnace was able to turn out far more work, with far fewer shutdowns, simply by changing from one type of refractory to another. Originally equipped with 4" thick fireclay floor and side baffles, the output of this furnace was 6 tons a day (8-hr). At best, furnace efficiency was low, and there was rapid wear on the hearth caused by unevenly shaped castings being treated. Every month, a 2 to 3 day shutdown was required for refractory repairs. And 2 or 3 times each year, the hearth would be beyond repair and need complete replacement.

Then, CARBOFRAX silicon carbide refractories replaced the clay. Because they could be made thinner and because of their far greater thermal efficiency (CARBOFRAX refractories conduct heat 11 to 12 times faster than fireclay), furnace output

immediately jumped from 12,000 to 15,000 lbs a day. A gain of one full day's production every 4 days.

As for refractory maintenance, it all but ceased. 18 months after installation the CARBOFRAX hearth was in perfect condition, still hard and true. Maintenance up to this time: ZERO.

dition, still hard and true. Maintenance up to this time: ZERO. In other words, after 18 months the CARBOFRAX hearth had not only outlasted 3 fireclay hearths, but saved roughly 45 days of downtime. Plus the labor. Plus the materials. Plus the lost production. And, it was still in excellent condition, still helping to deliver an extra 7½ tons of work per week, every week.

To find how these refractories can benefit *your* furnaces simply write to Department B-102, Refractories Division, The Carborundum Company, Perth Amboy, New Jersey.

Use Super Refractories by


CARBORUNDUM

Trade Mark

"Carborundum" and "Carbofrax" are registered trademarks which indicate manufacture by The Carborundum Company.

NEW equipment

New and improved production ideas, equipment, services and methods described here offer production economies... fill in and mail postcard on page 69 or 70.



Kickup machine bends steel sheets edgewise

This massive press bends steel sheets edgewise in the manufacture of automobile and truck frames. Using a combination of mechanical, magnetic and hydraulic power, it can reshape steel sheets 19 ft long x between 5/16 and 5/64 in. thick; will take material 16 in. wide. The edgewise bending process effects

important savings in steel consumption. The machine is set in a deep box-like foundation 15 ft below the floor level. Inside the pit is much of the hydraulic mechanism that lifts the ram and assists in holding it tightly down on the piece being shaped. A. O. Smith Corp.

For more data circle No. 18 on postcard, p. 69.




Gas booster is hydraulically driven

A hydraulically driven compressor booster takes bottled gas from 300 to 2000 psi and boosts it to any given output pressure up to 12,000 psi. With a 10-hp motor it delivers approximately 1.5 cu ft per min up to 1250 psi over input bottle pressure and approximately 0.9 cu ft per min from 1250 psi up to maxi-

mum receiver pressure. This is accomplished by means of a high-low automatic unloading pump system which increases the efficiency of the unit by about one-third over a single pump system. The booster is used in guided missile work. Haskel Engineering & Supply Co.

For more data circle No. 19 on postcard, p. 69.



1112

hs

O.

rh

il

US

m.

k.


m.

E

Steel pillow blocks take heavy-stock loads

All-steel pillow blocks provide high load-carrying capacity in a compact and rugged package. Engineering resources and bearing building experience of Dodge and Timken have been pooled to produce this new line of pillow blocks. High radial and thrust capacities of the new bearings and the stamina to take heavy-shock loads have been provided within minimum dimensions and with far less than

usual weight. Bearings are fully self-aligning, with spherical outer race. They are available in both expansion and non-expansion types. Double piston ring seals keep the lubricant in and dirt and dust out of the bearing mechanism. Bearings are sealed both on and off the shaft. They will be provided in shaft sizes from 2 15/16 to 10 in. and shipped from stock ready to install. Dodge Mfg. Corp.



Outside spindle center turns large parts


For manufacturers who must turn and grind large parts weighing up to 12 tons a new, improved Red-E heavy duty anti-friction, superaccurate center has been designed. It features a large special collet arrangement that clamps over the

outside diameter of the tail stock quill. Duplex arrangement of angular preloaded precision bearings assures smooth operation free from any end or side play. Ready ToolCo. For more data circle No. 21 on postcard, p. 69.

For more data circle No. 20 on postcard, p. 69.

Turn Page

Continued



Staking machine

Reduced operator fatigue and increased production are claimed for an all-electric staking machine. Basic improvement consists of powering the machine by a solenoid rather than a spring loaded trip hammer. Both hold-down pressure and staking blow are fully adjustable. Worker operates the Electrostake by lightly touching a foot treadle. The machine is used for assembly-line operation where two or more assembled parts must be pressed firmly together and then staked or riveted with a sharp blow. Black & Webster, Inc.

For more data circle No. 22 on postcard, p. 69.



Electric paint remover

New Calrod paint remover removes paint quickly and economically using radiant heat. The device consists of two skids under which is mounted a Calrod tubular heater rated at 1000 w, 115 v. When the device is slid along a painted surface, the heat from the Calrod unit causes the paint to soften and blister; it can then be removed with a putty knife. General Electric Co.

For more data circle No. 23 on postcard, p. 69.



Lock 'em - and Leave 'em

• If you have a problem lifting, moving or containing bundles of bars, rods, or pipes—forget it. Get some of the new AMERICAN Bundling Chains with automatic locks. They're easy to hook up, and once you lock them, they stay locked. Yet you can unlock them with a flip of the fork. Satisfied users tell us they have made possible real savings in handling costs.

Write today for information on Bundle Locks or the 1001 other items in the complete AMERICAN Chain line.


(Patent Pending)



Quick-dip conveyer

The Quick Vertical Dip is a production line unit used to step up the progressive stages of military packaging involving washing, degreasing, rinsing, drying, finger-print removing, preheating, preservative dipping and final drying. The Quick-Dip features a 9-in. radius with the cable conveyer at a 60° incline. The conveyer may range in overall length from a single 10-ft loop to 1600 ft dual drive units. Loads up to 160 lb can be carried on standard stock trolleys. Units are shipped in stock sections. E. W. Buschman Co.

For more data circle No. 24 on postcard, p. 69.



Testing gear cases

Testing gear cases and related mechanical power transmission components may be done under full load and full speed by the square rig method: power of the driving motor is 5 to 10 pct of the rated power of the unit to be tested. The method is economical and may be done inside a laboratory or test room with little or no supervision, and for any duration. The square rig testing machine illustrated shows a setup for testing a helicopter power transmission gear case of 275 hp and a gear ratio of about 8:1. Load can be adjusted from zero to any desired value up to 115 pct of full load. Load test stands can be built for virtually any type of gear case or other power transmission unit. Technical Development Co.

For more data circle No. 25 on postcard, p. 69. Turn Page



Can YOU Do This?

• Do your slings give maximum safety in handling the 101 odd loads that your crane moves daily? A combination of ACCO Registered Wire Rope Slings, as shown above, can be used safely because all fittings and attachments have full rope strength.

The DUALOC Ending produces the strongest wire rope sling made. Two collars insure uniform strength from sling to sling. Actual strength certified by warranty certificate. Preformed improved plow steel Green Strand wire rope with steel core assures maximum resistance to kinking.

Popular sizes in stock for immediate delivery.

*Trade Mark Registered







see the man with a

Versatile Torrington Spring Coiler

In spring coiling, the words "Torrington" and "Versatile" are synonymous! When you desire springs produced to meet exacting requirements, just call the professional springmaker who has a Torrington coiler. He's the man who can fill your needs with accuracy, speed and economy. On special springs, our sales department will gladly assist you in finding a source of supply, or help your springmaker devise just the right tooling to produce it.

Torrington's 14 different Spring Coilers cover a range of wire diameters from .003" to .750"



MODEL W-11 SPRING COILER

Wire diam. range: .015" to .072". Length per spring: 0" to 42". O. D. Coil Range: 3/32" to 19/16". Produces 23 to 190 springs per minute with variable speed drive. Extra wire feed gears, torsion, other attachments available.

NOW...Spring Makers and Users can get the same answers with

The TORRINGTON SPRING TESTER

An accurate, uniform and inexpensive means of measuring spring load and deflection!

For inspection or in-use testing.

to aid in designing and developing springs for specific uses or as a basis for statistical quality control. Write today for illustrated bulletin on the Torrington Spring Tester!


TORRINGTON MANUFACTURING COMPANY TORRINGTON, CONNECTICUT

New Equipment-

Continued

Cylindrical grinder

Built in 18, 24 or 30-in. swing and in work lengths of 48, 72, 96, 120, 144 or 168-in., this new cylindrical grinder provides faster grinding action and simplified set-




up and operation. All feed and speed controls are at the front for quick adjustment. A click-count indexing mechanism permits settings of 0.0001 in, work diameter without visual attention. Many other features add to operating speed and ease. Norton Co.

For more data circle No. 26 on postcard, p. 69.

Quick aid

A quick-aid combination fire extinguisher cart is equipped with three extinguishers designed to combat all types of fires. This Handy Fire Dolly is mobile and easily wheeled into the emergency area; the proper extinguisher can be selected and brought into action at once. General Detroit Corp.

For more data circle No. 27 on postcard, p. 69.



Drill unit

A small self-contained production tool can be mounted on a machine in any position for extra drilling and boring jobs. Spindle is direct-driven by an electric motor; control is by pushbutton; travers rate is over 400 ipm, feed rate to 30 ipm; capacity ½ in. in steel. Speeds can be varied by changing sheaves and belts. *Drillunit, Inc.*

For more data circle No. 28 on postcard, p. 69.

Turn Page

Specify SQUARE D Motor Starters for 3 Important Reasons



Straight line guided motion minimizes wear; large silver alloy contacts insure troublefree electrical performance.



96

at

d

21 ıd al

ne

tnte

n: m nd

69.

"Off-the-Shelf" Parts Kits make

normal maintenance easier than ever. Each kit contains parts necessary to replace all load contacts and finger springs. An illustrated service bulletin is enclosed to provide quick parts identification and complete installation instructions.



ELECTRICAL INTERLOCKS are available in kit form.


Practically any necessary number or arrangement of extra interlock contacts can be added to any standard starter. Sizes 2 and 3 starters will soon have new front-of-panel mounting interlocks for easier installation.

(See cutaway at left)

Write for Bulletin 8536.


Square D Company, 4041 N. Richards Street, Milwaukee 12, Wisconsin.

ASK YOUR ELECTRICAL DISTRIBUTOR FOR SQUARE D PRODUCTS



SQUARE D COMPANY


*Well-Cast



COMMERCIAL LIGHTWEIGHT CASTINGS

Your commercial requirements for lightweight castings in aluminum or magnesium may be tough, but we'd welcome an opportunity to look them over. We've tackled a good many diversified casting problems over almost a half century.

Our four completely equipped plants and their trained personnel are at your disposal.



Aircraft wheels, strut parts, engine parts and miscellaneous components are being made every day at our plants, in aluminum and magnesium. X-Ray inspection, close attention to detail, complete facilities for production in sand, semi-permanent and permanent mold form.

Well-Made Wood and Metal Patterns.
Well-Cast Ampco Bronze Castings.

*Copyrighted Trade Name.


If you would like to receive the Wellman Magazine each month without charge, drop us a note on your business letterhead.

THE WELLMAN BRONZE & ALUMINUM CO.

DEPT. 8, 12800 SHAKER BLVD., CLEVELAND 20, OHIO

-New Equipment

Continued



Clearview container

New features of the Clearview Cargotainer for storage, shipment or assembly - line operations include new leg design that makes stacking more secure and easier. Center legs have been eliminated which allows the use of any type moving equipment. The Cargotainer can be loaded above the top wire and still stack securely. Special corner plates resist shock. Five folded Cargotainers now occupy the space of one unfolded. Exhaustive tests made with 5200-lb loads prove that the container will stand up. Pittsburgh Steel Products Co.

For more data circle No. 29 on postcard, p. 69.

Packaging parts

Bulk packaging of bearings, bushings and similar precision parts for domestic and export shipment can be simplified and improved using a new heavy duty corrugated box. The box is easily put together without stitching; each outer cap is formed by folding over its edge-flaps, and each cap is slipped over the inner regular slotted box. Extra thicknesses of corrugated board provide reinforcement for supporting heavy loads. Printed in color the box acts as a traveling billboard. Hinde & Dauch Paper Co.

For more data circle No. 30 on postcard, p. 69.

Water repellent

Silicon type water repellent for use on exterior and interior masonry surfaces assures deeper penetration into the surfaces; prevents staining and efflorescence. Wilbur & Williams Co.

For more data circle No. 31 on postcard, p. 69.

Welded aluminum tubes

New heat exchanger tubes are made by longitudinally butt welding Alclad 3S-H12 aluminum alloy sheet, rather than drawing seamless aluminum tubes. In two standard sizes, 1-in. OD with 0.049-in. and 0.065in. wall thicknesses, the tubes are low-cost and provide double - barreled protection against corrosion. They have the protective Alclad coating on both inside and outside surfaces. Typical tensile strength for Alclad 3S-H12 welded tubes is 17,000 psi and yield strength 14,000 psi. Aluminum Co. of America. For more data circle No. 32 on postcard, p. 69.

Metal strapping

r

e

S

1-

S

1-

h

1-

h

9.

t

d

)-

t-

T

ia

IT

of

e.

a

h

59.

90

ry

ts

er

59.

E

Small coils of strap cut to exact customer's specifications are now available for use with portable kits. Coils of any width or thickness in stainless, Monel, etc., can be furnished in lengths up to 36 in. Company will also coil customer's strap if sent to factory. A. J. Gerrard & Co.

For more data circle No. 33 on postcard, p. 69.




Pipe cutter

Named the E-Z cutter, a new portable pipe, tube and conduit cutter is suitable for on-the-job cutting in large and small shops. It features power driven rollers that revolve around the pipe; cutting is continuous, slippage is eliminated and the heat treated, high speed tool steel cutter wheel does not wear in one spot. Pipe 3% to 2 in. and tubing 5% to 3 in. can be cut. Foot control switch leaves the operator's hands free to handle work; speeds up cutting. Quijada Tool Div. of Gaines-Collins.

For more data circle No. 34 on postcard, p. 69.

Turn Page



cleaning weldments for Frank G.
Hough Company with a

WHEELABRATOR

Welding spatter and flux is removed in minutes by the airless Wheelabrator to save hours of wire brushing, grinding and chiseling. Welded areas are spotlessly cleaned to provide a perfect anchor for bonding the final finish.

For the Frank G. Hough Co., where two full shifts and 14 men had been unable to maintain existing schedules by wire brushing, chipping and grinding, the Wheelabrator handles the vastly expanded production at a savings of 64 man hours daily. Finishing operations have been placed



on a production of dollars in production costs. In addition, the thoroughness of Wheelabrator cleaning provides a uniform surface to which paint adheres tenaciously.

The use of the Wheelabrator in the welding industry is described in the bulletin, "How Weldments are cleaned faster and cheaper with a Wheelabrator." Airmail your request for a free copy today.

-American

WHEELABRATOR & EQUIPMENT CORP.

Wheelabrator
AIRLESS BLAST
CLEANING

510 S. Byrkit St.,

Mishawaka, Ind.

WORLD'S LARGEST BUILDERS OF AIRLESS BLAST CLEANING EQUIPMENT



No stooping, no fumbling... just swing saw cover open and everything is at your fingertip. Release blade tension, remove blade, insert new one and tighten. It's as simple as that! Result? Minimum loss of time, less chance of damage to blade and of injury to operator.

OF THE

This is but one of many exclusive Kalamazoo features that add up to lowest cost intermittent or continuous cutting. It will pay you to specify Kalamazoo Metal Cutting Band Saws . . . three sizes, available with coolant system and casters.

MACHINE TOOL DIVISION

Kalamazoo TANK and SILO CO.

Remember . . . there's a Kalamagoo Metal Cutting Saw to fit your exact needs


Model 610 cuts 6" round and 6" x 10" flat. Coolant equipment available.



Model 816 cuts 8" round and 8" x 16" flat. Model 824 cuts 8" round and 8" x 24" flat. Both models are available with coolant equipment.



Heavy-duty Model 1220 cuts 12" plus on rounds and 12" x 20" flat. Available with or without coolant equipment.



A real money saver for industry. Proven by the experience of tool and die, electronic machine, radio, electrical and instrument manufacturers.

The Green Engraver zips out precision work on metal, plastics, wood, glass, hard rubber etc. . . . engraves panels, name plates, scales, dials, molds, lenses, instruments, instruction plates, directional signs . . . by simple tracing. Routing, profiling and three dimensional modeling indicate its versatility. Electric otching attachment available.

Specify the Green Engraver for the best in low cost performance. Special attachments and engineering service available for production work.

FREE - Fact-packed folder yours upon request.



365 PUTNAM AVENUE . CAMBRIDGE, MASS.

-New Equipment

Continued

Hard steel drill

A new carbide tipped hard steel drill features a solid carbide slug which is sandwich brazed to an alloy steel shank. The brazing process bonds carbide to steel in a V notch to assure exceptional torque strength when drilling heat-treated steel. Torque of driving is not dependent upon the braze, but on the way the carbide is held by the shank. Flute length is designed for average depth holes. Drills range from ½ to ½ in. diam in increments of 1/32 in. Nelco Tool Co.



Work gloves

Armor grip work gloves are made with closed, flexible metal zippers permanently bonded to fingers and palms in synthetic rubber, providing positive gripping action and long wearing qualities along with maximum pliability. Mittens and palm guards also provide the worker with a multiple safety factor against impact, cutting and abrasive wear. Surety Rubber Co.

For more data circle No. 36 on postcard, p. 69.

Gate valve

Motor operated gate valve is said to be one of the lightest and most compact developed. New method of manual over-ride, and complete elimination of rubber or synthetic rubber are important features. Teflon, selected for its high fuel resistance, replaces rubber. Limit switching arrangement makes it impossible for the valve to stop in mid-position, eliminating possible operating failures. The valve operates with aircraft fuel, engine oil, hydraulic oil, alcohol, water, air, and gas. Hydro-Aire, Inc.

For more data circle No. 37 on postcard, p. 69

Turn Page



High Quality

A. P. GREEN REFRACTORY PRODUCTS

REDUCE DOWN TIME AND OPERATING COSTS

A. P. Green refractory products have proved in service that high quality pays off in greater tonnages, smoother operation, and lower maintenance costs.

There is an A. P. Green product designed to meet industry's requirements for almost any type of service. You'll find that it pays to standardize on A. P. Green quality products.

For specific recommendations on your refractory problems, get in touch with your local A. P. Green distributor. He is listed in the yellow pages of your phone directory.

A. P. GREEN FIRE BRICK COMPANY

Mexico, Missouri, U. S. A.

In Canada:

A. P. GREEN FIRE BRICK COMPANY, LTD.

Toronto 15, Canada



DISTRIBUTORS IN THE PRINCIPAL CITIES OF THE WORLD

el

V

e d eie

e e

9.

le

rs

did

th

nd

kor

a-

69.

id

of te

ic

s. el

it

it


in

le

il.

69

F



Largest Stocks in the Country..

of this versatile steel. 52100 is hard, tough and long-wearing, yet it's easy to machine and is right for bearings, sleeves, pins, collars and many other machine parts.

Over 200 seamless tube sizes to choose from .898" O. D. to 8.250" O. D. Bar sizes from .171" round to 7.5" round. Also ring forgings in any analysis.

Write for our Latest Stock List Now

> New Headquarters of Peterson Steels, Inc. Union, New Jersey



PETERSON STEELS, INC.

DEPT. I, SPRINGFIELD ROAD UNION, NEW JERSEY


Detroit, Mich. . Chicogo, III.

-New Equipment-

Continued

Sand seal shoe

Keeping sand in the coping of a soaking pit at a uniform depth is possible with a double seal self-equalizing sand seal shoe. It consists of a pair of opposed shoe castings which when bolted to the pit frame forms an inverted V slot where they penetrate the sand. As



these castings displace the sand, the sand so confined will compact, moving both upwardly and endwise so as to completely fill the triangular space; this forms a positive double sand seal. Geo. P. Reinties Co.

For more data circle No. 38 on postcard, p. 69.

Wire cup brush

A new wire cup brush with replaceable filler has been developed for removal of rust, scale, paint and welding slag from railroad equipment, tanks, gears and other metal surfaces. The brush consists of inner and outer metal adapters with a replaceable cup-shaped filler in which wire bristles are anchored in place with rubber. Wire gages range from 0.014 to 0.028 in. Hewitt-Robins Inc.

For more data circle No. 39 on postcard, p. 69.

Spring tester

Loads and deflections of small compression and extension springs are accurately measured by a new spring tester having load range capacity from ½ oz to 25 lb. Scale is accurate to within ¼ of 1 pct meeting the National Bureau of Standards requirements. Steel rules measure lengths in 32nds and 64ths on one side and decimals in 10ths and 100ths on reverse side. Speed of testing varies from 250 to 500 tests per hr. Carlson Co. For more data circle No. 40 on postcard, p. 69.

Vinylite tarpaulins

Made of DuPont 10 gage Vinylite, these tarpaulins are half the weight of duck tarpaulins and cost half as much; are said to be more durable and tough. They are 100 pct waterproof, crackproof, peelproof; resistant to abrasion, motor oils, and most chemicals, and will not warp or shrink after prolonged weathering and exposure to wide temperature fluctuations. Non-inflammable, they protect varied sizes and shapes of industrial equipment during shipment and while stored out-of-doors. Grommets are inserted at 3-ft intervals. American Agency.

For more data circle No. 41 on postcard, p. 69.

Folding scaffold

Fold-A-Way scaffold is a folding aluminum rolling scaffold designed for easy carrying and erection. It is made of tubular frames hinged to open sideways so that one man is able to erect or dismantle the base section while standing within the base area without danger of frames folding under during erection. Sections are preassembled. Patent Scaffolding Co., Inc.


For more data circle No. 42 on postcard, p. 69.



Steam cleaner

A new fireless steam cleaner has no fire box, gets its heat and pressure from steam lines used for regular production and heating purposes. At full capacity, it delivers 200 gal of hot solution per hr at temperatures to 212°F and pressures to 90 psi. Solution tank holds 50 gal, enough cleaning compound in solution to operate 4 to 6 hr without refilling. Variable-volume pump keeps steady high-pressure cleaning stream even when steam is low. Malsbary Mfg. Co.

For more data circle No. 43 on postcard, p. 69.





Everybody gets into the act.

That's the way we want it to be, here at Claymont.

Because that's the way we make sure that your order for alloy steel gets careful, individualized supervision . . . painstaking attention to every processing detail right from the front office, through our laboratories, down to the men who roll your steel.

Let us show you how our *personal touch* assures you of alloy steels that are truly tailored to your specialized requirements.

Write or call Claymont Steel Products Department, Wickwire Spencer Steel Division, Claymont, Delaware.

THE COLORADO FUEL AND IRON CORPORATION · Denver, Colorado

THE CALIFORNIA WIRE CLOTH CORPORATION · Oaklana, California


WICKWIRE SPENCER STEEL DIVISION · Atlanta · Boston · Buffalo · Chicago · Detroit · New York · Philadelphia

CLAYMONT STEEL PRODUCTS

PRODUCTS OF WICKWIRE SPENCER STEEL DIVISION THE COLORADO FUEL AND IRON CORPORATION







Typical Steel Mill Application of Three Model 3000-6 Nitroneal Generators

SEE UNIT ON DISPLAY AT METAL SHOW PHILADEPHIA, OCT. 20-24

Available in 100 C.F.H. to 10,000 C.F.H. Capacities

Fundamentally new ammonia-air reactor produces pure nitrogen with a controllable hydrogen content that can be varied at will and maintained at any percentage from .25% to 30% as required.

BRIGHT ANNEALING

Furnace Brazing

STAINLESS STEEL Low and High Carbon Steels **Non-Ferrous Metals**

- FULLY AUTOMATIC
- NO OPERATING PERSONNEL REQUIRED
- NO EXPLOSION HAZARD
- 30% LESS COSTLY THAN DISSOCIATED AMMONIA

GAS RATIOS PER 1000 CUBIC FEET OF FINISHED NITRONEAL GAS

% HYDROGEN	.25	1.0	3.0	6.0	20.0	25.0	30.0
AMMONIA (c.f.)	301	304	309.3	316.7	350	370	386
AIR (c.f.)	1070	1064	1033	990	790	715	640

Baker & Co. INC. 113 ASTOR ST., NEWARK 5, N. J.

86

THE IRON AGE


SIX

har

Fier

cqu

tric



How to slow down the fastest aircraft engine ever made!

Though the jet engine's record-breaking speed is an asset in a fighter plane, it's a handicap in driving many vital accessories of a plane.

Hydraulic pumps, generators, radar equipment can't be driven directly from a shaft that turns 16,000 38,000 rpm. To reduce the shaft speed to 2,000 rpm without cutting the engine speed, proved a tricky problem.

Barium's Jacobs Aircraft Engine Co., Pottstown, Pa., solved it by grinding special gear transmissions to precision tolerances on Swiss gear grinders.

Jacobs gear specialists can do as well for you. Other members of Barium Steel Corporation can supply your other steel needs. This group of strategically located companies controls quality from blast furnace to end product, works as a selfcontained unit to speed urgently needed orders.

Address inquiries to Barium, 25 Broad Street, New York City.



BAYONNE BOLT CORP. * CENTRAL IRON AND STEEL COMPANY "CHESTER BLAST FURNACE * CLYDE IRON WORKS, INC. * CLYAHOGA SPRING COMPANY "ERIE BOLT AND NUT COMPANY "GEOMETRIC STAMPING CO. * GLOBE FORGE, INCORPORATED * INDUSTRIAL FORGE & STEEL, INC. * JACOBS AIRCRAFT ENGINE CO. * KERMATH MANUFACTURING CO. * KERMATH LIMITED (CANADA) * PHOENIX BRIDGE CO. * PHOENIX IRON & STEEL CO. * WILEY MANUFACTURING CO.



This inspector tests Jacobs gears for accuracy in a controlled temperature area. Tolerances to .0001 in, are needed to meet high load requirements on many parts such as those for aircraft gears.




This worker's skilled handling of the latest grinding equipment helps maintain Barium's Jacobs Aircraft Engine Co.'s leadership in spur and helical gears, from tiny sizes up to 12 in, diameter.



This board tests hydraulic parts with rapid precision. In addition to auxiliary drives and other jet components. Jacobs makes complete reciprocating aircraft engines and auxiliary power plants.

TROUBLE GOES OUT when HARPER FASTENINGS GO IN



EVERLASTING FASTENINGS

BRASS . SILICON BRONZE . NAVAL BRONZE . MONEL . ALUMINUM . STAINLESS STEEL

the Iron Age

SALUTES

Carleton B. Tibbetts

This successful businessman is one of the most active citizens in the third largest U. S. city.



GREAT cities don't just happen. Los Angeles is no exception. In the spectacular growth of the nation's third largest city there are hundreds of solid citizens whose civic-mindedness, judgment and enthusiasm have been major factors behind the sky-rocketing business graphs.

Right up at the top of the list is "Tib" Tibbetts, president of Los Angeles Steel Casting Co. And the community appreciates his more than quarter century of distinguished service. In 1942, for example, the Los Angeles Realty Board chose Tib as "Los Angeles' Most Useful Citizen."

Born in Berwick, Me., and educated in New Hampshire, Tib moved from Chicago to his "native" Los Angeles in 1923. He's been with Los Angeles Steel Casting ever since—16 years as president and 7 before that as vice-president and general manager.

He's been president of the Los Angeles Chamber of Commerce and the Metal Trades Manufacturers Assn.; vice-president of the Merchants & Manufacturers Assn. and a member of the National Labor Relations Board, Area War Manpower Committee, Libanus Lodge No. 49, F.A.M., and California and Rotary Clubs, and commander, San Marino Post, American Legion. He's also found time to serve 3 years as mayor of San Marino, Calif., and another 7 years as councilman for the same community.

With a sharp but subtle sense of humor, Tib just likes to work—preferably in his shirt sleeves. But when he can he indulges his favorite hobbies of fishing, camping and outdoor sports.

ABOUT IT


TYPICAL OF THE EXTRA VALUES YOU GET

BAIRD

Year-in and year-out, in many automobile and other headlined production plants, Baird's No. 76-H Automatic Chucking Machine has proved itself to be one of the best production units of its kind. It's easy to operate and service; has unusual versatility in tooling, operations, speeds; and it cuts costs with quality control.

But the pay-off comes when Baird engineers adapt this 6-spindle unit to your specific tooling and production requirements.


For example, gear blanks (drawing below) are turned completely in one operation as shown. Material: High tension iron-hardness



BAIRD No. 76H AUTOMATIC CHUCKING MACHINE

85-90 Rockwell B scale. Production: 65 seconds each, 55 pieces per hour.

Of course we're busy. But not too busy to try and solve a problem for a new or old customer. Ask Baird about it!



AUTOMATIC WIRE & RIBBON METAL FORMING AUTOMATIC MACHINE TOOLS . MACHINES . AUTOMATIC PRESSES . TUMBLING BARRELS

la

ma C(

ana

cul

Par

00

the Iron Age

INTRODUCES

E. C. Berg, appointed vice-president and controller, MACWHYTE CO., Kenosha, Wis.; and G. Johnston, named treasurer and assistant secretary.

Frank A. Gorman, elected a vicepresident, EASTERN STAINLESS STEEL CORP., Baltimore.

L. F. Reimann, promoted to assistant vice-president of manufacturing, JACKSON & CHURCH CO., Saginaw, Mich.

Robert B. Dean, made chief analytical chemist, resin plant, Bainbridge, N. Y., BORDEN CO.

NE

AG

John Davies, promoted to the position of assistant chief engineer, EATON MFG. CO., Axle Div., Cleveland; and Chester D. Christie, becomes staff engineer.

Donald M. Covert, named office manager, THE ALLIED METALS CO., Niles, Ohio.

Theodore B. Smith, appointed budget director, CHRYSLER CORP., Detroit. He succeeds Duncan A. Samson, who has retired.

Henry W. Willard, appointed factory manager, Passaic, N. J. plant, UNITED STATES RUBBER CO.; and Purdy Miller, made manager of molded goods sales.

Jack Hensel, named supervisor of analytical research, PITTSBURGH COKE & CHEMICAL CO.; William R. Davie and Arthur M. Gladstone, appointed assistant supervisors of agricultural chemical research.

George Seagstacken, appointed works manager, CHASE METAL WORKS, Waterbury, Conn.; F. G. Parke, named general superintendent. James E. Hays, promoted to group engineer for structures, Flightronic Flight Simulator Div., ENGINEER-ING & RESEARCH CORP., Riverdale, Maryland.

J. Miller Brown, appointed export manager, PIONEER ENGINEERING WORKS, Minneapolis.

Wayne H. Hunter, named assistant sales development manager, Republic Rubber Div., LEE RUBBER & TIRE CORP., Youngstown.

Wayne H. Keller, appointed director, Chemistry Dept., NATIONAL RESEARCH CORP., Cambridge.

Beresford N. Clarke, becomes sales engineer, New England territory, SURFACE COMBUSTION CORP.

David S. Hodgson, named district sales manager, New York area, THE PRODUCTO MACHINE CO.

John J. Watson, appointed manager of foundry sales, C. O. BARTLETT & SNOW CO., Cleveland.

Jack Canady, promoted to sales manager, Palmer Mfg. Corp., Phoenix, a subsidiary of McCRAY REFRIGE-RATOR CO., INC.

George W. Pattlow, appointed supervisor of general accounting, U. S. Steel Supply Div., U. S. STEEL CO., and Gordon F. Johns, named priorities administrator.

G. W. Huldrum, Jr., appointed sales manager, Eastern Div., SHELL CHEMICAL CORP., New York; and V. C. Irvine, named manager, Western Div.

William A. Hopkins, named general sales manager, BART-MESSING CORP., Belleville, N. J.



FRANCIS O. CASE, elected president, newly-formed Anaconda Aluminum Co., Columbia Falls, Mont.



WALTER L. SMITH, made vicepresident in charge of operations and director, Chase Brass & Copper Co., Inc., Waterbury, Conn.



LESLIE G. JENNESS, named vicepresident in charge of research, Kennecott Copper Corp., New York.



or Released in an Instant



Faster assembly . . . no more failures of fasteners. GREER STOP NUTS hold firm against jolts, shocks, shimmy, wobbles . . . any vibration, any kind.



Bolt threads are gripped tightly . . . these famous nuts neter work loose. Yet an ordinary hand wrench gives instant release. The tough, built-in GREERCOID collar does it . . . and seals against fluid leakage, too!



Study your fastener problem. Over 3000 types and sizes. Consult GREER. Proved on thousands of products. Meets gov't and military specifications.



GREER STOP NUT CO. 2620 Flournoy, Chicago 12, III.



Personnel

Continued

Arthur H. Beasley, appointed manager, Memphis, WAGNER ELECTRIC CORP.

Richard S. Stockwell, appointed exclusive sales and service representative, Minneapolis-St. Paul territory, LEWIS-SHEPARD PRODUCTS; and Raymond F. Purinton, made exclusive sales and service representative, Denver territory.

Lenvik Ylvisaker, becomes general manager, northeastern district, Eastern Metal Div., CONTINENTAL CAN CO.; and Wilbur K. Neuman, made general manager, southeastern district.

E. R. Koester, named manager, manufacturing, X-Ray Dept., GEN-ERAL ELECTRIC CO.

Ernest E. Bang, appointed advertising manager, Berger Mfg. Div.. REPUBLIC STEEL CORP., and Oscar A. Bamberger, named assistant district manager, Massillon and Canton.

W. M. Kreglow, appointed blast furnace superintendent, Johnstown, Pa. plant, BETHLEHEM STEEL CO.; and C. M. Nitchie made assistant blast furnace superintendent, Sparrows Pt. plant,

R. L. Bernhard, named manager, newly-created Centrifugal Compressor Dept., AMERICAN BLOWER CORP., Detroit.

William V. Cigliano, named assistant general manager, RUSSELL, BURDSALL & WARD BOLT AND NUT CO.; Price Berrien, appointed plant manager, Los Angeles; and John B. Gates, made treasurer and assistant secretary.

C. J. Masepohl, promoted to the position of works-manager, CALU-MET STEEL CASTINGS CORP., Hammond, Ind.

Charles E. Barby, named sales manager, Detroit district, PITTSBURGH PLATE GLASS CO., Fiber Glass Div.

David B. Tyler, appointed advertising manager, NORTON BEHR-MAN-NING OVERSEAS INC., Worcester.

Stephen Sesnick, appointed industrial sales representative, New Jersey and lower New York area, LOWE BROS. CO., Dayton.



GEORGE S. FABEL, elected president, Thermoid Co., Trenton, N. J.



ALVIN A. MEYROWITZ, becomes vice-president and general manager. H. Kramer & Co.



C. B. McGEHEE, made vicepresident, Truscon Steel Co., Youngstown.



ANDREW GAGARIN, appointed president, Torrington Mfg. Co., Torrington, Conn.

A Customer Reports:

105" Asarcon 773 Bearing Bronze Cuts Short-End Scrap, Machining Waste

Willas-Overland Motors has cut scrap loss in the making of machine tool bearings by using Asarcon 773 (SAE 660) Continuous-Cast Bronze. Pieces are cut to the exact length needed from 105" stock supplied by

Meier Brass & Copper Company, Detroit (distributors); there is only one

short end from an entire 105" tube, an economy impossible with ordinary 13" stock.

Also, unique dimensional accuracy and uniformity reduce metal losses in finishing.

Asarcon 773 bearing bronze is continuous-cast in diameters ½" to 51s", cored or solid. It contains no hard or soft spots; no blowholes or porosity of any type.

Since sand is not used in the process, and dirt and dross are excluded, there is no

surface- or internally-trapped abrasive to dull tools or discourage high cutting speeds.

yield strength and hardness are appreciably improved, too.

Fatigue characteristics are up to 100% higher than those of the same alloys produced by other casting methods; tensile strength,

Distributors across the country have in stock 216 sizes of Asarcon 773 rods, tubes and shapes. They will cut it long or short to suit your requirements.

A variety of alloys, longer lengths and special shapes can be cast to order. Write for free catalog containing complete descriptive material.



West Coast Sales Agent: KINGWELL BROS. LTD., 444 Natoma Street, San Francisco, Calif.

American Smelting and Refining Company

OFFICES: Perth Amboy Plant, Barber, New Jersey Whiting, Indiana



Continued

Robert H. Fox, appointed sales director, Crane & Shovel Equipt. Div., COOK BROS, EQUIPMENT CO., Los Angeles.

A. S. Blodget, Jr., appointed manager, Pittsburgh district, AIR REDUCTION SALES CO., E. S. Twining, Jr., becomes manager, Boston district.

Reed A. Weyburn, appointed representative-distributor of sales, FLEXI-BLE TUBING CORP., Guilford, Conn.

Maurice H. McGuire, joins sales staff, HYDRO-AIRE, INC., Burbank, Calif.

Michael F. Wiedl, Jr., joins staff of Advertising Dept., ATLANTA STEEL CO., Atlanta.

William G. Cole, appointed sales representative, BOHN ALUMINUM & BRASS CORP., Chicago office.

William B. Guffey, named traffic manager, UNITED ENGINEERING & FOUNDRY CO., Pittsburgh. He succeeds Leonard G. Hults, who is retiring.

M. B. Beline, appointed to newly created post of director of national accounts, Quaker Rubber Corp., a division of H. K. PORTER CO., INC., Philadelphia.

George W. Roper, promoted to assistant technical director, Dust and Fume Control Div., AMERICAN WHEELABRATOR & EQUIPMENT CORP., Mishawaka, Ind.

OBITUARIES

Thomas Walker Page, 45, mining engineer, Armco Steel Corp.

Edward E. Ames, 71, retired chairman of the board, director, vice-president and director of sales, General Box Co.

John A. Moritz, 62, superintendent of wire mills, Keystone Steel & Wire Co., at his home.

Thomas D. Potts, 56, executive vicepresident, Adirondack Foundries & Steel, Inc., Watervliet, N. Y.

Charles Dreifus, 81, retired president, Charles Dreifus Co.

Edward Lawrence Greene, 68, president, National Better Business Bureau, at his home in Mamaroneck, N. Y.



Quiet...Clean...Safe

Because they are quiet, clean and safe, battery industrial trucks can be used without restriction in virtually any department of the plant or warehouse including confined quarters as well as areas devoted to processing foods, pharmaceuticals and other products demanding utmost cleanliness. They can even be provided with spark-enclosed construction for operation in hazardous locations.

They use low-cost electric power for battery charging; and they use it with maximum economy, because they start instantly, yet consume no power during stops. With electric-motor drives and Edison Nickel-Iron-Alkaline Storage Batteries, they have a minimum of wearing parts; are easy to maintain, are rarely out of service for repairs. With batteries exchanged at convenient intervals, they operate around the clock with the highest dependability and lowest overall operating costs.

Edison batteries have these important features:

They are durable mechanically; grids, containers and other structural parts of the cells are of steel; the alka-

line electrolyte is a preservative of steel,

They can be charged rapidly; gassing cannot dislodge the active materials.

They withstand temperature extremes; are free from freezing hazard; are easily ventilated for rapid cooling.

They are foolproof electrically; are not injured by short-circuiting, reverse charging or similar accidents.

They can stand idle indefinitely without injury. Merely discharge, shortcircuit, and store in a clean, dry place.

They are simple and easy to main-

As a result of these features, they are the longest-lived of all storage batteries. In fact, they have such long life that they effect important economies in depreciation charges. And they are so trouble-free that they cut maintenance charges too. Send for bulletin *Modern Material Handling* for further details of the advantages of electric-motor drives and Edison batteries, Edison Storage Battery Division of Thomas A. Edison, Incorporated, West Orange, N. J. Thomas A. Edison of Canada, Limited, Montreal.

You can always rely on



EDISON

Nickel-Iron-Alkaline Storage Batteries

rique . . will do work that

di-Div. Los

ana-UC. Jr.,

pre-EXIonn. sales ank,

ff of EEL

sales M &

affic ING He s re-

ewly l acdivi-NC.,

asand AN ENT

ning

airresi-

eral

dent Wire

vices &

resi-

resieat

AGE

NO OTHER

High Speed Steel will do

... does most of the jobs done by

other High Speed Steels . . . 5 OR MORE TIMES BETTER!

There's only one Vasco SUPREME... unapproachable for high production performance; cuts harder materials and can be used at speeds 15 to 100% higher than other high speed steels. Hardened and ground flat tool bits now available from stock. Do you have the remarkable facts on this High Speed Steel?



Vanadium-Alloys

STEEL COMPANY

LATROBE, PA.

COLONIAL STEEL DIVISION . ANCHOR DRAWN STEEL CO.

selecting





is almost

this easy!

The age of push-button steelmaking has not yet arrived. But many a steel buyer has learned that a buzz to his secretary is the first step in making contact with a team of steel experts who can put their special knowledge and skills to work making the right steel to do the job. We have this team at Inland.



INLAND STEEL COMPANY

38 South Dearborn • Chicago 3, Illinois

SALES OFFICES: Chicago • Milwaukee • St. Paul • Davenport

Kansas City • St. Louis • Indianapolis • Detroit • New York



Armor Plate Quenched

Rapidly, Uniformly in Hydraulic Press



By G. A. Leytze
Vice President
The Williamson Heater Co.
Cincinnati

Plates ranging in thickness from ½ to 3 in. are quenched in a 2500-ton HPM Fastraverse hydraulic press. Dies are designed to achieve a rapid and uniform quench over the entire surface area of the plate. Press can handle plates up to 70 x 200 in. Unit is located between hardening and draw furnaces with handling done on roller conveyers. Total pressure applied can be varied to suit different sizes and thicknesses. Most plates are kept flat but some are formed before quenching.

Before homogeneous armor plate coming from steel mills is ready for use in tanks and for other applications, it must be heat treated. In most cases, the plates must remain flat. To assure the required degree of flatness, quenching must be done in a press provided with suitable dies. Otherwise, warpage is likely to occur.

In some instances plates must be formed while hot, just before quenching. In this case also, quenching must be done while the blank is still gripped in the die. Unless confined under heavy pressure, distortion is likely and deviation from the required shape may result. For these reasons, specialized heat-treating and quenching setups are required.

The accompanying photographs showing these specialized heat-treating and quenching operations, were taken in plants of two of the 19 subcontractors of the Standard Steel Spring Co.

Williamson produces today approximately 60

different shapes of homogeneous armor plate for tanks. Many are flat pieces, but some of the largest are formed. Most are of irregular outline with cutouts and drilled holes.

In addition to the fabricating facilities which are comparable to those operated by Williamson in World War II, a new continuous heat-treating line has been added which is one of the most advanced in operation anywhere.

Raw material reaches the south end of the plant by rail spur and is handled to ground storage and thence into the plant by a bridge crane which spans the track, the apron and the shipping dock.

Plate from the mill is rough cut to shape on Radiagraph flame cutters, then loaded onto a roller charger. This starts it through the heat treat line which occupies the entire length of a 400-ft wall of the building.

The pieces first enter a Drever roller hearth hardening furnace. This unit is normally gas fired, but it is equipped with combination burners which will also handle oil. It is fired from both sides in combustion tunnels under a silicon carbide tile hearth, venting through the arch. The burners are grouped in six zones, each of which is furnished with a proportioning type pyrometer controller.

Transit through the furnace is controlled by varying the speed of the rolls on the hearth. In the event of power failure, furnace rolls can be turned manually so that plates can be moved out to prevent possible overheating.

At the end of the heating period, a pulpit operator actuates the final 12 accelerating rolls of

"Plates are kept in constant motion until the proper draw time has elapsed . . . "

the furnace to eject the part on a high-speed elevating and positioning runout section which delivers it to the in-line quenching and forming press. Speedup is so plate will not cool below quench temperature before it gets into the press.

The press is a 2500-ton HPM Fastraverse hydraulic press. It is provided with dies designed to effect rapid and uniform quenching over the entire area of the plates processed. This press can accommodate plates as large as 70 x 200 in. Forming of large heated blanks is also done in this press but smaller size parts are handled in a smaller hydraulic press, using dies of similar type.

Plates ranging in thickness from ¹4 to ³ in. are quenched in the large press. To facilitate and to expedite handling the top face of the lower die is slightly below the level of the roller hearth of the hardening furnace.

Parting faces of both halves of quenching dies, whether flat or shaped for forming, are serrated with shallow channels. These divide the faces into checkerboard patterns. At the center of each checker or square a hole is drilled at right angles to the face. Each hole runs through the die wall and enters an interior channel filled with water under pressure when the die closes. From each hole a short channel extends to each side of the square where it joins a primary serration.

The part in place in the dies, the operator closes the press and starts the water pumps. As soon as the piece is clamped at full pressure, he opens the valves to supply water to the dies. Entering the dies through manifolds of piping and flexible hoses, the quench water simultaneously

sprays both sides of the piece. Water from the dies flows off through grill flooring surrounding the press to a hot well for recirculation.

Formed pieces receive their complete shaping in the press and flat pieces are also pressed in waffle-faced plates for holding maximum flatness during quenching.

The tempering furnace is also a Drever roller hearth unit of the forced air circulation type. Heat is supplied by air mixed with hot gasses generated by external air heaters and delivered through ducts to plenum chambers within the furnace. After being distributed uniformly to the working area, the mixture passes through collector ducts in the hearth back to the air heaters for reheating. Multiple-zone temperature control is effected.


Parts move on power rollers

All rolls forming the draw furnace hearths are power driven. As a plate nears one end of the hearth, the rolls are automatically reversed to turn in the opposite direction and cause plate motion to reverse. Thus, plates are kept in constant motion, back and forth on hearth, until the proper draw time has elapsed.


From the draw furnace, parts move on power rollers directly to the temper quench, where again they are sprayed with large quantities of cooling water. A light hydraulic pressure system is built into this unit with waffle platens for pressure quenching.

Traveling out onto the open discharge table at the end of the heat treating line, parts are individually tested for hardness. A tester mounted over the roller bed makes the necessary impression. Each ball depression is then measured by a micrometer microscope.

Having then arrived at the end of the shop area, parts are handled by Monorail crane onto loading cars for shot blasting in a Pangborn unit, and are ready for fabricating trip back



EMERGING from hardening furnace, armor plate moves on power-driven rolls of positioning and runout table to adjacent form-quench press which prevents quench distortion.



WITH DIES closed, water in form-quench press is turned on. Water travels through holes in dies, is distributed through checkered surface of dies to quench plate evenly.

to the shipping-receiving dock.

First fabricating step is flame cutting to finished shape, including cutouts of various forms. Eight Radiagraphs are available for straight-line cutting, which includes bevels. Larger units, a Travograph and an Oxygraph, are used for automatic shape cutting, under electric eye or magnetic head control.

After being cut to shape, parts pass on to grinding. Torch-cut edges are finished, and bevels are ground. Two reciprocating-head grinders with tracks are used, and three grinders with reciprocating beds. Another machine of the latter type, with a segmented wheel, is used to stack grind a number of parts at one loading. Contoured and cutout edges are finished by hand grinders.

Virtually all work is straightened, usually after grinding. Flame cutting operations produce distortions affecting flatness. And some corrections also need to be made due to heat treating, though the use of pressure during quenching holds this warpage to a minimum.


Flattening or straightening is handled in press brakes. These are equipped with V-block dies and ball transfer heads. Large parts are placed in the presses by fork lift trucks, while smaller pieces are handled by Monorail hoist.

Next step after straightening is drilling. Up to 30 holes are required on some parts, most countersunk and counterbored, while many are tapped. Three radial drills and one upright unit are used. Drills are high speed steel, though some carbide tools are used in counterboring.

Metallurgical inspection is completed with impace testing of Charpy specimens taken from heat treated plates. The original heat identification of all armor plate is preserved through all processing.

A large capacity system using recirculated city water supplies the quantities of quench water needed. Draining from the presses into a hot well, the quench water is routed to a cooling tower by two return pumps at the well. After cooling, tower water is ready for reuse.


Williamson installed its armor plate facilities in a building which had been 40 pct devoted to offices and 60 pct to warehousing. The Trundle Engineering Co. surveyed Williamson's facilities, finding room in existing buildings for the warehouse needs, and recommending a new building for the offices.




FORMED AND QUENCHED armor plate in the die and ready for removal to the draw furnace. Residual streams of water can be seen draining from holes in upper die.



STRAIGHTENING of armor, when necessary, is done in press brake with ball transfer heads and pinch dies. Fork truck moves heavy pieces of plate for this operation.



FOUR-TIER furnace, similar to that used at Williamson, tempers plate after hardening. Power driven roll conveyer from press can be lifted to level of any tier.



FINAL OPERATION is drilling, counterboring, countersinking, and tapping of holes, done in one of three radial drills or in an upright drilling machine.

High speed screw slotter

CUTS SEVERAL HEADS

By John A. Largay
Connecticut Screw & Rivet Co., Inc.
Waterbury, Conn.

Machine is used on all standard sizes and head shapes. Speed twenty times greater than conventional slotters has been achieved. Round head screws require no deburring. Saws have considerably longer life per grind than those on conventional equipment. Reduction of slotting costs has been estimated at 50 pct. Equipment is primarily intended for long production runs.

A new type of machine, capable of slotting more than 2200 screws per minute, has been in successful use for several months at Connecticut Screw & Rivet Co., Waterbury, Conn.

Since February, the machine has been used on all standard sizes and head shapes from a sixtine on up through a \\\^{1}4-20 machine screw. Production has been as high as 2375 blanks per minute on eight-line brass machine screws and 900 per minute on \\\^{1}4-20 round head steel machine screws.

The machine was developed by Waterbury-Farrel Foundry & Machine Co. from designs by Victor Fray of New Zealand. Its unusual speed, as much as 20 times greater than conventional slotters, is mostly due to the greater utilization of the saw, which cuts in more than one screw head at a time.

In operation, blanks are poured into a bowl opening at the front of the machine. From this they drop into a revolving drum, with vanes which lift the blanks up to a wide delivery chute.

The chute drops blanks onto rapidly-revolving rolls which position them and feed them into the conveyer section. The excess spills over the rolls and drops back into the hopper.

At the end of the feed rolls is a clearing mechanism which kicks out improperly-positioned blanks. The rest, head up, are conveyed between

guides by a thin endless steel belt toward the feed-in dial.

This notched wheel received bianks from the conveyer belt and presents them in timed relation to the carrying dial. This dial picks up the blanks with their heads projecting inward and their shanks positioned radially outward. Blanks are clamped into dial notches by a pressure plate. Heads are further controlled by a head ring to hold blanks in place.

The 4-in. saw is located inside the carrying dial, its center of rotation offset from the center of rotation of the dial. The dial turns counterclockwise, and the saw clockwise. The amount of offset, and the relation between saw diameter and inside diameter of the carrying dial, are such that the saw is cutting in several heads at all times.

A stationary cutter near the point where blanks leave the dial removes burrs on blanks with flat or fillister heads. Other types, such as round heads, require no deburring.

As originally planned, the machine was expected to slot about 1200 screws a minute, maximum. But during testing in Waterbury-Farrel's plant, in which Connecticut Screw & Rivet supplied the blanks, it was found possible to modify the original design to bring top speed up to at least 2000 blanks per minute.




FIG. 2—Saw of brush tooth design, right, is preferred over straight tooth type. Curved or hooked teeth seem to have more cutting and less tearing action on the screw head metal.

Considerable experimenting has been done on types of saws. Saws have considerably longer life per grind than those on conventional equipment. Connecticut Screw & Rivet favors a type of saw, which it has been developing, which has curved, or hooked, teeth, as shown in Fig. 2.

This type of saw seems to have more of a cutting and less of a tearing action on the screw head metal. Runs of over 100,000 blanks per grind are not unusual with these saws, and as many as 300,000 blanks have been run before a saw needed resharpening.

Operating problems so far have been almost entirely due to deformed blanks. These can cause jams which interrupt production and may cause saw breakage. Since 100-pct inspection of blanks is not practical, more careful blank production is required, and the slotter operator must be alert for deformed blanks. The problem is not serious when careful blank heading is done.

On the machine now in operation at Connecticut Screw & Rivet, changeover from the speed for one screw to the speed for another is made by changing gears. Changeover requires about an hour. Though this is not an excessive length of time, models of the slotter now in production will have an electric variable speed drive so that no change gears will be needed. An experienced operator can change saws in about six minutes.

Naturally, a machine with such a high output as this is primarily intended for long production runs. It will not replace conventional equipment for slotting screws in relatively small quantities. However, on long runs, Connecticut Screw & Rivet estimates slotting costs are reduced to 50 pct of costs of slotting by conventional equipment.




FIG. I—Waterbury high speed screw slotter in use at plant of Connecticut Screw & Rivet Co., Inc. Speed changeovers for different screws are made by changing gears. Safety guards have been removed in this photo to show more details.



Seeks Key to More and Better Steels

Steelmaking engineers and executives crowded into Cleveland's big Public Auditorium, where the annual Iron and Steel Exposition was held, with one purpose. That purpose—how to get more and better steels out of the nation's steelmaking machinery—gave the annual convention an underlying, muted note in harmony with the serious problems facing the industry. High interest was shown in Jacques Sejournet's paper on steel extrusion.

Ways and means to greater and more efficient production of steel was the central theme of the exposition of the Association of Iron and Steel Engineers held in the Public Auditorium at Cleveland, Sept. 30 to Oct. 3.

Above the noise at the exhibits—and they were reasonably quiet this year—if the visitor looked closely he could see an outline of some interesting trends that are now developing in the steel industry.

This year, for example, materials handling justifiably got a big play. Air conditioning entered the steel-making picture in an important way for the first time in the industry's history. Continuous casting got a lot of deserved attention. The number of electrical exhibits was greater than at any previous show, reflecting the trend toward automatic controls for all phases of steel processing.

If anyone attending the Cleveland Convention was thinking about the late, lamented steel strike, it wasn't evident. All indications pointed to the fact that all the stops in the steel industry are again pulled out for all-out, top quality peak production.

Models—both working and female—got a lot of attention at Cleveland. At the AISE show there were scale models of blooming mills, a continuous billet and slab mill, and other intriguing exhibits. Supplementing the model displays were colored moving pictures showing full-size equipment at

work in the nation's steel mills. Exhibits were both impressive and educational.

Of outstanding interest among the technical papers was the presentation, "The Extrusion of Steel-Equipment, Operation and Production," by Jacques Sejournet, general manager, Comptoir Industriel D'Etirage et Profilage DeMetaux, Paris, France. First press used for studying the



MATERIALS HANDLING on a big scale will be required at the new iron ore development at Puerto Ordiz, Venezuela. Link Belt showed a continuous belt conveyer which handles 6000 tons of ore per hr.

extrusion of steel was described as well as a new 1500 ton press now installed at Persan, France. Both existing and future extrusion presses for steel and nonferrous metals were included.

The author emphasized the fact that extrusion presses for a wide range of products will require a number of special features. While low alloy steels can be extruded, he said, at normal pressures for small tonnages, presses for common steels should be specialized if production costs are to be held down.

Preparation of billets, heating practice, piercing, untwisting, straightening and pickling were described. Rolling costs and extrusion costs are compared in the paper.

The new Fairless Works, destined to get a lot of attention in the next year or two, had a prom-



AIR CONDITIONING is moving up fast in the steel industry. Shown here is a "quiet, safe, comfortable" operator's pulpit built by James Campbell Smith, Inc. The cabinet is equipped with a television to help the operator follow distant operations. Applications include ingot buggies, rolling mills.



SCALE MODELS made it easy for AISE members to visualize an entire operation. Morgan Construction Co. drew attention with its operating model, scale 1/8 in. = 1 ft, of reversing blooming mill, 6-stand and 4-stand vertical-horizontal continuous billet and slab mill. Model included transformers, shears, cooling beds.

inent place on this year's AISE program. Carleton Lord, Materials Handling Engineer, presented an interesting paper, "Material Handling Layout of Blast Furnace and Coke Plant at Fairless Works." The author describes the layout and equipment for handling both present and future raw materials.

New foreign ores for Labrador, Venezuela and Liberia and U. S. deposits of low grade Taconite ores are destined to become important new sources of iron, R. P. Bremner, Youngstown Sheet & Tube Co., reminded the AISE. Economic factors favoring open pit ores have increased in recent years, the speaker said, and this is reflected in interest in open pit foreign deposits.

Results to date in the use of No. 1 B domestic oil to replace imported tongue oil used for cold-rolling steel have been "uniformly good." This new lubricant is now being tested in the majority of U. S. and Canadian tinplate mills, according to Robert C. Williams, the Ironsides Co.

A new high temperature alloy capable of operating temperatures up to 2200°F was described by M. N. Ornitz and R. H. English, National

CONVENTION HIGHLIGHTS

- Latest entrant in the continuous casting race is Koppers Co. Its display, centered about a built-to-scale model of a continuous casting machine, was filled to overflowing most of the week.
- Tapered roll necks were actually removed, replaced and gaged with a new air gage at the Timken Roller Bearing Co. booth. Trained demonstrators kept interest at a high pitch. Also shown were new 4-row tapered bar steel mill roll neck bearings.
- A newly developed powered hydraulic crane bridge brake system shown by Wagner Electric

- Corp., started a lot of conversation at the show.
- Cast refractories are getting a lot of attention. Steelmen are watching this development closely. Shorter downtimes and lower furnace repair costs are promised.
- Use of colored photographs, transparencies, black and white enlargements to effectively tell convention visitors the company story, is growing. Colored transparencies and black and white enlargements used by McDowell Co., Inc., told an impressive story of outstanding accomplishments in construction and engineering.

"New combustion controls, quench and tempered casing and cast refractories of high interest . . ."

Alloy Steel Div., Blaw Knox Co. Designated as NA22H, the new alloy has good resistance to oxidation and unusually high strength.

Other speakers described the growing use of chromium plating by iron and steel mills to reduce maintenance costs, oxygen control in the openhearth, new combustion controls, quench and tempered oil well casing, cast refractories, radiation gages, mechanized hot scarfing and other subjects of current interest.

AISE members elected John L. Young, vice president, engineering, United States Steel Co., president for 1953. Other new officers include: James D. O'Roark, Weirton Steel Co., secretary; W. H. Collison, Great Lakes Steel Corp., treasurer; E. L. Anderson, Bethlehem Steel Co., first



EASY-ON-THE-EYES models told the Westinghouse Service and Maintenance story in pantomine. The story of Westinghouse renewal parts was presented at a 3-stage miniature theater. The crowds loved it.

vice president; John H. Vohr, Gary Works, United States Steel Co., second vice president.



NEW OFFICERS OF AISE for 1953: John L. Young, president, left; E. L. Anderson, first vice president; John H. Vohr, second vice president; W. H. Collison, treasurer; James D. O'Roark, secretary.

NEW BOOKS

"Fundamentals of Physical Metallurgy," by Ralph Hultgren. A valuable text on this increasingly important phase of metal engineering. Explains the phase reactions predicted from phase diagrams. Effects of microstructure on mechanical properties of alloys are discussed. Topics include: Modern theory of martensite formation, dislocation theory, the future of titanium, laws of metallic crystal chemistry, deformation, recrystallization. Prentice-Hall, Inc., 70 Fifth Ave., New York 11. \$9.35, 395 p.

"Cutting Gear Teeth On A Milling Machine." A revised and rewritten edition of a useful pocket booklet. Cincinnati Milling Machine Co., Cincinnati 9. Free. 60 p.

"Fachworterbuch Werkzeuge," by Henry G. Freeman. An English-German dictionary of technical terms, companion book to a previously issued German-English dictionary. W. Girardet, Gerswidastrasse 2, Essen, Germany. \$6.00. 390 p.



Titanium ingot producing locations

Titanium

our No. 1 problem metal

By D. I. Brown Technical Editor

Part II

Titanium castings containing from zero to 0.015 C have been made by skull melting methods. New alloy powders soon to be made available promise to help solve some of the difficulties in melting homogeneous alloy ingots. It is possible that the price of sponge made by magnesium reduction might be lowered in the near future. Industry is in the process of working out direct chlorination processes of ilmenite to replace rutile as principal raw material for metal production.

Titanium ores are found abundantly in most parts of the world, but many known deposits are not large enough to be considered of economic importance. The two major titanium ores are ilmenite and rutile. United States is the largest producer of ilmenite which contains 43 to 66 pct TiO₂. Australia ranks first in the production of rutile which contains 93 to 97 pct TiO₂. The third source of the metal of importance is leucoxene which is chemically altered ilmenite in which hydrogen has replaced some of the iron. Deposits of this ore occur in this country.

Domestic production of ilmenite from 1941 to 1951 is shown in Table XIX. As yet a very small fraction of this ore has been used to make titanium sponge. Most of our metal production has been from rutile. Consumption from 1948 through 1951 of both of these ores classified by end use is shown in Table XX. The major domestic sources of ilmenite and leucoxene are shown in Table XXI.

The titanium metals industry is in the process

of adapting the ilmenites to direct chlorination processes for the basic raw material ${\rm TiCl_4}$ so that it won't be too long before rutile will not be the major ore for metal production. One of the problems in chlorination of ilmenite is that about half of the product of chlorination is ${\rm FeCl_2}$ and ${\rm FeCl_3}$. Before the ${\rm TiCl_4}$ containing these impurities can be used the iron chlorides must be removed either by boiling off the ${\rm TiCl_4}$ or some other method. It is possible to take the ${\rm TiCl_4}$ and burn it, the products of combustion being ${\rm TiO_2}$

DOMESTIC ILMENITE PRODUCTION (net tons)

	Production	Shipr			
Year	Gross Weight	Gross Weight	TiO ₂ Content	\$4,094,353 4,878,917 5,029,490 5,793,973 6,212,348 5,606,589	
1941-45 (avg.) 1946 1947 1948 1949 1950 1950	383,745	183,189 282,768 336,061 381,508 389,234 452,370 510,840	83,098 130,624 157,328 177,447 186,535 230,826 261,982		

Includes a mixed product containing altered ilmenite, leucoxene, and rutile.
 Source: U. S. Bureau of Mines.

Part 1 of this article, covering applications, fabrication, forging, welding and machining, appeared last week, THE IRON AGE, Oct. 9, p. 260.

TABLE XX

U. S. CONSUMPTION, RUTILE AND ILMENITE

Product	(Gross Wt.)	Rutile (Gross Wt.)
1942	257.535	10.616
1042		
40.44	302,822	17,634
1048	360,941	14,813
1945	381,178	9.791
1946	404,283	7.134
1947	479,524	7,692
Pigments (manufactured titanium dioxide)1	1558 448	2
Welding-rod coatings1	145	7.885
Alloys and carbide	6.377	952
	0,3//	175
	0.0	31.218
Miscellaneous	30	31,218
Total	565,000	10.230
1949:		
Pigments (manufactured titanium dioxide)1	505.432	2
Welding-rod coatings1	165	6.399
Alloys and carbide	4.969	660
Ceramica	4,808	143
	42	44.686
Miscellaneous	42	4,000
Total	510,608	411,888
1950:		
Pigments (manufactured titanium dioxide)1.4	671,335	2
Welding-red coatings1	210	9.218
Alloys and carbide	7.666	1.454
		195
Ceramics Miscellaneous	33	854
THIS CETTALIEOUS	33	004
Total	679,244	11,721
951:		
Pigments (manufactured titanium dioxide)1	703.068	11.708
Welding-rod coatings1	258	2.939
Alloys and carbide	10.024	265
	12822	
Miscellaneous	13	2.314
Total	713.363	17.226

^{1 &}quot;Pigments" include all manufactured titanium dic..ide, consumption of which in welding-rod coatings was 1,383 tons in 1948, 1,082 tons in 1949 and 1,439 tons in 1950.

and Cl_2 . Thus the TiCl_4 from ilmenite could be used either as a raw material for titanium sponge manufacturing or as TiO_2 for the pigments industries.

The chief reason the titanium industries, of which the major industry is pigments, want to use ilmenite is that we have good domestic sources and eventually they hope to lower their unit costs of ${\rm TiO_2}$ for pigments and ${\rm TiCl_4}$ for metal. Ordinarily ${\rm TiO_2}$ for pigment is made by dissolving the ilmenite in ${\rm H_2SO_4}$. The iron and titanium sulphates are then dissolved in water and the iron sulphate crystallized out of this solution. The titanium sulphate liquor is than hydrolized with steam and ${\rm TiO_2}$ is precipitated out of solution. This product must be washed and sorted.

The rutile crystal has the highest opacity or hiding power of any white pigment and the best method of producing rutile crystals is to burn TiCl₄ as previously mentioned. These facts indicate why all the chief pigment producers are basically interested in ilmenite or Sorel slag and coincidentally they are vitally interested in titanium, as TiCl₄ is common to both the pigment and the metal industries.

Slag from Quebec Iron & Titanium Corp., Sorel, Canada, is being tested for both pigments and metal production. This slag contains 75 pct TiO₂, around 5 pct Fe, and is concentrated from a hematite-bearing ilmenite which contains 35 pct TiO₂. These huge deposits in Canada plus that of this country insures us of an adequate raw material supply.⁶

Rutile costs \$140 to \$160 per ton compared to \$16 to \$20 per ton for iron bearing ilmenites. Costs of raw materials, whether leucoxene, regular ilmenite or rutile ores are used, are fairly low. One pound of rutile costs about 7¢ to 8¢ and this will make about 2 lbs of TiCl₄ so at best using the most expensive ore only 4¢ worth of raw material is used to make 1 lb of TiCl₄ from which titanium metal is reduced. The present market price of TiCl₄ runs between 40¢ and 47¢ per lb. Usually 4 lbs of TiCl₄ are required to make 1 lb of sponge.

The use of 70 pct ${\rm TiO_2}$ slag from the Sorel plant of Quebec Iron and Titanium might change the picture cost-wise. At the present price of slag, \$40.00 gt f.o.b., Sorel, raw materials to make 1 lb of ${\rm TiCl_4}$ would cost but $1 \rlap/\epsilon$. These estimated costs are advanced only to illustrate that raw materials costs are negligible compared to the sponge selling price.

The magnesium reduction process to produce titanium sponge is expensive to operate. It is a batch process which produces 1 ton batches of sponge. See Fig. 1, Part I, The Iron Age, Oct. 9, p. 260. Although the MgCl₂ is now being reused through electrolysing and therefore costs have been reduced, the entire process does not lend itself to cheap continuous operation.

At present there is no shortage of sponge. Du Pont, making 2 to $2\frac{1}{2}$ tons per day, sells to DMPA what they cannot market to the ingot makers. About 300 tons of sponge are now in stockpile. Originally \$5 million was set aside by General Services Agency for this purpose. The original contract expired in March 1952 but was extended to Jan. 1953 and unless large orders

TABLE XXI

DOMESTIC ORE SOURCES

Location	Ore	Producer
California Los Angeles county	ilmenite	Ferro Titan Minerals Co.
Florida Starke county	see below* ilmenite & rutile ilmenite & rutile	E. I. du Pont de Nemours & Co. Rutile Mining Co. Florida Ore Processing Co.
New York Essex county	ilmenite	National Lead Co.
North Carolina Caldwell county	ilmenite	Yadkin Mica & Ilmenite Co.
Virginia Nelson county	ilmenite	Calco Chemical Div. of America Gyanamid Co.

^{*} Altered ilmenite, leucoxene and rutile.

⁻ Included in "Miscellaneous" in order to avoid disclosure of individual company operations.

Includes rutile used:) make pigments.

⁻ includes a mixed product containing altered ilmenite, [eucoxene, and rutile used to make pigments and metal.

Source: U. S. Bureau of Mines.

"It is common practice for each melting unit to blend and mix the sponge . . ."

are placed before then this contract will again have to be extended.

The sponge shipped by Du Pont to stockpile is good sponge capable of making all of today's alloys and most of the commercially pure types of titanium. Tests made on shipments both by Du Pont and U. S. Bureau of Mines, College Park, show all shipments to be below the specifications, shown in Table XXII with much of it between 140-180 BHN. Original sampling and blending of different batches have been vastly improved by Du Pont as has the quality. As yet there is little correlation between sponge hardness and metal strength or hardness melted from different sponge shipments. It is common practice for each melting unit to sort out, blend and mix the sponge shipments to suit its particular requirements. Rem Cru, Republic Steel and Mallory Sharon all report that sponge quality




FIG. 18—Part of Bureau of Mines new titanium sponge pilot plant showing ten distillation furnaces installed; five furnaces are complete with individual vacuum pumps. Retorts in foreground have been lifted from the furnaces and placed in cooling stands.

TABLE XXII

STOCKPILE SPONGE SPECIFICATIONS

	Nitrogen	Iron	Magnesium	Hardness		
Original	0.05 max	0.25 max	0.10 max	250 VHN max		
Latest	0.03 max	0.25 max	0.10 max	225 VHN max		

TABLE XXIII

POWER CONSUMPTION AT HENDERSON*

Operation	KWH per th
Feed separation	2.0 .60 .05 2.30
Total	15.30

* Estimated.

^{°°} Note: Use gas heat, if vacuum distillation is done using electric power 3.5 KWH per lb would be needed.




FIG. 19—Cross section of electrically heated distillation furnace shown in Fig. 18 with retort and titanium chips in place. This type furnace is used by the Bureau of Mines for purification of titanium sponge by vacuum distillation of residual magnesium and magnesium chloride. Distilled impurities condense on the retort furniture. The furnace is evacuated as well as the retort. This method permits the use of a thin gage container instead of the more costly heavy wall retorts shown in Fig. 1 Part 1.



FIG. 20—View of sponge pilot plant operated by Crane Co., Chicago, III. This is a magnesium reduction process. Crane Co. buys the TiCl₁ as they do not have facilities to chlorinate the ore. So far Crane Co. has not sold any sponge to the melters.

continues to improve and Rem Cru is now receiving sponge in carload lots.

A melter cannot produce a titanium ingot softer in hardness than the sponge used for that ingot so that sponge hardness which is supposed to be a measure of impurities is only incidental to the hardness or purity of the melted ingot or the product rolled from it. Depending on melting methods and furnace techniques the hardness of the ingot metal will always be harder depending on final oxygen, nitrogen, carbon, hydrogen and alloy content. Because analysis methods, particularly that of oxygen are difficult, expensive and of questionable accuracy, the hardness of a melted button of sponge is generally used as a measure of sponge purity. One company melts a large button and rolls it on a small hand mill into strip. The hardness of the strip is the sponge quality criterion in this case.

Government money has been advanced for two sponge plants; the Du Pont plant to make 2700 tons a year will not be in operation before 1954; production by Titanium Metals Corp. at Henderson, Nev., is far behind schedule. Titanium Metals Corp. which started operation in Oct. 1951 has been producing sponge at Henderson, Nev., on an average rate of 1 to 1½ tons per day. It was hoped that 10 tons per day would be coming out of this plant by now but production difficulties, general market conditions and many other factors have prevented them from reaching that goal.

The plant has a power contract for 151 million KWH per year from nearby Hoover Dam. This power should be sufficient to make the ultimate tonnage of 10 tons per day. A total of about 15 KWH are required to make 1 lb of titanium ingot at Henderson. Power breakdown by operation is estimated in Table XXIII. Even had Henderson reached full production on schedule the combined sponge production of all four existing plants would have been far below the figures for which government is calling.

The new sponge plant just completed by U. S. Bureau of Mines, at Boulder City, Nev., see Figs. 18 and 19, will produce sponge as needed for government stockpile or Ordnance Corps. Ordnance has one sponge specification, MIL-T-12118 Ord, which specifies a sponge of extra high purity with a maximum melted button hardness of 140 BHN. This can't be compared to iodide sponge which runs around 90 BHN but it will be somewhat purer than that produced by other makers, see Fig. 20.

It is very likely the sponge price will be lowered in the near future. The new price won't be as low as that incorrectly reported in the daily press but \$3.00 per lb sponge is a definite possibility and will probably be offered even before the two new government plants have reached full capacity. With a \$3.00 sponge material at least \$4.00 a lb can be shaved off all commercially pure titanium products like bars, billets, sheets, etc. The lower sponge price may not materially reduce the price of alloys for some time however.

Titanium Melting Techniques

General arc melting practices for melting titanium sponge into ingots are similar in all shops. They are similar in that all shops use water-cooled copper molds in which the melted sponge is deposited in layers and the melting chamber is an air-tight vacuum in which inert atmospheres of helium and argon or both are maintained.

Methods of feeding the carefully sized sponge from air-tight hoppers mounted over the arc furnace are also similar. The chief difference in arc melting practice among the four major producers is found in the type of electrodes used. Carbon, tungsten and consumable electrodes have been used to date. There is no doubt that a consumable electrode furnace, like the Herres furnance, operated by Titanium Metals Corp., is the ultimate goal of all producers but these 5-ft electrodes are expensive and difficult to make. Little is known concerning the ease of operation when using such electrodes except that control of the melting operation is known to be most critical.

One of the earliest melting problems was to

"Ingots are improving . . . best surfaces are produced with consumable electrodes . . ."

control the melting rates of the sponge as it was gravity fed into the arc zone. Using consumable electrodes the melt-off rate of the electrode as well as the fusion rate of the sponge and alloy additions must be correlated. In both cases length of the arc and consistent and proper power input are necessary. If the arc goes out it generally means a new ingot must be started. If too high a temperature is built up in the melting zone other problems arise, such as excessive elephant-skinned ingots which cause higher scrap losses in machining the surface of the ingots, see Fig. 21. Ingot surfaces are improving rapidly and here again the best surfaces are produced with consumable electrodes.

Generally, tungsten electrodes melt the sponge at faster rates than carbon electrodes. For the same degree of fusion, using tungsten at $50~\rm v$ and $100~\rm amp$, the required current with carbon electrodes would run around $50~\rm v$ at $1000~\rm to$ $1200~\rm amps$.

Melting rates vary considerably from shop to shop but generally in a single electrode furnace, see Fig. 22, about 4 to 6 lb per min. is usual. Power consumption varies with furnace size, number of electrodes and type of electrodes. Usually the power requirements vary from 4 kw-hr to 1.50 kw-hr per lb melted. The first figure is for carbon electrodes while the latter figure is for consumable electrode melting.

Contamination of arc melted titanium usually comes from the electrodes. With carbon electrodes it is difficult not to pick up some carbon even with the best techniques. Rem Cru has achieved great success, however, using carbon tipped electrodes. The carbon averages under




FIG. 21—This ingot being conditioned at Rem Cru for roll cogging or forging weighs about 1000 pounds, which is the average ingot weight being produced at the moment.




FIG. 22—Top of the arc melting furnace at the Mallory Sharon Titanium Corp., Niles, Ohio. This furnace is typical of the single electrode being used by other producers. The electrode control shaft is shown in the center, bottom of the feed hoppers can be seen at extreme top of the photo.

0.10 in this shop. Fig. 23 is an overall view of Rem Cru's melt shop. Carbon acts as a grain refiner in titanium so that carbon contents up to the limit of solubility, 0.20 C max, impart strength to the metal without loss of ductility as does silicon. The reason producers don't melt out at the maximum carbon solubility content is that this carbon is detrimental to good ductility and particularly to ductile welds.

Contamination from tungsten tipped electrodes was one of the early problems, one of which was caused by splashing of the melted sponge. Some of the first sponge made contained too much MgCl₂ which was blamed for causing the splashing. Today's sponge is much lower in MgCl₂ but tungsten contamination is still a problem.

Generally, the molten titanium that reaches the tip of the electrode corrodes the tungsten along the grain boundaries and if allowed to proceed too long causes these grains to break off from the electrode and fall into the top of the ingot where they do not go into solution. To avoid these possibilities it is general practice to start a tungsten arc by using a magnesium ribbon to prevent getting any melting titanium on the electrode tip. Another practice is to melt the sponge using as long an arc as possible. The latter practice prevents contamination but a long arc is sometimes hard to maintain and even if kept constant the melting rate is greatly slowed down.

The next few years will see great improvements and changes in the type of arc melting furnaces. Although consumable electrodes made from sponge can be formed by briqueting, extruding and sintering or forging these methods




FIG. 23—Rem Cru melt shop at Midland, Pa. showing the three arc furnaces now producing plus the partially erected 24 in. diam furnace. Size of this melt shop will soon be greatly expanded.

are expensive. The electrodes could also be made in a small furnace as a cast ingot, but this entails double melting and possible contamination in the cast electrode. It is also possible to make a consumable electrode in which the alloys would be contained. Any method to produce a larger molten pool of metal will tend to produce better quality ingots at cheaper costs. Multiple arc furnaces are the next step which if combined with a good scrap using practice could greatly lower ingot costs.

The melting of alloys has presented the problem of segregation which must be solved. Because the metal is deposited in stalagmite form in the water cooled mold, proper alloy distribution is controlled by rate of fusion not by solution rates in a molten pool. Even larger molten pools under the electrode won't cure all the present troubles as the metal is molten for too short a period to prevent rapid freezing before the alloys are well mixed and homogeneously distributed.

A step in the direction of better alloy additions has been taken by the Electro Metallurgical Co., a division of Union Carbide and Carbon Corp. As in the alloy steel industry, the best way of introducing alloying metals during the arc melting of the titanium ingot is through the use of master alloys. Present methods of producing the

master alloys are either to make large ingots of the alloy and crush to size, or to bond microhomogenized powder. The Electro Metallurgical Co. has developed a series of master alloys, see Fig. 24, especially designed to have a high degree of uniformity of composition, to melt readily, and to handle satisfactorily in the different dispensing mechanisms.

At present, titanium master alloys have been tested in very limited quantities to add manganese, iron, chromium, aluminum, vanadium; or iron and chromium simultaneously. Other alloys can be readily produced as required by the titanium industry. The alloy content of these master alloys will vary depending upon the alloy in question; for example, a 75 pct Ti—25 pct V alloy has been produced, and other master alloys have been made containing 50 pct alloying ingredient. A pilot plant is now in the course of construction to produce these alloys.

Horizons, Inc., is working on a new reduction process under the auspices of Office of Naval Research. This material produced on an experimental basis is in the form of thin small particles of titanium. It is hoped that this material can eventually be used to replace sponge as charge material for arc melting. These particles are exceptionally pure but their light weight does not lend them to present melting practice. In order



FIG. 24—Samples of the titanium master alloys made experimentally by Electro Metallurgical Co. Mesh size of the sample on the left is 100xD. The coarse material on the right is roughly $\frac{1}{2} \times \frac{1}{4}$ in. screen size.

"By 1st quarter . . . ingots weighing up to 2 tons will be available . . ."

to properly gravity feed, these particles may have to be compacted into a heavier mass.

To date the largest arc furnaces in operation are believed to be 19 in. in diam. These furnaces are casting ingots weighing up to 1 ton. By 1st quarter 24 in. diam furnaces will be operating and ingots weighing up to two tons will be available. Some of the new furnaces will be of the continuous retraction type so that ingot size will be chiefly restricted by the length of the cut-off multiple that can be satisfactorily handled.

Induction melted ingots are available from most producers, see Fig. 25, but little market exists for this product because carbon or graphite crucibles are used. Carbon contamination can be decreased by a number of methods but even the best practice short of skull melting (detailed under casting) produces a metal too high in carbon for many uses. Combination induction and arc furnaces have been built and tested. In this practice the induction coils heat the charge, either all scrap or all sponge or any combination of each, short of the melting point. At this point one or more electrodes mounted in the top of the furnace are struck and plunged into the charge. Fast melting and pouring either through a plug in the furnace bottom or a side door is then necessary and critical lest contamination from the crucible and the electrodes ruin the heat.

Generally, alloy segregation in induction melted ingots is less than in arc melted material. The large molten pool plus the stirring action of the current decrease segregation. Induction melting can utilize scrap which need not be critically sized as is the scrap used in arc melting. Up to 25 pct scrap charge has been used by one company in arc melting but it is not believed to

be an economical practice. Scrap for arc furnace remelting must be cut $\frac{1}{2}$ in. max dimension. It must be clean of oil, grease or any other contaminant. In order to use turnings the scrap chips must not be discolored by an oxide scale lest this contamination be picked up also. Titanium is so prone to oxidation, when being severely cold worked, that even crushing of sponge is done in partial vacuum or under atmosphere protection to preclude any oxide formation.

In research projects are melted ingots are sometimes turned down into all chips and these chips used as charge material for remelting the actual ingot to be used for experimental purposes. However, this is not a commercial practice.

Titanium scrap, now a drug on the market, will eventually be used by the titanium industry. Such a process will do for titanium what the Siemens' openhearth furnace did for the steel industry. Until a scrap process is developed and used in tonnage titanium scrap will be used mostly as a substitute for ferrotitanium in steelmaking.




FIG. 25—Induction melting furnace shop of Mallory Sharon at Niles, Ohio. The two smaller furnaces are 500 lb units. The furnace at the right is a 1000 lb induction melting furnace.

All of the problems found in melting titanium plus a few more are encountered in casting the metal. Contamination again is the key. Because casting requires that all the metal be molten prior to pouring contamination possibilities are greatly increased as the molten metal must be held in some kind of a container. Titanium digests all known refractories although graphite resists this attack to some degree.

Oxyfluoride refractories are thought to be superior to any known oxide compounds with respect to non-contamination but further research is needed before this material can be proved. Another special project to investigate possible

refractories tested 3 metals and shell molds made of silica, silicon carbide, zirconia, aluminum and zircon.⁸ Results of these tests to be published shortly in these pages are not conclusive but at least good surface, reasonably sound castings and minimum contamination of 0.002 on a ½ in. cross section were achieved and future possibilities look fairly bright.

Two major attempts to make titanium castings have employed graphite molds. With good skull melting techniques the carbon can be held from practically zero to 0.015 max. In both cases to be cited here the melting furnace and the mold are encased in a vacuum chamber into which




FIG. 26—Schematic cross-section of vacuum skull casting furnace developed by Rem Cru Titanium Corp. under Ordnance Corps contract. The skull shown in color acts as a refractory to contain the molten metal.

inert gases are introduced and both employ $skull\ melting$ techniques.

The first method, developed by Rem Cru Titanium, Inc., under an Ordnance Corps research contract is briefly outlined wherein castings up to 100 lb have been made: "The expedient which circumvents melting contamination on a commercial scale today is that of arc melting and freezing a thin skin from the melt on a watercooled copper crucible. Thus the titanium is melted in itself. However, the amount of metal molten at any time is quite limited because of the rapid heat transfer through the water-cooled copper mold. Ingots are formed in such equipment by gradually feeding in the charge and melting it. Only the very top of the ingot is molten.

This is satisfactory for ingots made for forging or rolling. Casting shapes, however, requires that all the metal in the casting be molten just prior to pouring. For sometime Rem Cru has been developing equipment and procedures to accomplish this while avoiding crucible contamination by maintaining a thick skull of solid titanium between the crucible and a deep pool of molten titanium.

The only method yet found to accomplish this is by juggling of heat inputs, losses and transfer rates so a sufficiently gradual and steady thermal gradient is established between the arc-heated pool and the crucible. By proper controls, an inch thickness or more of titanium remains solid in contact with the crucible. Fig. 26 shows a sketch of a tilt-pour furnace which illustrates this.

The heat transfer controls employed can read-

ily be appreciated by examining this sketch. The primary source of heat is a direct current arc in which a graphite electrode is the cathode and the molten pool is the anode. The arc circuit is completed through the conducting graphite crucible. Thermal insulation is provided by granular alundum which is packed around the crucible. This refractory layer is surrounded by water-cooled copper coils which can add or subtract heat depending upon whether an induction heating current is employed or not.

The entire assembly, including the graphite mold, is contained within a vacuum-tight shell. The system is evacuated prior to arcing to remove contaminating gases. Purified argon is then admitted, the arc is struck, induction heating or water cooling is applied as required and the melt is poured when thermocouples in the crucible indicate the skull has reached its minimum desirable thickness.

Laboratory evaluation of skull melting and pouring has been relatively successful at Rem Cru. A cylindrical casting over 100 pounds in

TABLE XXIV

MECHANICAL PROPERTIES: CAST TITANIUM

Composition	0.2 Yield Strength (psi)	Ultimate Tensile Strength (psi)	Elongation (% in 1")	V-Notch Charpy (foot pounds)	
92Ti-4Mn-4A1 93Ti-7A1	94,100 98,500	118,000 109,400	9 13	17 30	

Source: Rem Cru Titanium, Inc.

weight and free from crucible contamination has been made from the furnace. Many smaller castings have also been made.

Further experimental evaluation of the skulltype titanium casting furnace is being conducted by Rem Cru under Ordnance Contract DA-10-059-ORD-188. The preliminary mechanical property results shown in Table XXIV have been obtained on skull-cast titanium alloys under this contract.

These as-cast results compare favorably with data from wrought materials of the same nominal compositions. The production of strong, tough titanium castings is eventually possible. But a series of very formidable technical and economic difficulties exist due to the inherent vulnerability of the metal to contaminations."

The other casting method, closely parallels the experience of Rem Cru except that definite shapes weighing less than 10 lb are the major goal of this research: "A technique has been developed for casting titanium alloys without contamination with carbon or other elements. This furnace

"Cylindrical castings of 100 lb, free from crucible contamination have been made . . ."

"Electric arc maintained between a water-cooled tungsten electrode and the Ti skull . . ."

utilizes a direct-current arc as the source of heat and a skull of solid titanium as the container for the bath. This furnace, Fig. 27, incorporates a water-cooled copper crucible as the melting chamber with the mold cavity attached to one side of the crucible. A retractable water-cooled copper door covers the mold until the bath is ready for pouring. The furnace is mounted on trunnions so that the whole assembly may be tilted to pour the casting.

Melting is carried out with a direct-current electric arc maintained between a water-cooled tungsten electrode and the titanium skull which forms the anode. A purified argon atmospher maintained in the furnace cavity prevents contamination of the molten metal during the melting and casting operations. A flexible gas-tight connection is formed around each of the movable water-cooled leads by a suitable sleeve of gasmask hose. The mold is of CS grade graphite machined to a shape which provides the neces sary gates and risers and permits removal of the finished casting without damage. No other mold refractory has been found which does not contaminate or react with the contained titanium during casting.

During melting, the arc is directed onto the top surface of the skull which is about 6 in.




FIG. 27—Cross section drawing of the skull melting furnace developed at Frankford Arsenal. The mold which is also encased in the vacuum furnace is machined from solid graphite.



FIG. 28—This experimentally cast connecting rod weighs 1/2 lb. The mold and cores were made of solid graphite machined to shape. Hardness of the rod as cast, 155 Bhn.

square by 2¼ in. deep and weighs about 14 lbs. The arc is maintained at about 1100 amp and 25 v for 15 min to establish a molten bath. The surface layer of the skull becomes molten and when equilibrium has been reached, the mold door is raised, the power is shut off, and the whole furnace is tipped to pour the bath into the graphite mold cavity.

In this method the poor thermal conductivity of titanium is utilized to permit the formation of a titanium bath of adequate size in a container formed by the solid titanium skull. A thin slab of solid graphite between the copper crucible and the titanium skull further augments the poor thermal conductivity of the titanium to permit a higher degree of superheat in the molten bath. Obviously, in this technique the skull must be of the same composition as that desired in the resultant casting. In Fig. 28 is shown a connecting rod cast from the furnace."¹⁰

Just as in all other phases of titanium the big pressure for castings has come from the Military. Eventually satisfactory techniques will be perfected and new refractories will be found. Until then it is believed that forgings will have to be used. One of the reasons castings were wanted originally was that high machining costs made the use of forgings very expensive. Machining costs are coming down as the industry gains experience with the new metal, see Part I, The Iron Age, Oct. 9, p. 278.

References

⁶ Brown, D. I., "More Titanium Oxide Now Available," The Iron Age, Nov. I, 1951, p. 119, Part I. The Iron Age, Nov. 8, 1951, p. 129, Part II.

Private communication Sept. 12, 1952.

^{*} Private communication Sept. 21, 1952.

^o Supplied by W. L. Finlay, R. F. Malone and P. F. Darby, Rem Cru Titanium, Inc.

¹⁰ Supplied by O. W. Simmons, R. E. Edelman and H. Markus, Frankford Arsenal, Ordnance Corps., U. S. Army.

Moly Based Metal Ceramic

designed for high temperature use


Development of a metal-ceramic, D-1922, which can withstand the high temperatures encountered in jet aircraft and guided missiles has resulted from 2 years research by P. R. Mallory & Co., Inc.

In 1950, a survey of 450 firms which previously had expressed an interest in materials of this nature showed 45 pct of failures were attributed to oxidation, see table.

Based on this study, research was directed toward production of a material with characteristics necessary to withstand thermal shock, resist oxidation, and operate dependably at temperatures to about 2700°F. From these efforts, Mallory produced the D-1922 metal-ceramic. The material is a hybrid incorporating molybdenum disilicide and suitable ceramic components.

Properties of the D-1922 metal-ceramic are as follows:


- 1—Modulus of rupture (determined on square specimens acting as single-centered loaded beams): 26,000 to 30,000 psi at room temperature and in excess of 2000 psi at 1000°C.
 - 2-Hardness: RA 80-100 at room temperature.
 - 3-Density: approximately 5 g per cu cm.
- 4—Electrical resistivity: 80 microhm centimeters at 68°F.
- 5—Temperature coefficient of resistivity: 0.26 pct per deg F between 68°F and 570°F.
- 6—Thermal expansion coefficient (average linear): 4.05 x 10⁻⁸ in. per deg F between 68°F and 1470°F.
- 7—Thermal shock: Will withstand, without failure, a minimum of 25 cycles from 2460°F to an air blast.
- 8—Oxidation resistance: Shows a weight gain of 0.60 milligrams per square centimeter for a one-hour heating at 2550°F.



PRESS AND FURNACE setup used in making D-1922 metalceramic at the P. R. Mallory Co., Inc. Material may be machined in "green" condition; ground after firing.

METAL-CERAMICS SURVEY

Reasons for Failure		Pcl
		45
Low Thermal Shock Resistance		28
Low Abrasion Resistance		8
Low Impact Strength		5
Others		 14
Working Temperatures, Deg. F		Pe
Room Temperature to 932°		10
933° to 1832°		25
1833° to 2732°		40
Over 2733°		25




VARIATION: Hardness with temperature, D-1922 metalceramic.

D-1922 is fabricated by powder metallurgy techniques. The material can be turned, drilled, filed, and cut in pre-fired or "green" condition. After the material has been fired, it may be cut by an abrasive cut-off disk and machined by grinding.

Potential uses of the material include: kiln furniture, saggers, gas turbine parts, combustion chamber parts for jet aircraft and guided missiles, sand-blast nozzles, exhaust tube linings, hot-draw or hot-press dies, and induction brazing fixtures.

While classified as a conductor, slight modification of the material's composition results in electrical properties which suggest possible use for high temperature resistors.

D-1922 has effectively resisted erosion when subjected to a mixture of steam and SO_3 at high temperatures. In addition, it is insoluble in HCl, HNO_3 , and NH_4OH at room temperature. The material is currently undergoing prolonged testing at elevated temperatures to determine stress rupture, creep, etc.



Use "dag" colloidal graphite dispersions to lubricate under all conditions of extruding, deep piercing, forging, stretch forming, wire-drawing and ingot stripping... to assist in the parting of castings... to provide a lubricant that is impervious to degreasing agents... to lubricate permanently parts that may be subject to extremely high temperatures.

"Dag" dispersions protect against heat... fatigue failures... heavy loads...in short, protect against all the causes of wear. At virtually any temperature experienced in hot-metal work "dag" colloidal graphite overcomes friction and heat and keeps parts lubricated for action.

DRY FILMS of lubricant formed with "dag" dispersions have extremely low coefficients of friction;

they resist oxidation and function far above the burning-point of conventional petroleum lubricants.

Dispersions of molybdenum disulfide are now commercially available. Experimental samples will be sent on request.

More data on the advantages of "dag" colloidal graphite for metalworking operations are contained in a recent bulletin available on request. Write TODAY for Bulletin No. 426-13K.

Acheson Colloids is equipped to do custom disintegrating, dispersing, and stabilizing of solids in a wide variety of vehicles. If you are in need of this type of service, tell us about it. We may be able to help you.

Acheson Colloids Company,


Port Huron, Mich.

..also ACHESON COLLDIDS L!MITED, LONDON, ENGLAND

Units of Acheson industries, Inc.

dag

STEEL PLATE WORK



TURBINE CASINGS

and other heavy steel plate work are fabricated at Puseyjones of Hot-Rolled, High-Strength, Low-Alloy Steel.

Every facility for large scale metal fabricating: - Heavy plate shop equipment - Rolls -Shears - Bending furnaces. Stress relieving furnace 33'x18'x16' up to 2100°F. Machine shop for facing, turning, and boring. 50 ton capacity gray iron foundry. Deepwater transportation on one side, the Pennsylvania RR on the other. Talk to our development engineers.

Metals Fabrication Division
THE PUSEY AND JONES CORP.
504 Front Street, Wilmington, Del.
Established 1848

PUSEYJONES

Technical Briefs

ELECTRONICS:

Engineers get peek at latest developments at Chicago meeting.

Over 5000 electronics engineers and manufacturers, registered for the eighth annual electronics conference in Chicago recently, got a looksee at the latest developments in electronic equipment.

In 3 days the specialists were briefed on radar, memory tubes, electronic computers, television, servomechanisms, audio, industrial measurements, reliability tests for components, transistors. They were given a guarded look at current military developments in electronics, and saw equipment exhibited by more than 60 producers.

Some of the things they heard were:

Small — Cadmium sulfide crystals as a semi-conductor in transistors was suggested as equal to germanium, selenium, and oxides of copper and aluminum. Application would be in radio units half the size of a kitchen match.

Military-LORAN — Long range navigation by electronic means, is back, in an advanced form. Continuous recording equipment was described that would give a continuous navigational fix during the entire period of an air flight or sea trip. The system has been field tested, looks particularly good for aircraft use.

Transistors, tiny units that allow the building of pocket-sized electronic equipment, are being improved. Studies will seek to allow use of higher power capacities with resultant greater power loads allowable.

Radar—Development of a quality factor that would compare the display effectiveness of two or more radar systems, should lead to refinements of existing radar in visually evaluating the "pips" and patterns on the screen. An improved method for measuring loudspeaker output cuts test time from two days of arduous labor to one hour and one sound reading.

BIG PLANER:

Unusual features cut costs in machining large parts.

Transverse, vertical, bevel and longitudinal planing operations in the toolroom can all be carried out with a single set-up on work pieces as large as 177 in. wide x 110 in. high x 394 in. long, through the use of a new double-column planer. Other operations possible with the same set-up include vertical and bevel slotting, longitudinal and transverse milling.

Adaptability of the Wagner Planer to a wide variety of machining operations without re-alignment of the work piece greatly reduces the costs of setting up heavy, bulky pieces. This feature is of particular importance in the machining of such pieces as large dies for forming aircraft parts.

Variable Drive — Machined on conventional planers, it is frequently impossible, after planing in one direction, to re-align the piece for planing at right angles. In this case, however, the left-hand cross rail head has an infinitely variable drive for feeding it along the cross rail, permitting transverse planing with the original set-up with the longitudinal movement immobilized.

For further savings in settingup time, the table is divided longitudinally into two sections with independent travel. The planer is distributed by Kurt Orban Co., Inc., New York.

ula

cur

tril

tha

ing

stre

DOF

cur

win

stat

Whe

cha

to



DOUBLE-COLUMN planer handles transverse, vertical and longitudinal planing. 35 well as vertical slotting, milling and reaming operations on bulky work pieces. Portain push-button stations permit operator control from points convenient to tool heads.

ud

CUS

tle

ier.

the and and

ner iin-

g11-

1'0-

V.V.

of

lies

on

fre-

ing

the les.

eft-

in-

ing

rig-

inal

ing-

ngi-

in-

· is

Co..

g.

mi g


ic tne

AG :

JUARE COPPER BUS:

Greater current carrying capacity, strength in square tube bus.

A ventilated square copper tube is that provides increased curnit-carrying capacity for a given ea of metal has been developed by hase Brass & Copper Co., Inc. Ventilating holes provide air circulation for dissipation of heat from ternal tube surfaces and increase



VENTILATED square copper tube bus increases current carrying capacity and provides a higher ratio of load capacity to weight per foot than unventilated tube or bus bar with greater square area of metal.

ac current-carrying capacity approximately 20 pct.

Corners—Rounded corners of the tube tend to reduce local heating from concentration of current in corner areas. Skin effect, which causes heating in the solid rectangular bus indicated above, results in current being less uniformly distributed throughout the conductor than is the case when square tubing is used.

Stronger—Square copper tube bus also provides mechanical strength in all directions so that longer spans, without unduly large sags, are obtainable between supports. Mechanical strength is also an advantage during heavy fault currents and to provide increased wind resistance and ability to withstand the weight of ice and snow when bus is installed outdoors.

The combination of greater mechanical strength plus the ability to greater loads indicates possibilities for savings in power set-

Turn Page





Anti-Corrosive has millions of stainless steel fastenings in stock for immediate delivery . . . plus exceptional production capacity that can fill your requirements beyond stock items faster, better!

FREE - Write for Slide-Chart 52K which instantly identifies A-N nos. pertaining to stainless fastenings.



III CASTELLICS OF STAILLESS STEEL

Metal Products Co., Inc lanufacturers of STAINLESS STEEL FASTENINGS

CASTLETON ON HUDSON NEW YORK

Specify...The ABBOTT METHOD MATERIALS

LONGER OPERATING LIFE

Manufacturers of Deep Hardened and Tempered Carbon Steel Bearing Balls, Grinding and Graining Materials.

THE ABBOTT BALL COMPANY 1094 New Britain Ave., Hartford, Conn.



Is Your Plant "Well Informed

- Keep your entire plant abreast of the latest developments in the Metalworking Industry by distributing extra copies of THE IRON AGE to all department
- An extra subscription or two will make the vast storehouse of information provided each week in THE IRON AGE available to many additional employees In your organization.

Additional subscriptions \$8 per year Write: CIRCULATION MANAGER

the Iron Age

100 East 42nd St., New York 17, N. Y.

Technical Briefs

THREADS:

Inserts in magnesium cast covers provide strong threads.

In converting side covers of caculating machines from aluminum to lighter weight magnesium castings, engineers of Marchant Calculating Machine Co., Oakland, Calif., had to offset limiting physical characteristic of the magne-



BOSS ON RIGHT side of cover being tapped to receive thread insert. Standard drill sizes are used and thread fits from class I to 3 can be produced.



THREAD INSERT of stainless steel diamond wire partially installed in magnesium cast cover used on calculating machines.

sium low tapped thread strength.

Required strength in the metal was obtained by installing stainless steel wire thread inserts into the prepared thread bosses of the cast side covers. Three inserts are used in each cover, forming 5/1 -18 internal threads 5/16 in. long.

The inserts, multipurpose, are helical coils of diamond-shap d



21.

a -

id.

8 -

h.

iet.il

ain-

into tle

are

/1 -

re if

ap 1

AG:


ıg.

the smith had the right idea

When it comes to forming metals, there's no substitute for the hammer. No other method gives metal equal toughness and resiliency.

The Torrington Swager operates on the same principle—delivering 4000 hammer blows a minute. It reduces,

tapers and points rod, wire and tubing accurately and economically...using every ounce of stock.



THE TORRINGTON COMPANY

Swager Department

555 Field Street • Torrington, Conn.

Makers of

TORRINGTON NEEDLE BEARINGS

-Technical Briefs

stainless steel wire, serve three purposes. They provide internal threads having a tensile strength up to 50 per cent greater than is possible in the magnesium alone.

The tight-fitting stainless steel inserts, made by Heli-Coil, prevent the electrolytic action that would result in corrosion if standard steel threaded fasteners came in direct contact with the magnesium.

Hard Threads—Should the side plates need removal for servicing the machine, there is no risk of damage to threads. The inserts are harder and tougher than any machine screw. An increase in assembly time was reported as a result of using the thread inserts.

STANDARDIZATION:

New policy cuts maintenance, output costs on military vehicles.

A parts standardization program borrowed from mass production techniques is helping cut production and maintenance costs of U. S. military vehicles.

The mass production principle has been broadened in the military vehicle field to extend to planning and designing of military models. Many standard parts may now be used interchangeably in more than one type of tank or truck. The result is lower cost through greater volume of these parts and ease and simplification in maintenance.

This is how it works. Today one tank engine serves 11 tanks and tank-family vehicles. Each World War II engine had more than 5000 parts, none of which could be interchanged with other models. New tank engines now have fewer than 2000 parts, 60 pct of which can be interchanged.

In the light tank family 60 major components are interchangeable. These include engines, generators, torsion bars, ignition systems and suspension systems. The Army's catalog of automotive spare parts has been reduced from 450,000 to 125,000 separate items as a result.



'Joe, who can make these small parts to our close 'specs'?"

"Torrington can, Tom.
They have the
experience and
equipment to maintain precision
tolerances on any
quantity of small
metal parts."



Small precision parts often take more production time than can be spared. That's why many leading manufacturers have turned over their parts problems to Torrington. Using the latest automatic and semi-automatic equipment, our Specialty Department produces hundreds of thousands of parts every day to the exacting specifications of hundreds of customers. These companies—some of them Torrington customers for over 40 years—have learned that they save both time and money when their small metal components are made by Torrington.

Why not send us a blueprint or sample of *your* small parts? We will quickly tell you how little it costs to have uniformly accurate components.



THE TORRINGTON COMPANY

Specialty Department

555 Field Street . Torrington, Conn.

TORRINGTON NEEDLE BEARINGS

SAVE TIME, INCREASE PRODUCTION

WAY MACHINES

Ex-Cell-O Way Machines save time by working from 2, 3, or 4 directions simultaneously, holding accurate relationship between the various operations. Standard, self-contained way units can be rearranged for different work, using units individually or combined with others.

This Three-Way Precision Boring Machine uses three standard way units. The two side units perform conventional boring, plunge-facing and chamfering operations on holes approximately 3 inches in diameter. The rear station performs more complicated work requiring a cross-feed head (see drawing). The bore diameter at the rear station is 4 inches, and is held to limits of plus or minus .0005".

Ask your Ex-Cell-O representative for complete information.


10

de

sh

ua

0



Right: Tool layout for roughing operations at the rear station. Tool 1 bores the hole as the table feeds forward to a positive stop. Then the cross-feed head moves across while tool 2 faces an area at the base of the bore and tool 3 faces the shoulder of the counterbore. As the cross-feed slide approaches the end of its stroke tool 4 chamfers the edge of the bore. The table then reverses in feed until tool 2 blends its cut with the bore produced by tool 1, and tool 3 bores the counterbore, after which both table and cross-feed head return to the start position. The upper drawing is a view looking into the hole. The circle in broken lines shows the path of tool 2 while tool 1 is boring. The shaded portion is the area faced by tool 2.

EX-CELL-O
CORPORATION
DETROIT 32, MICHIGAN

MANUFACTURERS OF PRECISION MACHINE TOOLS
CUTTING TOOLS • RAILROAD PINS AND BUSHINGS
DRILL JIG BUSHINGS • DAIRY EQUIPMENT
AIRCRAFT AND MISCELLANEOUS PRODUCTION PARTS



Record Steel Output Stirs Still-Hungry Consumers

Operations scheduled at 106 pct of capacity for second week in row...Consumers all want steel right away... Inventories drastically unbalanced, by plants, products.

Steelmakers are beating all previous production records, and they seem to be gearing up for even greater output.

1

1)

c,

ne

ns

0

n-

be

he

to

Or

This week the steel industry is scheduled to operate at 106 pct of rated capacity, the same as last week's record-shattering pace. Even higher operations are possible as more new steelmaking capacity continues to be brought into production.

Mills are turning out finished steel so fast that there are not enough freight cars available to carry it away. Early this week THE IRON AGE learned one mill in the Pittsburgh area had at least 10,000 tons of finished steel items awaiting shipment. Other mills are in pretty much the same boat, with the result that railroads serving mills in that area are under terrific pressure.

Spot shortages of freight cars hampered scrap flow in some areas.

New Hope—Encouraged by reports of high production, steel consumers are applying renewed pressure for early delivery. Everybody wants his steel right now—sooner if possible. Mills are trying to explain that no reasonable rate of production could satisfy pent up demands all at once.

This is undoubtedly true, but it is hard to explain to sheet users (for example) that deliveries can not be speeded. Before the strike sheets were easy, could be had on very short delivery. Now some consumers of sheets can't even find a home for their fourth quarter allocations. This means the earliest delivery possible would be next March, since fourth quarter orders have been extended to January and February.

Demand is also more intense for other major tonnage items such as heavy plates, bars, pipe and structurals.

Short-Term Demand—But nearly all consumer effort is aimed at relieving short-term supply deficiencies. Both consumers and producers still expect the steel market to start easing during the first quarter and to attain reasonable balance by the second quarter of next year.

Instead of acting to ease consumer pressure, this belief is intensifying it. There is special market advantage for manufacturers in attaining high production before steel again becomes abundant for all. A few consumers are using thinly veiled threats—that if mills hope to get their business when steel turns plentiful they had better deliver now. This is food for serious thought, but it is doubtful the mills can do much about this problem.

Double Trouble-For one thing they are still getting government directives which can delay other deliveries already promised and scheduled. Only last week THE IRON AGE learned National Production Authority ordered some conversion work off a mill to make way for a military order. A farm equipment order was pulled off and and a shell program order put in its place. This, of course, meant a rescheduling and explaining job for the mill. Similar instances are not uncommon, but they are always tough to handle.

Despite current consumer pressure for delivery there are some indications that mills are adopting a cautious attitude toward the probable market in 1953. Some producers are avoiding long-range commitments on steel scrap. One mill that previously had agreed to a six-month contract would renew only on a 30-day basis.


Mills also see supply safety in tall stockpiles.

Slow Death — The conversion market may wither toward the end of the year, but it is not likely to die in December, as had been predicted. Some conversion rolling space is being wiped out as mills bring in new openhearth furnaces to balance production. In addition, at least two conversion mills overbooked in anticipation of cancellations. They still count on them, but reports from big conversion customers indicate they haven't lost their appetites for steel.

Steel items are not uniformly hard to get. Merchant wire products and nails are relatively easy. Light (strip mill) plates are in fair supply. Some specialty items, such as silicon sheets, are fairly easy. And light structurals and small shapes are coming back. Although these items are watched as tattle tales of easier supply, they do not make up a large portion of total steel production.

Spotty Inventory — Consumers' inventories are extremely spotty, ranging widely among plants and steel items. In a single plant you might find steel supply of different items ranging from hand-to-mouth to double the 30-day limit.

If sheet users expect model changeovers in Detroit to give them a chance to catch their breath, they are in for a rude surprise. Shutdowns for model changes will now occur periodically for the rest of the year. But, while each will ease the situation momentarily for the specific plant, production is geared so high that no overall easing can be expected.



Finding a Faster Way to Measure a Star



Another example of how Carpenter *Application Engineering Service is working for industry

The giant 200-inch telescope at California's Mt. Palomar Observatory was picking up thousands of stars missed by other telescopes. But the job of measuring and coordinating the data revealed by the photographs was so big that astronomers couldn't keep abreast of it. Then the delicate astrophotometer

was developed and the problem was solved. The new device mechanically computes the size of a star in a fraction of the time trained astronomers could do it with former devices.

Naturally, such a precise instrument posed quite a few materials problems. One was the type of steel for the hardened ways on which the machine travels horizontally back and forth. Many different special steels were tried. All failed because they couldn't meet the exacting straightness that was required.

Then, Carpenter Application Engineering Service was called in... and Carpenter Vega, a new air-hardening steel that shows practically no distortion in heat treatment was put to work. Used successfully for thousands of critical tool and die applications, Vega has proved to be the only steel found to stay straight enough in the 20" lengths of the ways. Are there applications in *your* plant where a steel providing this kind of performance could give your product extra competitive advantages?

Time and again, industry is finding new ways to save money and improve the salability of products with the help of Carpenter Application Engineering Service... a service that uses imagination to apply steels for best results. A.E.S. is yours to profit by when you do business with Carpenter. THE CARPENTER STEEL COMPANY, 121 W. Bern St., Reading, Pa.



Carpenter Tool, Alloy and Stainless Steels

Pioneering in Improved Tool, Alloy and Stainless Steels Through Continuing Research

di

01

Market Briefs and Bulletins

Warehouses—Inquiries and sales at warehouse level continue at a high rate. Though warehouses continue to move steel items almost as fast as they come in, they are beginning to accumulate better stocks of light product lines such as small pipe, light structurals, sheets and strip. Warehouse activity reflects a high rate of manufacturing, as well as unbalanced inventories in consumers' hands. The number of urgent calls continues high.

Can Prices—Office of Price Stabilization told can manufacturers recently that it has compiled enough earnings data to issue a tailored order providing a percentage-factor price ceiling increase. It also stated manufacturers could pass along recent increases in tinplate costs. But some industry spokesmen said they would gain more from ceilings set by CPR 22, combined with a Capehart-type adjustment and pass-through of tinplate costs. The tailored order proposed by OPS would roll back some ceilings already established, they said.

Small Business Aid—National Production Authority will continue its small business hardship program for at least the remainder of 1952. Administrator Richard McDonald says third quarter requests for such help have fallen to a "very low" level, and that so far only a few cases are listed for the fourth quarter.


Whip Snapped—Communist Party's congress in Moscow was told that Soviet industrial production must increase 70 pct by 1955. Overall production this year was expected to be 230 pct higher than in 1940. Machinery and equipment alone were reported 300 pct higher. Anticipated production for 1952 includes 25 million tons of pig iron, 35 million tons of raw steel; 27 million tons of rolled steel and 300 million tons of coal.

No Ceiling Prices—Ceiling prices no longer have to be stated by defense contractors and subcontractors. Firms supplying services connected with defense-materials and suppliers of the materials need only certify that their prices are not in excess of ceilings. Authority for this OPS ruling is Amend 3, Rev. 1, General Overriding Reg. 2.

Training Planes—North American Aviation, Inc., will build an unnamed number of T-28B training planes for the Navy at its Downey, Calif., plant. The trainers are counterparts of the Air Force's T-28A but have more powerful engines and three-blade propellers.

Iron Supply Solid—Except for low phos grades, iron supply appears adequate. A foreign offer of pig iron for delivery early next year aroused little interest among Midwestern consumers. Only basis on which foreign pig would be bought today is if price is comparable with domestic level. The foreign offer was considerably in excess of this.

Freight Cars Off—Effects of the steel strike on freight car building hit hard in September. Builders were able to deliver only 3762 units, lowest monthly figure since July, 1950. New orders remained at a low level and just about balanced deliveries. Order backlog stands at 95,377.



District Operating Rates—Per Cent of Capacity

Week of	Pittsburgh	Chicago	Youngstown	Philadelphia	West	Buffalo	Cleveland	Detroit	Wheeling	South	Ohio River	St. Louis	East	Aggregate
Oct. 5 Oct. 12	108.0°	106.0	106.0*	100.0	107.0°	106.5°	108.0°	110.0°	99.0°	101.0	93.0	108.1	110.0°	106.0°
	108.0	106.5	105.0	100.0	103.0	106.5	105.0	106.0	99.0	103.0	90.0	110.0	113.5	106.0

Beginning Jan. 1, 1962, operations are based on annual capacity of 108,587,670 net tons. * Revised.

ed.

lled

hat

1.10

die

10

nere ind

eti-

nev

of

that S. is

iter.

St.

els

arci

GI

Price Cuts Don't Raise Demand

Lead, zinc prices down, but customers stay leery... Drop in London lead prices pressure cuts here... May decline further... Dual zinc pricing ended—By R. L. Hatschek.

Transatlantic doings were behind the sharp 1¢ drop in U. S. lead prices last week. Freeing of the London lead market lowered prices there, at one time as low as 13¢, New York delivery. Since U. S. producers were selling at 15.80¢, St. Louis, something had to give

As a result, domestic consumers are suspicious of the whole market. Major sellers say they will try to keep lead at the present price of 14.80¢, but admit that if British prices stay at current levels of about 135 c, the U.S. will have to follow suit. They stress their feeling that the London drop is exaggerated, however. But some trade sources aren't so sure. Some feel light demand will cut prices in any event.

Government Aid—Britain's Ministry of Supply is being rapped for helping to depress the lead market there. The government doesn't trade on the London Metal Exchange, but gladly makes aftermarket sales to British consumers. Prices in these deals are based on closing exchange figures. Thus, foreign producers charge, buyers do their best to depress prices on the exchange so they could buy cheaply from the government at a future time.

If this situation can be corrected.

there is a chance of British lead prices firming.

Low lead prices here could cut production and possibly tighten the labor supply at the mines. Miners' wages in the Midwest are tied to lead prices, and some miners have already lost as much as 25¢ per day as a result of the 1¢ drop. These are the first cuts under the sliding scale wage contract which allows pay cuts of 25¢ per day for each 1¢ drop in the price of lead.

Zinc Drop—The dual price market in zinc was eliminated last week when all producers dropped from 14c per lb to 13.5c. This brought prices into line with the one established some 3 weeks ago by a custom smelter. But customers weren't interested even at the lower prices. Just to add to zinc producers' blues, increasing stocks of foreign metal were reported offered at cut prices. Some foreign zinc has been offered at under 13c, trade sources have reported.

Copper Talk — Copper demand continued to exceed domestic supply. But consumers have not yet taken all the higher-priced foreign metal allocated for October.

The fouled-up price situation still bothers U. S. copper producers. A conference with Office of Price Stabilization officials will be probably called this week or next. The industry spokesmen will undoubtedly ask for removal of controls, but the real fight will come on the price differential between domestic and foreign metal.

Aluminum Record—A new postwar record in U. S. production of primary aluminum was set in August, according to Donald M. White, secretary of The Aluminum Assn. August output was 170,-350,658 lb, 12.5 pct over July, and 15.5 pct over August 1951.

"The industry's building program continues to gain momentum," said Mr. White, "although at the present time production is being curtailed because of power shortages."

Canada, too, is boosting aluminum capacity. Output in the next 2 years will be upped almost one-third, and final goal will be more than half the present world total. Production last year was 890 million lb, about 25 pct of world output.

Bigger Boost—Producers of primary aluminum mill products should be allowed an 8 pct increase in ceilings instead of the 5 pct rise authorized by OPS in August, the agency has been told.

Spokesmen for primary aluminum producers said the 5 pct increase allowed by Supplementary Reg. 113, General Ceiling Price Reg., is insufficient in relation to the 1c-per-lb rise in ceilings allowed for pig and ingot aluminum. Nonintegrated mill products manufacturers in particular are being squeezed by higher pig and ingot costs on one hand and greater expenses for labor and additional materials on the other.

This is contributing to a rickety profits structure.


Most mill products makers have cost data available to show the relationship of total production costs to the cost of pig and ingot. OPS said it intends to ask for this information for use in considering whether the percentage increasauthorized should be greater.

NONFERROUS METAL PRICES

	Oct. 8	Oct. 9	Oct. 10	Oct. 11	Oct. 13	Oct. 14
Copper, electro, Conn.	24.50	24.50	24.50	24.50	24.50	24.50
Copper, Lake delivered	24.625	24.625	24.625	24.625	24.625	24.625
Tin, Straits, New York	\$1.213/8	\$1.211/2	\$1.213/8	\$1.213/8	\$1.213/8	\$1.213/8*
Zinc, East St. Louis	13.50	13.50	13.50	13.50	13.50	13.50
Lead, St. Louis	14.80	14.80	14.80	14.80	14.80	14.80
Note: Quotations are going	prices.					

*Tentative.

+Effective Oct. 7, 1952.



er

xt

re

11-

ld

he

ni-

11-

m.

a-

MILL PRODUCTS

(Cents per lb, unless otherwise noted)

Aluminum

(Base 30,000 lb, f.o.b. ship. pt. frt. allowed)
Flat Sheet: 0.188 in., 2S, 3S, 31.6c; 4S, 418-0, 23.6c; 52S, 38.8c; 24S-0, 24S-0AL, 44.6e; 76S-0, 76S-0AL, 41.9c; 0.081 in., 2S, 28, 32.8c; 4S, 61S-0, 35.2c; 52S, 37.4c; 24S-0, 24S-0AL, 48.8c; 75S-0, 75S-0AL, 43.9c; 0.032 in., 2S, 3S, 34.5e; 4S, 61S-0, 39.9c; 52S, 41.8c; 24S-0, 24S-0AL, 43.8c; 75S-0, 75S-0AL, 54.8c

248-0, 248-0AL, 43.8¢; 758-0, 758-0AL, 54.8¢.
Plate ½ in. and Heavier: 2S-F, 3S-F, 29.7¢; 4S-F, 31.7¢; 53S-F, 33.4¢; 61S-O, 32.3¢; 24S-O, 24S-OAL, 34.0¢; 75S-O, 75S-OAL, 40.7¢.
Extruded Solid Shapes: Shape factors 1 to 5, 35.6¢ to 77.2¢; 12 to 14, 36.2¢ to 93.5¢; 24 to 26, 38.7¢ to \$1.2\$; 36 to 38, 45.9¢ to \$1.79.
Rod, Rolled: 1.064 to 4.5 in., 2S-F, 3S-F, 39.4¢ to 35.2¢; cold-dinished, 0.375 to 3 in., 2S-F, 3S-F, 42.5¢ to 36.8¢.
Serew Machine Stock: Rounds, 11S-Ts, ½ to 11/32 in., 56.2¢ to 44.1¢; ½ to 1½ in., 43.6¢ to 41.0¢; 19/16 to 3 in., 40.4¢ to 37.8¢; 17S-Ts, 1.6¢ per lb lower. Base 5000 lb.
Drawn Wire: Coiled, 0.051 to 0.374 in., 2S, 41.6¢ to 30.5¢; 52S, 50.4 to 36.8¢; 56S, 53.6¢ to 44.1¢; 17S-T4, 56.7¢ to 39.4¢; 61S-T4, 50.9¢ to 48.9¢.
Extruded Tubing: Rounds, 63S-T5, OD in in.;

88.9¢.
Extraded Tubing: Rounds, 63S-T5, OD in in.:
1½ to 2, 38.9¢ to 56.7¢: 2 to 4, 35.2¢ to 47.8¢;
4 to 6, 35.7¢ to 43.6¢; 6 to 9, 36.2¢ to 45.7¢.
Roofing Sheet: Flat, 0.019 in., x 28 in., per sheet, 72 in., \$1.199; 96 in., \$1.598; 120 in., \$1.997; 144 in., \$2.398, 0.24 in. x 28 in., 72 in., \$1.487; 96 in., \$1.931; 120 in., \$2.414; 144 in., \$2.897. Coiled sheet: 0.019 in. x 28 in., 26.6¢ per lb; 0.024 in. x 28 in., 28.2¢ per lb.

Magnesium

(F.O.B. mill, freight allowed)

(F.O.B. mill, freight allowed)

Sheet and Plate: FS1-0, ½ in., 63c; 3/16 in., 65¢; ½ in., 67¢; B & S Gage 10, 68¢; 12, 72¢. Specification grade higher. Base: 30,000 lb.

Extruded Round Rod: M, diam in., ¼ to 0.311 in., 74¢; ½ to ¾ in., 67.5¢; 1¼ to 1.749 in., 53¢; 2½ to 5 in., 48.5¢. Other alloys higher. Base up to ¾ in. diam, 10,000 lb: ¾ to 2 in., 20,000 lb.; 2 in. and larger, 30,000 lb.

Extruded Solid Shapes, Rectangles: M. In weight per ft, for perimeters less than size indicated, 0.10 to 0.11 lb, 3.5 ln., 62.3¢; 0.22 to 0.25 lb, 5.9 in., 59.3¢; 0.50 to 0.59 lb, 8.6 in., 56.7¢; 1.8 to 2.59 lb, 19.5 in., 53.8¢; 4 to 6 lb, 28 in., 49¢. Other alloys higher. Base, in weight per ft of shape: Up to ½ lb, 10,000 lb; ½ to 1.80 lb, 20,000 lb; 1.80 and heavier, 30,000 lb.

Extruded Round Tubing: M, wall thickness, outside diam, in., 0.049 to 0.057; ½ in. to 5/16, \$1.40; 5/16 to 3½, \$1.2¢; ½ to 5½, 93¢; 1 to 2 in., 76¢; 0.165 to 0.219, 9½ to ¾, 61¢; 1 to 2 in., 57¢; 3 to 4 in., 56.¢. Other alloys higher. Base, OD in in.: Up to 1½ in., 10,000 lb; 1½; in. to 3 in., 20,000 lb; 3 in. and larger. 30,000.

Titanium

(10,000 lb base, f.o.b. mill)

Commercially pure and alloy grades: Sheets and strip, HR or CR, \$15; Plate, HR, \$12; Wire, rolled and/or drawn, \$10; Bar, HR or forged, \$6; Forgings, \$6.

Nickel and Monel

(Base pri	C	e.	8	,	Ĵ	.0.8	mill)	
					5.0	A"	Nickel	Monel
Sheets, cold-rolled							77	60 14
Strip, cold-rolled							83	63 1/2
Rods and bars							73	5814
Angles, hot-rolled							73	5814
Plates							75	5914
Seamless tubes						. 1	0.6	9314
Oh - 4 3 1 1 - 1								

Copper, Brass, Bronze

(Freight prepaid on 200 lb)

	C11		Extruded
	Sheet	Rods	Shapes
Copper	45.52		45.12
Copper, h-r		41.37	
Copper, drawn.		42.62	
Low brass	42.34	42.03	
Yellow brass .	40.17	39.86	
Red brass		42.79	
Naval brass	44.72	38.78	40.04
Leaded brass			38.02
Com's bronze .		44.08	****
Mang. bronze .	48.44	42.83	43.89
Phos. bronze .		64.97	
Muntz metal	42.69	38.25	39.50
M aliver, 10 pct	51.96	54.18	

PRIMARY METALS

(Cents per lb, unless otherwise noted)
Aluminum ingot, 99+%, 10,000 lb, freight allowed
Aluminum pig 19.00
Antimony, American, Laredo, Tex., 39.00
Beryllium copper, 3.75-4.25% Be . \$1.56
Beryllium aluminum 5% Be, Dollars
per lb contained Be\$69,50
Bismuth, ton lots \$2.25
Cadmium, del'd \$2.00
Cobalt, 97-99% (per lb)\$2.40 to \$2.47
Copper, electro, Conn. Valley 24.50
Copper, Lake, delivered 24.625
Gold, U. S. Treas., dollars per oz. \$35.00
Indium, 99.8%, dollars per troy oz. \$2.25
Iridium, dollars per troy oz \$200
Lead, St. Louis 14.80
Lead, New York 16.00
Lead, New York
Tex., 10,000 lb 24.50 Magnesium, sticks, 100 to 500 lb.
Magnesium, sticks, 100 to 500 lb.
42.00 to 44.00
Mercury, dollars per 76-lb flask,
f.o.b. New York\$193 to \$195
f.o.b. New York\$193 to \$195 Nickel electro, f.o.b. N. Y. warehouse 59.58
Nickel oxide sinter at Copper
Creek, Ont., contained nickel 52.75
Palladium, dollars per troy oz\$24.00
Platinum, dollars per troy oz. \$90 to \$93
Silver, New York, cents per oz 83.25
Tin, New York \$1.21%
Titanium, sponge \$5.00
Zinc, East St. Louis 13,50
Zinc, New York 14.58
Zirconium copper, 50 pct \$6.20
The second section of the second second

REMELTED METALS

Brass Ingot

(Cents	per	lb,	delivered	carload	8)
85-5-5-5 in	got				
No. 120					26.75
No. 123					26.25
80-10-10 in	got				
No. 305					33.00
No. 315					30.50
88-10-2 ins	rot				
No. 210					41,50
No. 215	× 1				40,00
No. 245					34.50
Yellow ing					
No. 405					23.25
Manganese	bro	nze			
No. 421			*****		30.50

Aluminum Ingot

(Cents per lb, 100,000 lb and over)
95-5 aluminum-silicon alloys
0.30 copper, max 20.
0.60 copper, max 20.
Piston alloys (No. 122 type) 20.
No. 12 alum. (No. 2 grade) 19.
108 alloy
195 alloy 20.
13 alloy (0.60 copper max.) 20.
ASX-679
Steel deoxidizing aluminum, notch-bar
granulated or shot

Grade 1—95-97 4% Grade 2—92-95% Grade 3—90-92% Grade 4—85-90%

ELECTROPLATING SUPPLIES

Anodes

(Cents per lb, freight allowed, 500 lb	lots)
Copper	
Cast, oval, 15 in. or longer	37.84
Electrodeposited	33 %
Flat rolled	38.34
Forged ball anodes	43
Brass, 80-20	
Cast, oval, 15 in. or longer	343,
Zinc, oval	26 16
Ball, anodes	25 1/2
Nickel, 99 pct plus	20 72
	76.00
Cast Rolled, depolarized	
Rolled, depolarized	77.00
Cadmium	\$2.15
Silver 999 fine, rolled, 100 oz lots,	
per troy oz. f.o.b. Bridgeport,	
Conn	9714
Chemicals	
Chemicals	

Chemicais	
(Cents per lb, f.o.b. shipping poin	sta)
Copper cyanide, 100 lb drum	63
Copper sulfate, 99.5 crystals, bbl	
Nickel salts, single or double, 4-100	
lb bags, frt. allowed	27 1/4
Nickel chloride, 375 lb drum	271/
Silver cyanide, 100 oz lots, per oz	671/4
Sodium cyanide, 96 pct domestic	
200 lb drums	19.28
Zinc cyanide, 100 lb drum	47.7

SCRAP METALS

Brass Mill Scrap

(Cents per pound, add 1/2e per lb for shipments of 20,000 to 40,000 lb; add 1e for more than 40,000 lb)

												av	y	T	u	rn-	
Copper				0	0	۰						1 1/2		2	U	%	
Yellow	bra	LSS					0	0		0	13	9 1/4		1	7	1/4	
Red bra											20	0 34		1	9	%	
Comm.	bro	nze	9								21	0 1/4		1	9	34	
Mang.											11	8 1/4		1	7	3/4	
Brass r											13	8 %		*			
	-					_											

	Cust	om	5	m	e	11	eı	rs		5	c	r	a	p		
(Cents	per 1	pour	id,	re	co	n	lo	a u	d)	1	0	ta	,	6	le	livered
No. 1 c	opper	Wi	re						٠.	*					*	19.25
No. 2 c	opper	Wi	re		-					*	*			è		17.75
Light o	copper		×		*										*	16.50
Refiner	y bra	38								*					*	17.25
Radiate	ors .						×	*		*			8	*	ĸ	14.75
* Dry	copp	er	co	ni	e	nt										

Innat Makasa! Casas

Ingot Makers Scrap
(Cents per pound, carload lots, delivered to refinery)
No. 1 copper wire
The a copper wife the state of
Light copper 16.50
No. 1 composition
No. 1 comp. turnings 18.25
Rolled brass 15.50
Brass pipe 16.50
Radiators 14.75
Aluminum
Mixed old cast 9 - 9%
Mixed new clips 10 -11
Mixed turnings, dry 9 - 9%
Pots and pans 81/2-9

Dealers' Scrap (Dealers' buying price, f.o.b. New York in cents per pound)

Copper and Brass

No. 1 heavy copper and wire.	18% -19%
No. 2 heavy copper and wire.	17 -17%
Light copper	1516-16
New type shell cuttings	15 14-16
Auto radiators (unsweated)	14
No. 1 composition	171/2-18
No. 1 composition turnings	17 -17%
Unlined red car boxes	
Cocks and faucets	
Mixed heavy yellow brass	111/2-12
Old rolled brass	1414-16
Brass pipe	15 1/2-16
New soft brass clippings	16 -16 1/2
Brass rod ends	15 1/3 16
No. 1 brass rod turnings	15 -15 1/4
Aluminum	


		All	umi	IIII	un	8			
	lum, piston							61/2-7	
	duminum er							4 72	
	S aluminum							10 1/2	
C	old sheet an	d uter	nsil	S				 7 1/4	
E	sorings and	turni	ngs					 5 - 6	
7	lisc, cast a	lumin	um					71/2-8	
I	oural clips	(24S)					*	 7 1/2	
			Zir	10					
N	lew zinc clip	pings						 81/2-9	
	old zinc .							6 1/2 - 7	
	inc routing							 3 3/4 - 4 1/4	

Old die cast scrap	5 - 5
Nickel and Monel	
Pure nickel clippings	35 -36
Clean nickel turnings	35 -36
Nickel anodes	
Nickel rod ends	35 —36
New Monel clippings	28 -29
Clean Monel turnings	20 -21
Old sheet Monel	28 -29

Clean Monel turnings Old sheet Monel Nickel silver clippings, mixed. Nickel silver turnings, mixed.	$\begin{array}{cccccccccccccccccccccccccccccccccccc$
Lead	
Soft scrap, lead Battery plates (dry) Batteries, acid free	12 1/4 — 13 6 1/4 — 7 4 1/6

Segregated solids	15 -16
Castings	14 —15
Miscellaneous	
Block tin	100
	70
No. 1 pewter	
No. 1 auto babbitt	55 60
Mixed common babbitt	
Solder joints	19 -20
Siphon tops	60
Small foundry type	19 -19 1/2
Monotype	1514-16
Lino, and stereotype	
Electrotype	
Hand picked type shells	9 % 10
Lino, and stereo, dross	7
Electro. dross	6 1/2

Magnesium



What she doesn't know about BRASS she could find out in a Flash!

It takes plenty of Brass to make a star. For stars must shine, and that takes light. But take Brass away, and she'd be dancing in the dark. Ask any stage electrician or Hollywood "top juicer" . . . he'll point out scores of unseen spots where *only Brass* can do the job that's being done so well. For that matter, look around your own home, from light bulbs to fuse box.

The reasons are not far to seek. Only Brass combines the qualities of relatively high conductivity, resilient strength, and almost endless service life. That's why in lighting, as in so many other fields of application, there is no substitute for the golden-

yellow alloy . . . cast, drawn and rolled as carefully as any precious metal . . . the way it's done here in the modern mills at Bristol. Now you may have a job, too, for which Brass is best, whether it's in electrical equipment or in costume jewelry. Want more light on this profit-laden possibility? Write:

The Bristol Brass Corporation, makers of Brass since 1850 in Bristol, Conn. Offices or warehouses in Boston, Chicago, Cleveland, Dayton, Detroit, Los Angeles, Milwaukee, New York, Philadelphia, Pittsburgh, Providence, Rochester.

Bristol-Tashion means Brass at its Best

Scrap Flow Steady Despite Some Apathy

There is no frenzy to get in the scrap but scrap traffic remains substantial . . . If consumer is indifferent blame it on heavy stockpile . . . Scarcity of scrap for dealers' stocks.

Although consumers are not urging scrap men to break their necks to fill orders, enough sales are being made in most categories to make scrap movement substantial. If there is buying indifference, towering inventories in consumers' yards is seen as motivation.

In Pittsburgh, the market was reported dull—except for electric furnace grades and openhearth material. Some large mills are laying low as far as orders are concerned, content to work off some of the inventory fat they've put on. For the most part, scrap flow continues steady with ceiling prices being maintained and not immediately endangered.

The scarcity of scrap for preparation in dealers' yards is lingering. Some smaller yards not working near capacity see the approach of winter putting peddlers in hibernation and the situation worsening. Birmingham reports scrap yards are almost cleaned out of openhearth and blast furnace grades because of heavy buying pressure from the North, Detroit yards are squirming as collections stay sickly.

Pittsburgh — Mills generally are apathetic, and the market is dull. Exceptions are electric furnace shops which are pressing for deliveries to bolster fading inventories, Deliveries have been slowed by a shortage of freight cars in the district. Cast scrap continued to show weakness in the face of lagging demand but openhearth grades are still strong.

Chicago—Scrap movement was unchanged. There had been a number of rejections of electric furnace scrap over the week and demand for this grade was still rather slow. Cast continued poor, openhearth grades were moving at ceiling and moving well, and blast furnace grades were moving

slowly. As in electric furnace, there seemed to be some blast furnace material of poor quality that was practically unmovable.

Philadelphia—All the symptoms of a solid but not excited market continued here with no change in prices. Dealers were moving material as fast as they could get it and felt that they were not getting enough to process. Unstripped motor blocks showed no activity and generally cast grades coasted along. Although there was no buying push for turnings ceiling prices held and there were no signs of their slipping under.

New York — Ceiling prices for all grades except cast were steady in this area. The market was considered firm and seen continuing this way. Buying is steady but there is no great enthusiasm. Reports of freight car shortages continued. Dealers could use more scrap to process. This shortage on the dealer level is reported especially severe in the South. Cast buyers have trouble in buying much below ceiling.

Detroit—Scrap picture here has two sides. Industrial scrap is moving rapidly and enjoying a strong market. Yards are suffering from poor collections, a situation that may be aggravated by colder weather. Steelmaking grades continue strong and any noticeable weaknesses in blast furnace grades have not affected ceiling prices. Dealers are showing concern over inability to add to inventories.

Cleveland—Market is firm but some mills are holding up shipments. Feeling prevails that consumers with well stocked inventories will be content to draw on reserves at least until the first of the year. Cast scrap is still at ceiling, although dealers are finding it increasingly hard to move. Consumers in the cast market continue to limit springboards. Demand for electric furnace grades remains brisk. Scrap shipments from southwest may brighten lean yard picture.

St. Louis—Shipments of scrap from the country continue to taper off and receipts in the industrial district are low. Steel mills are eating daily into their inventories which are large. Not much buying is expected before Nov. 1. Because of the steel strike railroads are estimated 90 days behind in their shop operations resulting in a thinning out of railroad lists. Some improvement is expected shortly in the cast iron situation.

Birmingham-Scrap yards are just about cleaned out of openhearth and blast furnace grades, most of which have gone North in the last 30 days to one large consumer. Another large northern buyer came into the market this week and brokers were scurrying around to fill orders. Only one mill in the area is buying now, principally No. 2 bundles. Calls for electric furnace grades have eased off. One of the large purchasers of cast in the district, who was paying a premium for shipments from west of the Mississippi, has filled its needs and withdrawn its price for distant tonnage. Some cast continues to move throughout the district at fairly steady prices.

Cincinnati—Scrap is moving at a steady pace here but dealers say there is room for general market improvement. Widespread weakness in cast scrap is reflected by more rigid foundry inspection and scarcity of markets. Openhearth grades and low phos are in good demand. There is very little scrap coming into the area and yards are practically bare.


Boston—Scrap grades are moving well at ceiling. Cast grades are still somewhat under ceiling but are holding. Heavy breakable cast moved up \$2 per ton.

Buffalo—A continuation of an embargo on shipments at one of three leading mill consumers came as a surprise to dealers. Embargo has now been in effect the last 3 weeks. The mill's unloading facilities are tied up by influx of ore. Expected strength in cast failed to develop when one of the area's top buyers again made purchases at under ceiling.

West Coast — Scrap volume remained about normal last week with no price changes. Although dealing below ceiling in most grades there apparently are few candidates for "distress permits" for export to Mexico.

SCRAP at your Service!

The facilities and experienced personnel in each of our offices, stand ready to supply your every scrap requirement whenever and wherever needed.



CONSULT OUR NEAREST OFFICE FOR THE PURCHASE AND SALE OF SCRAP BROTHERS AND COMPANY, INC.

LINCOLN-LIBERTY BLDG. Philadelphia 7, Penna.

PLANTS

LEBANON, PENNA. DETROIT (ECORSE), MICHIGAN READING, PENNA. MODENA, PENNA. PITTSBURGH, PENNA.

CLEVELAND, OHIO NEW YORK, N. Y. SAN FRANCISCO, CAL.

BOSTON, MASS. HOUSTON, TEXAS PUEBLO, COLORADO

BUFFALO, N. Y. LEBANON, PENNA. READING, PENNA.

BIRMINGHAM, ALA. DETROIT, MICH. PITTSBURGH, PENNA.

CHICAGO, ILLINOIS LOS ANGELES, CAL. ST. LOUIS. MO.

SEATTLE, WASH.

LEADERS IN IRON AND STEEL SCRAP SINCE 1889

d

d

p

in

13-

E

Iron and Steel SCRAP PRICES

(Maximum basing point prices, per gross ton, as set by OPS in CPR 5 and amendments.

Switching Charge	0.99 75 75 75 75 75 75	5.25.55	28.88	200.025	82422	10	99.	25.	.78	. 50	.33	15.	8888
(Dollars per gross ten)	98	E -2	5	cken.	F. O.				lty.	City			Cal.
Basing Points	Pitteburgh Johnstown Brackenridge Butler Midland Menessen Sharon	oungstov anten teubenvi /arren	leveland uffalo incinnati	Chicage Claymont Coatesville Conshehocken Harrisburg Pheenixville	parrews ethlehen shland, b okome, ertemou	St. Louis.	Detroit	Duluth	Kanses City	Birmingham. Alabama City. Atlanta	Minnequa	Heusten	Les Angeles Pittsburg, Cal Portland, Ore San Francisco San Francisco
GRADES OPS No.	2280250	>0035	2002	000014	NOAXO	S	0	0	×				74400
Ne. 1 bundles 1 Ne. 1 busheling 2 Ne. 1 beavy melting 3 Ne. 2 heavy melting 4 No. 2 bundles 5 Machine shop turnings 6 Mixed borings and turnings 7 Shoveling turnings 8 Cast iron borings 10	\$44.00 44.00 43.00 43.00 43.00 34.00 38.00 38.00 38.00	\$44.00 44.00 43.00 43.00 43.00 34.00 38.00 38.00 38.00	\$43.00 43.00 42.00 42.00 42.00 33.00 37.00 37.00	\$42.50 42.50 41.50 41.50 41.50 32.50 36.50 36.50 38.50	\$42.00 42.09 41.00 41.00 41.00 32.00 36.00 36.00	\$41.00 41.00 40.00 40.00 40.00 31.00 35.00 35.00	\$41.15 41.18 40.15 40.15 40.15 31.15 35.15 35.15	\$40.00 49.00 39.00 39.00 39.00 30.00 34.00 34.00	\$39.50 39.50 38.50 38.50 38.50 29.80 33.50 33.50	\$39.00 38.00 38.00 38.00 38.00 29.00 33.00 33.00 33.00	\$38.00 38.00 37.00 37.00 37.00 28.00 32.00 32.00	\$37.00 37.00 38.00 38.00 36.00 27.00 31.00 31.00	\$35.00 35.00 34.00 34.00 34.00 25.00 29.00 29.00
ie. 1 chemical borings26	41.00	41.00	40.00	39.50	39.00	38.00	38.16	37.80	36.50	36.00	35.00	34.00	32.00
orge crops 11 Bar crops and plate 12 Punchings and plate 14 Liestric furnace bundles 15 Lut struc., plate, 3 ft and less 16 Lut struc., plate, 2 ft and less 17 Lut. struc., 1 ft and less 18 Lut struc., 1 ft and less 20 Lut struc., 1 ft and less 21 Lut struct.	51.50 49.00 46.50 46.00 47.00 49.00 50.00 44.00 46.00 43.00	51.50 49.00 46.50 46.00 47.00 49.00 50.00 44.00 46.00 43.00	50,50 48,00 45,50 45,00 46,00 49,00 49,00 45,00 42,00	50.00 47.50 45.00 44.50 45.50 47.59 48.50 42.50 44.50 41.50	49.50 47.00 44.50 44.00 45.00 47.00 48.00 42.00 44.80 41.00	49.50 46.00 43.50 43.00 44.00 48.00 47.00 41.00 43.00 40.00	48.85 46.15 43.65 43.15 44.15 46.16 47.15 41.18 43.15 40.15	47.50 45.09 42.50 42.00 43.00 45.00 46.00 40.00 42.00 39.30	47.00 44.59 42.00 41.50 42.50 44.50 45.50 45.50 41.50 38.50	48.50 44.00 41.50 41.00 42.00 44.00 45.00 39.00 41.00 38.00	45.50 43.00 40.50 40.00 41.00 43.00 44.00 38.00 40.00 37.00	44.50 42.00 39.50 39.00 40.00 42.00 43.00 37.00 39.00	42.50 40.00 37.50 37.00 38.00 40.00 41.00 35.00 37.00 34.00
1 RR heavy melting	46.00 48.00 51.00 52.00 53.00 48.00 51.00 51.00 51.00 51.00 51.00 50.00 50.00 50.00	46.00 48.00 51.00 52.00 54.00 53.00 48.00 51.00 49.00 51.00 58.00 51.00	45.00 47.00 50.00 51.00 53.00 52.00 47.00 50.00 50.00 57.00 50.00	44, 50 46, 50 49, 50 50, 50 52, 50 51, 50 49, 50 49, 50 49, 50 49, 50 56, 50 49, 50 38, 50	44.00 48.00 49.00 50.00 52.00 51.00 46.00 49.00 47.00 49.00 49.00 49.00 38.00	43.00 45.00 48.00 49.00 51.00 55.00 45.08 48.00 46.00 48.00 55.00 48.00 37.00	43.15 45.15 48.15 49.15 59.15 59.15 46.15 48.15 48.15 48.15 50.15 50.15	42.86 44.80 47.00 48.80 50.00 49.00 47.00 47.00 47.00 54.00 47.00 54.00	41.50 43.50 46.50 47.50 49.50 48.50 46.50 46.50 46.50 53.50	41.00 43.00 46.00 47.00 49.00 48.00 46.00 44.00 46.00 53.00 46.00 35.00	40.00 42.00 45.00 46.08 48.00 47.00 42.00 45.00 45.00 52.00 52.00 34.00	39.00 41.00 44.00 45.00 47.00 48.90 41.00 44.00 44.00 51.00 44.00 33.00	37.00 39.00 42.00 43.00 45.00 44.00 39.00 42.00 42.00 42.00 42.00 31.00

Cast Scrap Ceilings

Prices set by CPR 5, OPS

(P.o.b. all shipping points)

Grades				O	PS	No.
Cupola cast					1	\$49.00
Charging box cast		·			2	47.00
Heavy breakable cast					3	45.00
Cast iron brake shoes	*					41.00
Stove plate			0	0	6	46.00
Clean auto cast					7	52.00
Unstripped motor blocks					8	43.00
Cast iron carwheels		0	0	0	9	47.00
Malleable	0	٠	0		10	55.00
Drop broken mach'y cast		0	0		11	52.00

Celling price of clean cast iron foundry runout or prepared cupola drops is 75 pct of corresponding grade.

Under Ceiling Scrap Prices

Pittsburgh

Machine shop turnings	\$32.00
Mixed borings, turnings	32.00
Cast iron borings\$35.00	to 35.50
No. 1 machinery cast	52 00
Heavy breakable cast	45.00
Malleable	55.00

Chicago

Low phos. forge crops \$	50.00	to	\$51.00
Low phos. 3 ft and under	44.00		45.00
Cut struc., plate, 2 ft & less	45.00	to	46.00
Cut struc., plate, 3 ft & less	43.50	to	44.50
Machine shop turnings	30.00	to	31.50
Mixed borings, turnings	34.00	to	35.50
Shoveling turnings	34.00	to	35.50
Cast iron borings	34.00	to	35.50
Cupola cast	44.00	to	45.00
Heavy breakable cast	41.00	to	42.00
Malleable	52.00	to	53.00
Stove plate	42.00	to	43.00
Clean auto cast	48,00	to	50.00
Charging box cast	43.00	to	44,00
Drop broken mach'y	48.00	to	49.00
Unstripped motor blocks.	36.00	to	38.00

Philadelphia Area

Clean	east	chem.	borings	 \$36.50	to	\$37.00
Cupol	a ca	st		 47.00	to	48.00
Unstr	ipped	l moto	r blocks	 41.00	to	42.00
Charg	ring	box ca	tat	 45.00	to	46.00

Cleveland

Cast iron	bo	ri	n	gs			*			\$34.00	to	\$34.50
Stove plat	0 .					0				45.00	to	46.00
Malleable								0	0	54.00	to	55.00

Youngstown

Cast	iron	borings				\$35.00	to	\$35.	.50

Buffalo

250	4	machinery	0000			49.00	* 0	\$50.00
INO.	A.	machinery	CSFRE	0	0 - 4	43.00	10	\$30.00
No.	1	cupola cast				46.00	to	47.00

Birmingham

Shoveling turnings					0	\$30.00	to	\$32.00
Cast iron borings						30.00	to	32.00
No. 1 cupola cast						46.00	to	47.00
Stove plate							to	42,50
Charging box cast							to	40.00
Heavy breakable						37.00	to	38.00
Drop broken mach	i	ne	ET	y		46.00	to	47.00
Unstripped motor							to	40.00

New York

Brokers' Buying prices per g	ross tor	on cars:
Clean cast chem. borings	\$30.00	to \$30.50
No. 1 machinery cast	48.00	to 50.00
Mixed vard cast		43.00
Charging box cast	43.00	to 44.00
Heavy breakable cast	44.00	to 45.00
Unstripped motor blocks.		36.00

Boston

Brokers'	Buying	prices	per	gross	ton.	on e	ars:	
Mixed -	eupola	cast		\$40	.00 to	341	0.0	
Heavy				. 41	of 00.	42	.00	
Stove 1					On to			
I'netrin	ned mo	tor ble	neks	. 30	00 to	3.1	.00	

Detroit

Brokers'	Buying	prices	per	gross	ton,	on	CRIS
No. 1 ct	ipola ci	ast				\$ 41	8.00
Heavy	breakat	le cas	t	. \$43.	.00 to	4	4.00
Stove p	ate			. 43.	.00 to	9	4.00
Cost inc	n brak	e shoe	9	3.9	00 to	4.6	0.00

Cincinnati

	cast	\$49.00
Stove plate . Drop broken	cast \$51.00 to	46.00 \$52.00
	St. Louis	

Charging box cast ... \$43.00 to \$44.00 No. 1 cupola cast 43.00 to \$43.00 Heavy breakable cast ... 41.00 to 42.00 Unstripped motor blocks ... \$38.00

San Francisco

No. 2 heavy melting	31.00
No. 2 bundles	 29.00
Machine shop turnings	 17.00
No. 1 cupola cast	 43.00

Los Angeles No. 2 heavy melting

\$31.00

0

No. 2 bundles Machine shop turnings Shoveling turnings No. 1 cupola cast	29.00 17.00 20.00 50.00
Seattle	
No. 2 bundles No. 1 cupola cast	\$29.00
Heavy breakable	35.50

Hamilton, Ont.

naminion, on.	
No. 1 hvy. melting	\$35.50
No. 1 bundles	35.50
No. 2 bundles	35.00
Mechanical bundles	33.50
Mixed steel scrap	31.50
Mixed borings, turnings	32.50
Rails, remelting	35.50
Rails, rerolling	44.80
Bushelings	30.50
Bush, new fact, prep'd	33.50
Bush, new fact, unprep'd	32.50
Short steel turnings	32.50
Cast scrap	50.00



Sometime during unrecorded history a meteoric mass, weighing
fifty tons, fell to earth at Bacubirito in Mexico . . . And long before
the white man established settlements in North America, the Aztecs
had developed an unusual skill in using iron from such meteorites to
fashion their knives, daggers and other instruments.

To the Aztecs, this "scrap" was important for tools of war and tools of peace . . . for our industrial and military uses of the 20th Century, an unfailing supply of scrap in millions of tons is urgently needed.

For the purchase or sale of iron or steel scrap . . . phone or write "Your Chicago Broker"



231 S. La Salle St., Chicago

Telephone ANdover 3-3900

Comparison of Prices

Steel prices on this page are to of major producing areas: P. Youngstown.					Pig Iron: (per gross ton) Oct. 14 Oct. 6 Sept. 16 Foundry, del'd Phila. \$60.69 \$60.69 \$60.69 Foundry, Valley 55.00 55.00 55.00	Oct. 16 1951 \$57.97 52.50
Price advances over previous declines appear in Italics.	week ar	e printed	in Heav	y Type.	Foundry, Southern. Cin'ti 58.93 58.93 58.93 Foundry, Birmingham 51.38 51.38	55.58 48.88
	Oct. 14 1952	Oct. 7 1952	Sept. 16 1952	Oct. 16 1951	Foundry, Chicago	52.50 57.09 52.00
Flat-Rolled Steel: (per pound) Hot-rolled sheets Cold-rolled sheets Galvanized sheets (10 ga) Hot-rolled strip	3.775¢ 4.575 5.075 3.725 5.20	3.775¢ 4.575 5.075 3.725 5.20	3.775¢ 4.575 5.075 3.725 5.20	3.60¢ 4.35 4.80 3.50 4.75	Malleable, Chicago	52.50 52.50 70.56 186.25
Cold-rolled strip Plate Plates wrought iron Strains C-R strip (No. 302)	3.90 9.00 36.75†	3.90 9.00 36.75†	3.90 9.00 36.75†	3.70 7.85 36.75	† The switching charges for delivery to foundries in the district is \$1 per ton. 2 Average of U. S. prices quoted on Ferroalloy pages.	Chicag
Fin and Terneplate: (per base bo Tinplate (1.50 lb.) cokes Tinplate, electro (0.50 lb.) Special coated mfg. ternes	\$8.95 7.65 7.75	\$8.95 7.66 7.75	\$8.95 7.65 7.75	\$8.70 7.40 7.50	Composite: (per gross ton) Property Pro	\$52.72
Bars and shapes: (per pound) Merchant bars Cold finished bars Alloy bars Structural shapes Stainless bars (No. 302) Wrought iron bars	3.95¢ 4.925 4.675 3.85 31.50† 10.05	3.95¢ 4.925 4.675 3.85 31.50† 10.05	3.95¢ 4.925 4.675 3.85 31.50† 10.05	3.70 <i>e</i> 4.55 4.30 3.65 31.50 9.50		\$44.00° 42.50° 42.50° 41.15° 46.50° 49.00† 49.00†
Wire: (per pound) Bright wire	5.225¢	6.225€	5.225€	4.85€	* Basing pt., less broker's fee. * Shipping pt., less broker's fee	
Rails: (per 100 lb) Heavy rails Light rails	\$3.775 4.25	\$3.775 4.25	\$3.775 4.25	\$3.60 4.00	Composite: (per gross ton) No. 1 heavy melting scrap \$42.00 \$42.00 \$42.00	\$43.00
Semifinished Steel: (per net ton) Rerolling billets Slabs rerolling Forging billets	59.00 70.50	\$59.00 59.00 70.50	\$59.00 59.00 70.50	\$56.00 56.00 66.00	Coke, Connellsville: (per net ton at oven) Furnace coke, prompt \$14.75	\$14.75 17.75
Alloy blooms, billets, slabs Wire Rod and Skelp: (per pound) Wire rods Skelp	76.00 4.325¢ 3.55	76.00 4.325¢ 3.55	76.00 4.325¢ 3.55	70.00 4.10e 3.35	Copper, electrolytic, Conn. 24.50 24.50 24.50 Copper, Lake, Conn. 24.525 24.625 24.625 Tin, Straits, New York \$1.21% \$1.2	24.50 24.625 \$1.03 19.50
† Add 4.7 pct.					Lead, St. Louis	18.80
Composite: (per pound) Finished steel base price	4.376e	4.376€	4.376¢	4.131e	Nickel, electrolytic	59.58 24.50 42.00

Composite Price Notes

Finished Steel Composite

Weighted index based on steel bars, shapes, plates, wire, rails, black pipe, hot and cold-rolled sheets and strips, representing major portion of finished steel shipment. Index respitulated in Aug. 28, 1941, issue and in May 12, 1949.

Starting with the issue of May 12, 1949, the weighted finished steel composite was revised for the years 1941 to date. The weights used are based on the average product shipments for the 7 years 1937 to 1940 inclusive and 1946 to 1948 inclusive. The use of quarterly figures has been eliminated because it was too sensitive. (See p. 139 of May 12, 1949, issue.)

Pig Iron Composite

Based on averages for basic iron at Valley furnaces and foundry iron at Chicago, Philadelphia, Buffalo, Valley and Birmingham.

Scrap Steel Composite

Average of No. 1 heavy melting steel scrap delivered to consumers at Pittsburgh, Philadelphia and Chicago.


Warehouse Price Notes

Base Quantities (Standard unless otherwise keyed): Cold finished bars; 2000 lb or over Alloy bars; 1000 to 1999 lb. All others; 2000 to 9999 lb. All HR products may be combined for quantity. All galvanized sheets may be combined for quantity. CR sheets may not be combined with each other or with galvanized sheets, for quantity.

Exceptions: (1)500 to 1499 lb, (3)1500 to 3499 lb, (3)6000 lb or over, (4)450 to 1499 lb.

WARE									Ваза	price, f.	o.b., dol	lars per	100 lb.
HOUSES		Sheets		Str	rip	Plates	Shapes	Ba	27.5		Alloy	Bars	
Cities. City Delivery	Charge Hot-Rolled	Celd-Relled (15 gage)	Galvanized (10 gage)	Hot-Rolled	Celd-Reliad		Standard	Het-Rellad	Cold. Finished	Het-Relied A 4615 As relied	Het-Relled A 4140 Annealed	Cold-Draws A 4615 As relied	Cold-Draws A 4148
Baltimere \$.	0 5.81	7.17	8.42-	6.42		6.30-	6.47	6.41	7.18-		******		
Birmingham	5 5.80	6.65	8.57 7.70 ¹	5.80		6.47	5.95-	6.71 5.80	7.43 8.25- 8.40				
Besten	0 6.48	7.35-	8.59-	6.55	8.501	6.75-	6.56-	6.38-	7.10-	10.78	11.15-		13.18
Buffale	5.80	6.60-	8.74 8.40- 8.46	6.16- 6.21	6.19	6.80 6.26- 6.37	6.75 5.96- 6.08	6.54 5.76- 5.90	7.63 6.90- 6.95	10.70	11.18 11.00- 11.07	12.70	12.51- 14.42
Chicago	5.80	6.65	8.05	5.83-		5.95-	5.95- 6.98	5.83	6.56-		10.65		12.65
Cincinnati		6.72	8.52	6.21		6.47	6.42	6.13	7.16		11.07		13.87
Cleveland	5.81	6.65	8.16- 8.19	6.00- 6.01		6.12- 6.22	6.28-	5.89	6.66- 6.98		10.79		12.79
Denver	7.17			7.43-7.69	8.90	7.37	7.50-	7.61-7.71	8.24	******	******	******	*****
Detroit	6.00		8.34	6.13	7.99	6.45-		6.12-	6.975- 7.21	10.72	10.92	12.72	13.02
Houston		- 7.78-	8.68	6.61-	9.80	6.63-		6.82-	9.60-	11.90	11.90		13.98
Indianapolis del'													
Kansas City	6.47	7.31	8.50- 8.72	6.51	8.07	6.62-	6.62	6.50	7.57	11.15-	11.45-	13.13-	13.43
Las Angeles	6.60		9.80-	6.74-	9.15	6.66-	6.60-	6,60-	8.36-		12.05		14.60
Memphis	0 6.56			6.60		6.71	6.71	6.57-	7.98-				
Milwaukee	5.97		8.22	6.00-		6.12-	6.12	6.00	6.83-		10.82		12.82
New Orleans	6.28	7.12		6.32		6.43	6.43	6.31	7.85				*****
New Tork	6.69	7.60	8.313	7.05	9.53	6.60- 7.19	6.70	6.59-	7.53- 8.05	10.74-	11.04- 11.28	12.74- 12.97	13.04
Nerfolk	7.10			6.81		6.64	7.25	6.44	8.45				
Philadelphia	6.38	7.92	8.79	6.45- 7.45		6.24-	6.17-	6,42-6,68	7.45-7.69	10.57	10.79- 11.02		12.79
Pittsburgh	5.80		8.05-	5.94-		5.95-	5.95	5.83	6,66-	, ,	10.65		12,65
Portland		9.00	10.25	7.60		7.30	7.30	7.35	9.45	******	******		
Salt Lake City			10.904	8.45		7.85	8.00	8.40	*****			x	
San Francisco	6.80		9.70- 10.40	6.79-	9.25-	7.10	6.70-	6.65-	8.40- 8.70		11.85		14.40
Seattle	20 7.46		9.60	7.39		7.19	6.91	7.22	9.37				
St. Louis	20 6.10		8.35-	6.14-	9.73	6.35-	6.35	6.13-	6.96-	10.65	10.95	12.65	12.95
St. Paul			8.71	6.50		6.61	6.61	6.49	7.32		l	·	l

Specify GLOBE for the finest steel tubes



assure uniform high-quality STEEL TUBES

AT Globe, specialization is the keynote. Men, machines, and raw materials are all tailored to fit the Globe specialized process. Precision checks - and rechecks - at every stage of production insure Globe Tubes that meet your exacting specifications.

Be sure! Specify dependable, high-quality Globe Steel Tubes and be certain of getting the finest tubes available. Write for the General Catalog and become acquainted with Globe specialized process.

GLOBE STEEL TUBES CO., Milwaukee 46, Wisconsin

Chicago • Cleveland • Detroit • New York • Houston • St. Louis Denver • San Francisco • Glendale, Cal. • Philadelphia

Globe's Physical Testing Laboratory one of the seven different research and testing labs in Globe's House of

GLOBE STEEL TUBES ARE AVAILABLE IN:

• Stainless Steels — Globe seamless • High Purity Iron — Globeiron • Stainless Steels Gloweld Welded . Corrosion Resistant Steels . Alloy Steels . Carbon Steel . High-Temperature Service Steels . Standard and Special Analysis Steels * Mechanical and Pressure Tubing

Bett Buff Clay Coal Con Har Har Har Har Har New Photo Span Alto Can Oth Chia Stee Cleve Det	thlehem, Pa. thlehem, Pa. thalo, N. Y. ayment, Del. atesville, Pa. mshoheckon, Pa. arrisburg, Pa. artford, Conn. hustown, Pa. twark, N. J. tw. Haven, Conn. arrows Pt., Md. breester, Mass. enton, N. J. ton, Ill. bland, Ky.	Carbon Forging Net Toa	Alloy Net Ton	Carbon Rerolling Net Ton \$59.00 B3	Carbon Foreing Net Ton \$70.50 B3	Alloy Net Ton \$76.00 B3 \$76.00 B3, R3	PIPE SKELP	Sheet Steel	SHA STRUCT Carbon 3.90 B3 3.90 B3		Hot- rolled 3.725 B3, R3	Cold-rolled	Hi Str. H.R. Low Alloy	Hi Str., C.R. Lev Afloy
Bett Buff Class Span Con Har	thlehem, Pa. Iffalo, N. Y. aymont, Del. atesville, Pa. Inshoheckon, Pa. Intrinder, Conn. Instown, Pa. Itwark, N. J. Itwark, N. J. Itwark, Conn. It	Forging	Alloy Net Ton	Rerolling Net Ton	Forging Net Ton \$70.50 B3, R3 \$77.50 A2	\$76.00 B3 \$76.00 B3, R3		Steel	3.90 B3	Low Alloy 5.80 B3	3.725 B3,	rolled	H.R. Low Alloy	C.R. Lov
Buffi Clays Coan Com Har Har Har New Phon New Can Oh Chic Ste Clev Det	ayment, Del. ayment, Del. atesville, Pa. anshohecken, Pa. arrisburg, Pa. artford, Conn. anstown, Pa. awark, N. J. aw Haven, Conn. arrows Pt., Md. arrows Pt., Md. arcester, Mass. eenton, N. J.				\$77.50 A2	\$76.00 B3,		4.675 B3			3.725 <i>B</i> 3, <i>R</i> 3	5.10 <i>B</i> 3	5.70 B3	7.90 B3
Clay Coan Har Har John New Pho Putt Spa Alte Ash Can Oh Chia Ste	ayment, Del. atesville, Pa. mshohecken, Pa. mrisborg, Pa. mrisborg, Pa. mristown, Pa. mark, N. J. me Haven, Conn. moenixville, Pa. minam, Conn. marrows Pt., Md. mrcester, Mass. eenton, N. J.				\$77.50 A2	\$76.00 B3,		4.675 B3			3.725 <i>B</i> 3, <i>R</i> 3	5.10 B3	5.70 B3	7.90 B3
Coan Har Har John New Pho Putt Spaa Weir Car Oh Chie Ste Dul Gar Ince	atesville, Pa. nshohockon, Pa. nrisburg, Pa. nrisburg, Pa. nrisburg, Pa. nristown, Pa. nristown, Pa. nristown, Pa. nristown, Pa. nristown, Pa. nristown, Conn. nristown, Conn. nristown, Conn. nristown, Conn. nristown, Conn. nristown, Conn. nristown, Mass. nriston, N. J. ton, III.			\$59.00 B3	\$77.50 A2	\$83.00 A2								
Con Har	nshohecken, Pa. arrisburg, Pa. arrisburg, Pa. arrisord, Conn. hnstown, Pa. awark, N. J. aw Haven, Conn. aconixville, Pa. attnam, Conn. arrows Pt., Md. arcester, Mass. enton, N. J. ton, III.			\$59.00 B3	•	\$83.00 A2	****							
Harr Harr John New Phon New Alter Ash Ash Cannot Chief Stee Dull Gar Inc.	nerisborg, Pa. nerford, Conn. hnstown, Pa. newark, N. J. new Haven, Conn. noenixville, Pa. nernam, Conn. nerrows Pt., Md. nercester, Mass. enton, N. J. ton, III.			\$59.00 B3	•	\$83.00 A2								
Harry John New Pho Putt Span Alte Anh Can Oh Chin Ste	ortford, Conn. hnstown, Pa. twark, N. J. tw Haven, Conn. toenixville, Pa. ttnam, Conn. arrows Pt., Md. preester, Mass. enton, N. J. ton, III.			\$59.00 B3							4.125 A2		5.90 A2	
John New Puts Span Alto Ash Can Ob Chia Ste	hnstown, Pa. wark, N. J. w Haven, Conn. moenixville, Pa. ntnam, Conn. arrows Pt., Md. mrcester, Mass. enton, N. J. ton, III.			\$59.00 B3										
New	twark, N. J. w Haven, Conn. noenixville, Pa. ntnam, Conn. arrows Pt., Md. orcester, Mass. enton, N. J. ton, III.			\$59.00 B3	\$70.50 B3									
Pho Putt Span Word Tree Alto Carn Oh Chie Ste	tw Haven, Conn. toenixville, Pa. ttnam, Conn. arrows Pt., Md. ercester, Mass. enton, N. J. ton, III.					\$76.00 B3			3.90 B3	5.80 B3	3.725 B3			
Pho Putter Span West Treet Alto Cara Oh Chie Ste	oenixville, Pa. ttnam, Conn. arrows Pt., Md. orcester, Mass. enton, N. J.													
Putus Span West Trees Alto Ash Can Ob Chie Ste	etnam, Conn. arrows Pt., Md. brcester, Mass. enton, N. J. ton, IH.											5.60 A5 5.85 D1		
Span Word Tree Alta Ashh Can Oh Chie Ste	arrows Pt., Md, orcester, Mass. enton, N. J.								6.10 P2					
West Tree Alta Ash Can Oh Chic Ste Det	enton, N. J.			7-11										
Tree Alto Ash Can Oh Chie Ste Det	enton, N. J.										3.725 B3	5.10 B3	5.70 B3	7.90 B3
Alto Ash Can Oh Chic Ste Det	ton, III.													
Cleve Dul												6.45 R4		
Can Oh Chic Ste Clev Det	hland, Ky.										4.20 L1			
Clev Det											3.725 A7			
Cleri	nten-Massillon, thie				\$70.50 R3	\$76.00 R3 \$78.60 T5								
Dul Gar	icage, terling, III.			\$59.00 U1	\$70.50 U1, R3,W8	\$76.00 U1, R3,W8		4.675 U1	3.85 U1, W8	5.80 UI	3.725 A1,W8 4.725 N4	5.35 Al		
Dul Gar Inc	eveland, Ohio				\$70.50 R3							5.10 A5,J3		7.45 J3
Gar Inc	etroit, Mich.	\$56.00 R5	\$57.00 R5		\$73.50 R5	\$79.00 R5				Andrews Andrews Andrews	4.025 G3 4.40 M2	5.30 <i>G</i> 3 5.45 <i>M</i> 2 5.60 <i>D</i> 1 6.05 <i>D</i> 2	6.30 G3	8.15 G3
	aluth, Minn.					-								
2	ary, Ind. Harbor, ndiana			\$59.00 UI	\$70.50 U/	\$76.00 UI, YI		4.675 13	3.85 <i>13</i> , <i>U1</i>	\$.80 <i>13</i> , <i>UI</i> 6.30 <i>YI</i>	3.725 <i>I</i> 3, <i>UI</i> , <i>YI</i>	5.35 /3	5.65 13, UI 6.15 YI	
Gra	anite City, III.								-					
-	kome, Ind.													
-	iddletown, Obio											5.19 A7		
	les, Ohio		*								4.225 SI	5.80 SI	5.65 SI	7.30 5/
-	itsburgh, Pa.	\$\$4.00 U1	\$57.00 UI	\$59.00 UI,	\$70.50 UI.	\$76.00 UI	3.55 U! 3.65 J3	4.675 U1	3.85 U1, J3	5.80 U1,J3	3.725 J3,A7 3.975 A3°	5.10 J3, A7 5.45 A3		-
_											4.225 S7,S9	5.80 B4,S7		-
-	ortsmouth, Ohio								4.10.11/2		2 025 11/2	E 10 /2/2	£ 10 14/2	7.95 W
Fo	eirton, Wheeling, ollansbee, W. Va.								4.10 W3		3.825 W3	5.10 W3	6.10 W3	
You	oungstown, Ohio					\$76.00 Y1. C10	3.55 U1, R3			6.30 Y/	3.725 U1. Y1,R3	5.10 R3, YI 5.70 C5 5.80 B4	5.65 R3, UI 6.15 YI	7.30 R 7.80 Y
Fon	entana, Cal.	\$81.00 K1	\$83.00 K/	\$78.00 K/	\$89.50 K!	\$95.00 K/			4.45 K1	6.40 K1	4.975 K1	6.75 K1	6.55 KI	
Ger	eneva, Utah				\$70.50 C7				3.85 C7	5.80 C7				
Kar	ansas City, Mo.								4.45 S2		4.325 S2			
Les To	s Angeles, orrance, Cal.				\$89.50 B2	\$96.00 B2			4.45 C7,B2	6.35 <i>B2</i>	4.475 C7,B2	6.85 C/	6.40 B2	
	innequa, Colo.								4.30 C6		4.775 C6			-
Pi	n Francisco, Niles, Pittsburg, Cal.				\$89.50 B2		-		4.40 B2 4.56 P9	6.30 B2	4.475 C7,B2		6.40 B2	
					\$89.50 B2				4.50 B2	6.40 B2	4.725 B2		6.65 B2	
Bir	eattle, Wash.			\$59.00 72	\$70.50 T2		-		3.85 T2,R3	5.80 T2	4.275 A8 3.725 T2,R3			
Ho			\$65.00 S2	-	\$78.50 S2	\$84.00 S2	-		4.25 S2		4.125 S2		-	-

3.77

4 175

3.775

3.775 /3 3.975

4.30 G

4.175 5

3.775 W W5

4.725 K 3.875 C

4.475 C

3.775 T. R3

Tn

				SHEETS	5				WIRE ROD	TINP	PLATE	BLACK PLATE	STEEL PRICES
ot-rolled 18 ga. k hvyr.	Cold- rolled	Galvanized 10 ga.	Enameling 12 ga.	Long Terne 10 ga.	Hi Str. Low Alloy H.R.	Hi Str. Low Alloy C.R.	Hi Str Low Alloy Galv.	Hot- rolled 19 ga.		Cokes* 1.25-lb. base box	Electro* 0 25 lb. base box	Hollowware Enameling 29 ga.	
													Bethlehem, Pa.
3 775 B3	4.575 B3				5.675 B3	6.925 B3							Buffalo, N. Y.
									-	+ Special e	antad mla		Claymont, Del
					-					† Special coated mfg ternes deduct 95c from 1.25-lb coke base box		-	Coatesville, Pa.
1 175 42					5.925 A2					price. Can-	making quality		Conshohocken, Pa.
1113 774				**	3.363 712			-		deduct \$2.20 coke base b	0 from 1.25-lb		Harrisburg, Pa.
					-			-		* COKES:	1.50-lb	-	Hartford, Conn.
	-		-		-	-			4.325 B3	ELECTRO: 0.50-lb add 25c; 0.75-lb add 65c.		-	Johnstown, Pa.
				-		-			4.000 027				Newark, N. J.
	-								-				New Haven, Conn.
													Phoenixville, Pa.
									-				Putnam, Conn.
3.775 <i>B3</i>	4.575 B3	5.075 B3			5.675 B3	6.925 B3	7.775 B3		4.425 B3	\$8.80 B3	\$7.50 B3		Sparrows Pt., Md.
									4.625 A5				Worcester, Mass.
									4.425 R4				Trenton, N. J.
									4.70 <i>L1</i>				Alten, III.
3.775 A7		5.075 A7	4.925 A7						-				Ashland, Ky.
		5.075 R3								-			Canton-Massillen, Ohio
3.775 W/8					5.675 UI				4.325 A5, N4,R3				Chicago, Sterling, III.
3.775 R3,	4.575 R3,		4.925 R3		5.675 R3,	6.925 R3,			4.325 A5				Cleveland, Ohio
J3 3.975 G3	4.775 G3				6.225 G3	7.475 G3							Detroit, Mich.
													Duluth, Minn.
3.775 <i>[3,</i> UI, YI	4.575 /3, UI, YI	5.075 <i>13</i> , <i>U1</i>	4.925 U1	5.475 U/	5.675 <i>13</i> , <i>UI</i> 6.175 <i>YI</i>	6.925 <i>13</i> , <i>U1</i> 7.425 <i>Y1</i>			4.325 Y1	\$8.70 UI, 13, YI	\$7.40 UI.	6.10 UI. YI	Gary Ind. Harbor, Indiana
4.30 GZ	5.275 G2	5.50 G2	5.625 G2								\$7.60 G2	6.30 G2	Granite City, Ht.
		5.475 C9											Kokomo, Ind.
	4.575 A7		4.925 A7	5.475 A7									Middletown, Ohio
4.175 <i>S1</i>					5.675 SI						\$7.40 R3		Niles, Ohio Sharon, Pa.
3.775 UI, J3, A7 3.925 A3	4.575 U1, J3, A7	5.075 UI	4.925 UI		5.675 U1, J3	6.925 UI, J3	7.625 UI		4.325 A5	\$8.70 U1, J3	\$7.40 U1,	6.10 UI	Pittsburgh, Pa.
									4.525 P7				Portsmouth, Ohio
3.775 W3, W5	4.575 W3, W5	5.075 W3, W5		5.475 W3, W5	6.025 W3	7.275 W3				\$8.70 W3, W5	\$7.40 W3, W5	6.35 W5	Weirton Wheeling, Follansbee, W. Va.
3.775 UI, R3. YI	4.575 R3, Y1	5.775 R1	4.925 Y/	6.05 E2	5.675 R3. U1 6.175 Y1	6.925 R3 7.425 Y1		5.65 <i>E2</i> 5.825 <i>R1</i>	4.325 Y1	\$8.70 R3			Youngstewn, Ohio
4.725 K1	5.525 K1				6.625 K1	7.875 K1			5.125 K1				Fontana, Cal.
3.875 C7													Geneva, Utah
													Kansas City, Mo.
4.475 C7		5.825 C7						5.575 C7	5.125 C7,B2				Los Angeles, Torrance, Cal.
	-				-				4.575 C6				Minnequa, Colo.
4.475 C7	5.525 C7	5.825 C7							4.975 C7	\$9.45 C7	\$8.15 C7		San Francisco, Niles Pittsburg, Cal.
													Seattle, Wash.
													Atlanta, Ga.
3.775 T2, R3	4.575 T2	5.075 T2, R3			5.675 T2			4.925 R3	4.325 T2. R3	\$8.80 T2	\$7.50 T2		Birmingham, Ala., Alabama City, Ala.
									4.725 S2				Houston, Tex

SI


W3

R3 YI

				producers listed								
	STEEL PRICES			BA	RS				PLA	TES		WIRE
		Carbon Steel	Reinforc-	Cold Finished	Alloy Hot- rolled	Alloy Cold Drawn	Hi Str. H.R. Low Alloy	Carbon Steel	Floor Plate	Alloy	Hi Str. Low Alloy	Mfgr's Bright
	Bethlehem Pa.				4.675 B3	6.00 B3	5.925 B3					
	Buffale N. Y.	3.95 B3,R3	3.95 B3,R3	4.975 B5	4.675 B3,R3	6.00 B3,B5	5.925 B3	3.90 B3	****		5.95 <i>B3</i>	
	Clayment Del.							4.35 C4	-	5.35 C4		
	Contesville Pa.							4.35 L4		5.75 L4		
	Conshohocken Pa.							4.35 A2	4.95 /12	3.13 L4	6.20 A2	
	Harrisburg Pa.	-						6.50 C3	6.50 C3		0.20 /12	
	Hartford Conn.			5.475 R3		6.45 R3		0.50 €5				
ST	Jehnstewn Pa.	3.95 B3	3.95 B3		4.675 B3		5.925 <i>B3</i>	3.90 B3		5.25 B3	5.95 B3	5.225 B3
EAST	Newark N. J.		3.80 111	5.375 W10		6.35 W10						
	New Haven Cenn.											
	Phoenizville Pa.									-		
	Patnam Cenn.			S.475 W10								
	Sparrows Pt. Md.		3.95 B3					3.90 B3		5.25 B3	5.95 B3	5.325 B3
	Worcester Mass.					6.35 A5						5.525 A5
	Trenten N. J.											
	Alten III.	4.50 L/										5.45 L1
	Ashland Ky.							3.90 A7				
	Canton-Massillen	3.95 R3		4.925 R2,R3	4.675 R3 4.72 T5	5.99 T5 6.00 R2,R3						
	Chicage Sterling III.	3.95 U,W8, R3, 4.55 N4	3.95 R3 4.70 N4	4.925 A5,B5, W8,W10	4.675 R3 U1, W8	6.00 B5, L2, R3, W8, W10 6.05 A5		3.90 U1, W8	4.95 UI	5.25 UI	5.95 U1	\$.225 A3 N4, R3 5.325 K2 5.475 W7
	Cleveland Ohio	3.95 R3	3.95 R3	4.925 A5,C13		6.00 C13 6.05 A5	5.925 R3	3.90 R3,J3	4.95]3		5.95 R3, J3	5.225 A5 C13,R3
	Detroit Mich.	4.10 <i>R5</i> 4.30 <i>G3</i>		5.075 R5,P8 5.175 P3	4.825 <i>R5</i> 5.025 <i>G3</i>	6.15 <i>R5</i> , <i>P8</i> 6.20 <i>P3</i>	6.675 G3	4.45 G3			6.90 G3	-
ST	Duluth Minn.											5.252 A5
WEST	Gary Ind. Harber	3.95 13, U1,	3.95 /3, UI,	4.925 L2,	4.675 13, U1,	6.90 L2,M5,	5.925 <i>13, U1,</i>	3.90 13, U1,	4.95 /3	5.25 UI	5.95 13, UI	5.325 M4
DIE	Indiana	Y1	Y1	M5,R3	Y/	R3,R5	6.425 Y/	Y/			6.45 Y/	
MIDDLE	Granite City III.							4.60 G2				
1	Kekeme Ind.				-							5.325 C9
	Middletown Ohio											
	Niles Ohie							4.15 5/		5.70 SI	5.95 SI	
	Sharen Pa. Pittsburgh Pa.	3.95 U1,J3	3.95 U1, J3	4.925 A5, J3, W10, R3, C8	4.675 U1, J3	6.00 W10,C8 6.05 A5	5.925 U1, J3	3.90 U1,J3	4.95 U1, J3	5.25 U1, J3	5.95 U1,J3	5.225 A
	Pertsmouth Ohie											5.625 P7
	Weirten Wheeling	4.10 W3				-		3.90 W5		-		0.460 //
	Fellansbee W. Va.	*.14 17 /						4.20 W3				
	Youngstewn Ohio	3.95 U1, Y1, R3	3.95 U1, Y1, R3	4.925 Y/	4.675 UI,CIO, YI	6.00 C10, Y1	5.925 <i>U1</i> 6.425 <i>Y1</i>	3.98 UI, YI, R3			5.95 R3 6.45 Y1	5.225 Y
_	Fentana Cal.	4.65 K/	4.65 K1		5.725 KI		6.975 K1	4.50 K/		6.20 K1	6.55 K1	
	Geneva Utah							3.90 C7			5.95 C7	-
	Kansas City Me.	4.55 S2	4.55 S2		5.275 S2							5.825 SI
WEST	Les Angeles Terrance Cal.	4.65 C7,B2	4.65 C7,B2	6.375 R3	5.725 B2		6.625 B2					6.175 C7
R	Minnequa Colo.	4.40 C6	4.75 C6					4.70 C6				5.475 C6
	San Francisco Niles Pittsburg Cal	4.65 C7,P9 , 4.70 B2	4.65 C7,P9 4.70 B2				6.675 B2					6.175 C6
	Seattle Wash.	4.70 B2	4.70 B2				6.675 B2	4.80 B2			6.85 B2	
	Atlanta Ga.	4.50 A8	4.50 A8		İ							5.475 A
SOUTH	Birmingham Ala. Alamama City Ala.	3.95 T2,R3	3.95 T2,R3				5.925 T2	3.90 T2,R3			5.95 T2	5.225 T
S	Houston Tex.	4.35 S2	4.35 S2	1	5.075 S2			4.30 S2				5 625 S

CONTINENTAL CHIPPER

MECHANICAL CHIPPING AND CONDITIONING



Complete Rolling Mill Installations:

BLOOMING MILLS . STRUCTURAL MILLS . RAIL MILLS BILLET MILLS . ROD MILLS

BAR MILLS • MERCHANT MILLS • SLABBING MILLS UNIVERSAL MILLS • PLATE MILLS

HOT STRIP MILLS + COLD STRIP MILLS + TEMPER MILLS ROLL LATHES + SPECIAL MACHINERY

CHICAGO - FILLED COM

CHICAGO · PITTSBURGH

CASTINGS—carbon and alloy steel from 20 to 250,000 pounds

ROLLS iron, alloy iron and steel rolls for all types of rolling mills

WELDMENTS fabricated steel plate, composite materials, or east-weld assemblies.





E

YI

SI

5 C6

5 C6.C7

5 A8

5 T?

5 S2

95

5 C7, B1

Plants at: Fast Chicago, Ind. • B heeling, B . Ja. • Pittsburgh, Pa.



- Upon the correct metal hardness rests the length of life you can expect from the gears you use. Good gear making consists of more than meets the eye. You can see a bad job of machining, but you can't see that the metal is too soft or too hard—until the gears give trouble.
- Here at BRAD FOOTE we make sure of metal hardness. We hold to extremely close tolerances checked carefully on the latest and best hardness-testing equipment.
 Nothing is left to chance, and no one shares our responsibility.
 So, when you buy BRAD FOOTE gears for your own use, or for use on equipment you make for others, you know that they will give long, satisfactory service.
- BRAD FOOTE makes every type of gear, out of any type of material. BRAD FOOTE makes speed reducers, gearmotors, transmissions, and intricate power units. We would like to discuss your requirements and make recommendations, or quote on your specifications. We'll give you prompt service.



subsidiaries

AMERICAN GEAR & MFG. CO. • PITTSBURGH GEAR COMPANY
Phone: Lemont 920
Phone: ATlantic 1-9950
Pittsburgh 22, Pennsylvania

B2 B3 B4

C2 C3 C4 C5 C6 C7 C8 C9 C10

E2

GI G2

HI

]1]2]3

K1 K2 K3

LI L2

L3

MI M2

M4 M5

N2

TH

Key to Steel Producers

With Principal Offices

- Acme Steel Co., Chicago
- Alan Wood Steel Co., Conshohocken, Pa. Allegheny Ludlum Steel Corp., Pittsburgh
- American Cladmetals Co., Carnegie, Pa.
- American Steel & Wire Div., Cleveland
- Angell Nail & Chaplet Co., Cleveland
- Armco Steel Corp., Middletown, O. 48 Atlantic Steel Co., Atlanta, Ga
- Babcock & Wilcox Tube Co., Beaver Falls, Pa.
- Bethlehem Pacific Coast Steel Corp., San Francisco
- Bethlehem Steel Co., Bethlehem, Pa., Blair Strip Steel Co., New Castle, Pa. H3
- 85 Bliss & Laughlin Inc., Harvey, Ill.
- Calstrip Steel Corp., Los Angeles
- Carpenter Steel Co., Reading, Pa.
- Central Iron & Steel Co., Harrisburg, Pa
- Claymont Products Dept., Claymont, Del.
- Cold Metal Products Co., Youngstown
- Colorado Fuel & Iron Corp., Denver
- Columbia-Geneva Steel Div., San Francisco
- Columbia Steel & Shafting Co., Pittsburgh
- Continental Steel Corp., Kokomo, Ind.
- Copperweld Steel Co., Glassport, Pa.
- C// Crucible Steel Co. of America, New York
 C// Cumberland Steel Co., Cumberland, Md.
- C13 Cuyahoga Steel & Wire Co., Cleveland
- DI Detroit Steel Corp., Detroit
- 02 Detroit Tube & Steel Div., Detroit
- D3 Driver Harris Co., Harrison, N. J.
- Eastern Stainless Steel Corp., Baltimore
- E? Empire Steel Co., Mansfield, O.
- Firth Sterling Steel & Carbide Corp., McKeesport, Pa.
- F2 Fitzsimmons Steel Corp., Youngstown
 F3 Follansbee Steel Corp., Follansbee, W. Va.
- Gl Globe Iron Co., Jackson, O.
- G2 Granite City Steel Co., Granite City, Ill.
- Great Lakes Steel Corp., Detroit
- HI Hanna Furnace Corp., Detroit
- 12 Ingersoll Steel Div., Chicago
- Inland Steel Co., Chicago
- Interlake Iron Corp., Cleveland
- Jackson Iron & Steel Co., Jackson, O.
- Jessop Steel Corp., Washington, Pa.
- Jones & Laughlin Steel Corp., Pittsburgh Joslyn Mfg. & Supply Co., Chicago
- KI Kaiser Steel Corp., Fontana, Cal. K2 Keystone Steel & Wire Co., Peoria
- K3 Koppers Co., Granite City, Ill.
- Laclede Steel Co., St. Louis L2 La Salle Steel Co., Chicago
- Lone Star Steel Co., Dallas
- L4 Lukens Steel Co., Coatesville, Pa.
- MI Mahoning Valley Steel Co., Niles, O.
- M2 McLouth Steel Corp., Detroit
 M3 Mercer Tube & Mfg. Co., Sharon, Pa.
- M4 Mid-States Steel & Wire Co., Crawfordsville, Ind.
 M5 Monarch Steel Co., Inc., Hammond, Ind.
- Mystic Iron Works, Everett, Mass.
- National Supply Co., Pittaburgh National Tube Co., Pittsburgh N2
- Niles Rolling Mills Co., Niles, O.
- N4 Northwestern Steel & Wire Co., Sterling, Ill.
- 01 Oliver Iron & Steel Co., Pittsburgh

GE

- Page Steel & Wire Div., Monessen, Pa.
- Phoenix Iron & Steel Co., Phoenixville, Pa.
- Pilgrim Drawn Steel Div., Plymouth, Mich.
 - Pittsburgh Screw & Bolt Co., Pittsburgh
 - Pittsburgh Coke & Chemical Co., Pittsburgh

- P6 Pittsburgh Steel Co., Pittsburgh
- P7 Portsmouth Div., Detroit Steel Corp., Detroit
- P8 Plymouth Steel Co., Detroit
- P9 Pacific States Steel Co., Niles, Cal.
- RI Reeves Steel & Mfg. Co., Dover, O.
- R2 Reliance Div. Eaton Mfg. Co., Massillon, O.
- R3 Republic Steel Corp., Cleveland R4 Roebling Sons Co. (John A.), Trenton, N. J.
- R5 Rotary Electric Steel Co., Detroit
- S1 Sharon Steel Corp., Sharon, Pa
- Sheffield Steel Corp., Kansas City Shenango Furnace Co., Pittsburgh 52
- 53
- S4 Simonds Saw & Steel Co., Fitchburg, Mass. S5 Sloss Sheffield Steel & Iron Co., Birmingham
- Standard Forging Corp., Chicago
- **S7** Stanley Works, New Britain, Conn 58
- Superior Drawn Steel Co., Monaca, Pa 59
- Superior Steel Corp., Carnegie, Pa. S10 Sweet's Steel Co., Williamsport, Pa
- S11 Seidelhuber Steel Rolling Mills, Seattle
- 71 Tonawanda Iron Div., N. Tonawanda, N. Y. Tennessee Coal & Iron Div., Birmingham
- T3 Tennessee Products & Chem. Corp., Nashville
- T4 Thomas Steel Co., Warren, O.
- Timken Steel & Tube Div., Canton, O.
- 76 Tremont Nail Co., Wareham, Mass.
- UI United States Steel Co., Pittsburgh
- U2 Universal-Cyclops Steel Corp., Bridgeville, Pa.
- W1 Wallingford Steel Co., Wallingford, Cor
- W2 Washington Steel Corp., Washington, Pa.
- W3 Weirton Steel Co., Weirton, W. Va. W4 Wheatland Tube Co., Wheatland, Pa
- W5 Wheeling Steel Corp., Wheeling, W. Va. W6 Wickwire Spencer Steel Div., Buffalo
- W7 Wilson Steel & Wire Co., Chicago
- W8 Wisconsin Steel Co., S. Chicago, Ill. W9 Woodward Iron Co., Woodward, Ala.
- W10 Wyckoff Steel Co., Pittsburgh
- YI Youngstown Sheet & Tube Co., Youngstown

MERCHANT WIRE PRODUCTS

	Standard & Coated Nails	Woven Wire Fence 9-15½ ga.	Fence Pests	Single Leep Bale Ties	Twisted Barbless Wire	Gal. Barbed Wire	Merch, Wire Ann'ld	March, Wire Gal.
Fob Mill	Col	Col	Col	Cel	Col	Col	¢/lb	e/lb
Alabama City R3°+	118	135		132		184	6.075	6.325
Aliquippa Pa 13		141				148	6.075	6 525
Atlanta A8	130			135			6.325	
Harlonville A.2	127	139	140				6.075	
Ruffalo W6							0.010	0.50
Buffalo W6 Chicago N4°	118	137		132	146	146	6.075	6 425
Cleveland A6	-							
Cleveland A5								6.225
Crawfrdsvl M4		140		134			6.175	
Donora Pa 45*	119	133				142	6.075	6.225
Duluth 45*	118	133		132		142	6.075 6.075	6.225
Fairfield Ala 72° Houston S2	118	133		132		142	6.075	6.225
Houston S2	135	147				156	6.475	6.925
Johnson Pa Kii	1177				149			6.575
Joliet III A5°	118	133		132		142	6.075	6.225
Kokomo Ind C9							6.175	
Los Angeles B2								
Kansas City S2	139			144		160	6.675	7.125
Minnequa C6*	123	146	138	137		153	6.325	6.70
Monessen P6								
Moline III R3			136					
Pittaburg Cal C7*	137	156		156	162	162	7.025	7.125
Dittaburah P6	197	178			147	147	6.075	6.45
Portsmouth P7 Rankin Pa A5*	132						6.47	
Rankin Pa A5*	118	133				142	6.075	6.225
So Chicago R3°†	118	135	140	132		144	6.075	6.325
S San Fran C6				156		167	6.075 7.025	7.40
Sparrows Pt B3	129			134	151			6.675
Sparrows Pt B3 Struthers O Y/1							6.075	
Torrance Cal C7°.	138						7.025	
Worcester A5°	124						6.375	
Williamsport	-							
Pa S10								

Cut Nails carleads base \$7.80 per 100 lb. (less 20¢ to jobbers) at Conshehocken Pa. (A2) Wheeling W. Vs. (W5) \$7.80.

- * Add 45¢ per 100 lb. on Std. & Coated Nails.
- † Zinc axtra if not included on Galv Morch Wire.
- 2 Galv. Merch. Wire based on 15¢ Zinc.

STAINLESS STEELS			Base price, cents per lb, f.o.b. mill. Ads 4.7 pct								
Product	301	302	303	304	316	321	347	410	416	430	
Ingets, rerelling	14.25	15.25	16.75	16.25	24.75	20.00	21.75	12.75	14.75	13.00	
Slaba, billets, rerolling	18.50	20.00	22.00	21.00	32.25	26.25	28.50	16.50	20.00	16.75	
Forg. discs, die blocks, rings	34.00	34.25	36.75	35.75	53,00	40.25	44.75	28.00	28.50	28.50	
Billets, forging	26.25	26.50	28.50	27.75	41.50	31.25	35.80	21.50	22.00	22.00	
Bars, wires, structurals	31.25	31.50	34.00	33.00	49.25	37.00	41.50	25.75	26.25	26.25	
Plates	33.00	33.25	35.25	35.25	52.00	40.75	45.25	27.00	27.50	27,50	
Sheets	41.00	41.25	43.25	43.25	57.00	49.25	53.75	36.50	37.00	39.00	
Strip, het-relled	26.50	28.25	32.50	30.25	48.75	37.00	41.25	23.50	30.25	24.00	
Strip, cold-rolled	34.00	36.75	40.25	38.75	59.00	48.25	52.25	30.50	37.00	31.00	

STAINLESS STEEL PRODUCING POINTS—Sheets. Midland, Pa., C11 Brackenridge, Pa., A3 Butler, Pa., A7 McKeesport, Pa., U1 Washington, Pa., W2 (type 316 add 4.54) J2 Baltimore, E1 Middletown, O., A7 Massillon, O., R3 Gary, U1&Bridgeville, Pa., U2 New Castle, Ind., 12 Ft. Wayne, J4 Lockport, N. Y., R4. A

Strip, Midland, Pa., C1 Cleveland, A5 Carnegie, Pa., S9 McKeesport, Pa., F1 Reading, Pa., C2 Washington, Pa., W2 (type 316 add 4.5¢); W. Leechburg, Pa., A3 Bridgeville, Pa., U2 Detroit, M2 Canton-Massillon, O., R3 Middletown, O., A7 Harrison, N. J., D3 Youngstown, C5 Lockport, N. Y., S4 Sharon, Pa., S1 (type 301 add ½¢); Butler, Pa., A7 Wallingford, Conn., W1.

Bars. Baltimore, A7. Duqueme, Pa., UI. Muchall, Pa., UI. Reading, Pa., C2. Titusville, Pa., U2. Washingten, Pa., McKeesport, Pa., UI. FI. Bridgeville, Pa., U2. Dunkirk, N. Y., A3. Massillon, O., R3. Chicago, UI. Syracuse, N. Y., I. Watervliet, N. Y., A3. Waukegan, A5. Lockport, N. Y., S4. Canton, O., T5. Ft. Wayne, J4.

Wires, Waukegan, A5 Massillon, O., R3 McKeesport, Pa., F1 Ft. Wayne, J4 Harrison, N. J., D3 Baltimore, A7 Dunkirk, A3 Monessen, P1 Syracuse, C11 Bridgeville, U2.

Structurals. Baltimore, A7 Massillon, O., R3 Chicago, Ill., J4 Watervliet, N. Y., A3 Syracuse, C11.

Plotes. Brackenridge, Pa., 43 (type 416 add 1/46); Butler, Pa., 47 Chicago, Ul Munhall, Pa., Ul Midland, Pa., Cll New Castle, Ind., 12 Lockport, N. Y., S4 Middletown, 47 Washington, Pa., J2 Cleveland, Massillon, R3.

Forged discs, die blocks, rings. Pittsburgh, C11 Syracuse, C11 Ferndale, Mich., A3 Washington, Pa., J2. Forging billets. Midland, Pa., CII Baltimore, A7 Washington, Pa., J2 McKeesport, F1 Massillon, Canton, O., R3 Watervliet, A3 Pittsburgh, Chicago, UI; Syracuse, CII.

ALLEGHENY LUDLUM-Slightly higher on Type 301; slightly lower on others in 300 series.

WASHINGTON STEEL-Slightly lower on 300 series except where noted.

PIPE AND TUBING

Base discounts f.e.b. mills. Base price about \$200 per net ton.

		BUTTWELD															SEAN	ILESS		
	1/2	In.	3/4	In.	1	In.	11/4	In.	11/2	In.	2 1	In.	21/2-	3 In.	2	ln.	21/2-	3 In.	31/2	4 In.
STANDARD T. & C. Sparrews Pt. B3 Toungstown R3 Fontan KI Pittsburgh J3 Alton III. L1 Sharen M3 Pittsburgh N1 Wheeling W5 Wheatland W4 Toungstown Y1 LIndiana Harber Y1 Lerain N2	Blk. 30.5 32.5 21.0 32.5 31.5 32.5 32.5 32.5 32.5 32.5 32.5 32.5	8.25 10.25 +1.25 10.25 9.25 9.25 10.25 10.25 10.25 10.25 10.25	Blk. 33.5 35.5 24.0 35.5 34.5 35.5 35.5 35.5 35.5 35.5 34.5 35.5	Gal. 12.25 14.25 2.75 13.25 13.25 14.25 14.25 14.25 14.25 14.25 14.25	Blk. 35.5 38.0 26.5 38.0 37.0 38.0 38.0 38.0 38.0 37.0 38.0 37.0 38.0	GaL 15.75 17.75 6.25 15.75 16.75 16.25 17.75 17.75 17.75 16.75 17.75	Blk. 36.5 39.4 27.0 38.5 37.5 38.5 38.5 38.5 38.5 38.5 38.5 38.5 38	Gal. 16.25 18.25 6.75 16.75 17.25 16.75 18.25 18.25 18.25 18.25 18.25	Blk. 37.0 39.0 27.5 39.0 39.0 39.0 39.0 39.0 39.0 39.0 39.0	Gal. 17.25 19.25 17.25 17.25 18.25 17.25 19.25 19.25 17.25 19.25 19.25	Bik. 37.5 39.5 28.0 39.5 38.5 39.5 39.5 39.5 39.5 39.5 39.5 39.5	Gal. 17.75 19.75 8.25 17.75 18.75 17.75 19.75 19.75 19.75 19.75 19.75	Bik. 38.0 40.0 28.5 40.0 39.0 40.0 40.0 40.0 40.0 40.0 40.0	Gal. 18.25 20.25 8.75 18.75 19.25 18.25 20.25 20.25 18.75 20.25 19.25 20.25	24.0	3.75	27.0		29.0 29.0 29.0 29.0	Gal. 7.75
E&TRA STRONG PLAIN ENDS Sparrows Pt. B3. Youngstown R3. Fontans K1 Pittaburgh J3. Alton III. L1 Sharon M3. Pittaburgh N1 Wheeling W5. Wheatland W4 Toungstown Y1 Indiana Harber Y1 Lorain N2.	30.25 32.25 20.75 32.25 32.25 32.25 32.25 32.25 32.25 32.25 31.25 32.25	9.5 11.5 10.0 8.5 10.5 11.5 11.5 10.0 11.5 10.5	34.25 36.25 24.75 36.25 33.25 36.25 36.25 36.25 36.25 36.25 36.25 36.25	13.5 15.5 14.0 12.5 14.5 15.5 14.0 15.5 14.5 15.5	36.25 38.25 26.75 38.25 38.25 38.25 38.25 38.25 38.25 37.75 37.25 38.25	17.0 19.0 16.0 16.0 17.5 19.0 19.0 17.5 19.0	36.75 38.75 27.25 38.75 38.75 38.75 38.75 38.75 38.75 38.75 38.75	17.5 19.5 17.0 16.5 18.0 19.5 19.5 17.0 19.5 18.5 19.5	37.25 39.25 27.75 39.25 39.25 39.25 39.25 39.25 39.25 39.25 39.25 39.25	18.5 20.5 17.5 17.5 18.5 20.5 20.5 17.5 20.5 19.5 20.5	37.75 39.75 28.25 39.75 36.75 39.75 39.75 39.75 39.75 39.75 39.75 39.75	19.0 21.0 18.0 18.0 19.0 21.0 21.0 21.0 21.0 21.0 21.0 21.0	38.25 40.25 28.75 40.25 37.25 40.25 40.25 40.25 40.25 40.25 40.25 40.25	19.5 21.5 19.0 18.5 19.5 21.5 21.5 19.0 22.5 20.5 21.5	23.75 23.75 23.75 23.75	2.0 4.5 4.5	27.75 27.75 27.75 27.75	6.5 8.5 8.5	31.25 31.25 31.25 31.25	12.0

Galvanized discounts based on zinc, at 17¢ per lb, East St. Leuis. Fer each 1¢ change in zinc, discounts vary as follows: ½ in., ¾ in., and 1 in., 1 pt.; 1¼ in., 1½ in., 2 in., ¾ pt.; 2½ in., 3 in., ½ pt. Calculate discounts on even cents per lb of zinc, i.e., if zinc is 16.51¢ to 17.50¢ per lb, use 17¢. Jones & Laughlin discounts apply only when zinc price changes 1¢. Threads only buttweld and seamless, 1 pt. higher discount. Plain ends, buttweld and seamless, 3 in. and under 3½ pts. higher discount. Buttweld jobbers' discount, 5 pct. St. Louis zinc price new 13.5¢.

Furnace, beehive (f.o.b. oven) Net-To Connellsville, Pa
Foundry, beehive (f.o.b. oven) Connellaville, Pa. \$17.50 to \$18.6 Foundry, oven coke Buffalo, del'd \$26.1 Chicago, f.o.b. 224. Detroit, f.o.b. 244. New England, del'd 24 Seaboard, N. J., f.o.b. 22 Philadelphia, f.o.b. 22 Swedeland, Pa., f.o.b. 22
Foundry, beehive (f.o.b. oven) Connellaville, Pa. \$17.50 to \$18.6 Foundry, oven coke Buffalo, del'd \$26.1 Chicago, f.o.b. 224. Detroit, f.o.b. 244. New England, del'd 24 Seaboard, N. J., f.o.b. 22 Philadelphia, f.o.b. 22 Swedeland, Pa., f.o.b. 22 Swedeland, Pa., f.o.b. 22
Connellaville, Pa. \$17.50 to \$18.65 Foundry, oven coke Buffalo, del'd \$26.1 Chicago, f.o.b. 23. Detroit, f.o.b. 24.1 New England, del'd 24. Seaboard, N. J., f.o.b. 23. Philadelphia, f.o.b. 22. Swedeland, Pa., f.o.b. 22.
Foundry, oven coke Buffalo, del'd \$26. Chicago, f.o.b. \$23. Detroit, f.o.b. 24. New England, del'd 24 Seaboard, N. J., f.o.b. \$2. Philadelphia, f.o.b. \$2. Swedeland, Pa., f.o.b. 22.
Chicago, f.o.b. 22.1 Detroit, f.o.b. 24.1 New England, del'd 24.1 Seaboard, N. J., f.o.b. 22.2 Philadelphia, f.o.b. 22.2 Swedeland, Pa., f.o.b. 22.2
Chicago, f.o.b. 22.1 Detroit, f.o.b. 24.1 New England, del'd 24.1 Seaboard, N. J., f.o.b. 22.2 Philadelphia, f.o.b. 22.2 Swedeland, Pa., f.o.b. 22.2
Detroit, 1.0.0. 24 New England, dei'd 24 Seaboard, N. J., f.o.b. 22 Philadelphia, f.o.b. 22 Swedeland, Pa., f.o.b. 22
Seaboard, N. J., f.o.b. 22 Shiladelphia, f.o.b. 22 Swedeland, Pa., f.o.b. 22
Seaboard, N. J., f.o.b. 23. Philadelphia, f.o.b. 22. Swedeland, Pa., f.o.b. 22.
Philadelphia, f.o.b
Swedeland, Pa., f.o.b 22.
Painesville, Ohio, f.o.b 24.
Erie, Pa., f.o.b
Cleveland, del'd
Cincinnati, del'd
St. Paul, f.o.b
St. Louis
Birmingham, del'd 21.
Neville Island 23.

ELECTRICAL SHEETS

22 Ga. H-R cut length F.o.b. Mill Cents Per Lb.	Armature	Elec.	Moter	Dyname	Transf. 72	Transf. 65	Transf. 58
Beech Bettem W5.		7.85	9.10	9.90	10.45	11.00	11.70
Brackenridge 43.	7.35	7.85	9.10	9.90	10.45	11.00	11.70
Granite City G2		8.55	9.80				
Ind. Harber 13	7.35	7.85	9.10				
Mansfield E2	7.35	7.85	9.10	9.90			
Niles, O. N3 Vandergrift UI	7.35	7.85					
Vandergrift UI	7.35	7.85	9.10	9.98	10.45	11.00	11.70
Warren, O. R3 Zapesville A7	7.35	7.85	9.10				
Zapesville A7	7.35	7.85	9.10	9.90	10.45	11.00	11.70

PIG IRON

Dellaranea	 f = h	subject to	awitching	charges

Producing Point	Basie	Foundry	Malleable	Bessemer	Lew Phes.	Bl. Furnace Silvery	Lew Phes. Charceal
Bethlehem B3	56.50	57.00	57.50	58.00			
Birmingham R3	50.88	51.38					
Birmingham W9	50.88	51.38					*****
Birmingham S5	50.88	51.38					*****
Buffalo R3	54.50	55.00	55.50			11111	*****
Buffale H1	54,50	55.00	55,50			66.75	*****
Buffale W6	54.50	55.00	\$5.50				
Chicago 14	54.50	55.00	55.00	55.50		****	****
Cleveland A5	54.50	55, 00	55.00		59.50	****	* * * * *
	54.50	55.00		55,50	39.30	*****	*****
Daingerfield, Tex. L3	50.50		55.00	10111	*****	*****	*****
Delete 14		51.00	51.00	44144			****
Duluth 14	54.50	55.00	55.00	55.50	*****	*****	****
	54.50	55.00	55.00	55.50	*****	****	
Everett, Mass M6		59.25	59.75			****	*****
Fentans KI	60.50	61.00				*****	
Geneva, Utah C7	54.50	55.00					*****
Granite City, III. K3	56.40	56.90	57.40				*****
Hubbard, Ohio Y/	54,50	55.00	55,00				
Irenten, Utah C7	54.50						
Jackson, Ohio JI GI						65.50	
Lyle, Tenn. 73.			****			-	68,50
Minneque C6	54.50	57.50	57.50				
Menessen P6	54.50				****		
Neville Island P4	54.50	55.00	55 88	55.50		*****	****
Pittsburgh UI	54.50	33.99	55.00		*****	****	
Sharpaville S3	54.50	44144	22122	55.50		*****	****
		55.00	55.00	55.50	11711		****
	56.50	57.00	57.58	58.00	62.50		
Swedeland A2	58.50	50.00	59.50	60.00		****	****
Toledo /4	54.50	55.00	55.00	55.50			****
Troy, N. Y. R3	56.50	57.00	57.50	*****	62.50		*****
Teungstewn Y1	54.50	55.00	55.00	55.50			****
N. Tenawanda, N. T. TI		55.00	55.50			*****	

DIFFERENTIALS: Add 50¢ per tan for each 0.25 pct silicon over base, (1.75 to 2.25 pct, except low phea., 1.75 to 2.00 pct), 50¢ per tan for each 0.50 pct manyaness over 1 pct, 52 per tan for 0.5 to 0.75 pct nickel, \$1 for each dditional 0.25 pct nickel. Subtract 38¢ per tan for phosphorus, centent 0.70 pct and over. Silvery Iron: Add \$1.50 per tan net for each 0.50 pct allican over hase (6.01 to 6.50 pct) up to 17 pct. \$1 per tan for 0.75 pct or more phosphorus, manyaness as above. Bessement forms of the comparable silvery iron.

CAST IRON WATER PIPE

6 to 24-in., del'd Chicago \$105.30 to \$108.80 6 to 24-in., del'd N.Y... 108.50 to 109.50 6 to 24-in., Birmingham 91.50 to 96.00 6-in. and larger, f.o.b. care, San Francisco, Los Angeles, for all rall shipments; rail and water shipments less \$123.00 to \$130.00 Class "A" and gas pipe, \$5 extra; 4-in pipe is \$5 a ton above 6-in.

BOILER TUBES

You Rug Con pro life low


nea

pro

\$ per 100 ft. carlead lets, cut 10 to 24 ft. F.e.b. Mill	Size		Seamless		Elec. Weld	
	OD- In.	B.W. Ga.	H.R.	C.D.	H.R.	C.D.
Babcock & Wilcox	2	13			23.19	
	21/2	12	32.17	37.83	31.19	36.67
	3	12			34.69	
	31/2	11			43.36	
	4	10	55.52	65.31	53.83	63.3
National Tube	2	13	22.81	27.94	22.23	
	21/2	12	31.28	38.31	30.51	
	3	12	35.87	43.93	34.98	
	31/2	11	42.56	52.12		
	4	10	54.02	66.16		
Pittsburgh Steel	2	13		28.58		
	21/2	12	32.16	39.19		
	3	12	36.87	44.93		
	31/2	11	43.76	53.32		
	4	10	55.54	67.68		

C-R SPRING STEEL

	CARBON CONTENT						
Cents Per Lb. F.e.b. Mill	0.26-	0.41- 0.60	0.61- 0.80	0.81- 1.05	1.06-		
Bridgepert, Conn. 57							
Carnegie, Pa. S9		7.65	8.25	10.20	12.5		
Detroit D1	6.45	7.50	8810	10.20	16.00		
New Castle, Pa. B4.		7.65	8.25	10.20			
New Haven, Conn. DI		7.60	8.20				
Sharen Pa. Sl	5.80	7.65	8.25	10.20	12.50		
Trenten N. J. R4		7.95	8.55	10.50	12.80		
Weirton W. Va. W3.	5.80	7.65	8.25	18.20	12.5		
Worcester, Mass. A5	5.40	7.60	8.55	10.50	12.8		
Youngstown C5		7.65	8.25	10.20	12.5		



*CONTINENTAL Fence Features
For Long-Lasting Property Protection

- Fence fabric is hot-dip galvanized—after weaving
- Heavy, modern post caps and barb-wire arms
- Snug-fitting inside-outside couplings

7.75

8.75

2.0

3 63.32

1.06-

12.50 12.50

12.50 12.50 12.50 12.50 12.50

1952

- Sturdy, closely spaced line posts in two styles
- Improved, pivot-type hinges—welded gates
- Extra ties hold fence fabric securely to posts and rails

You get more dollar value fence protection with Continental Chain Link fence. Rugged fabric is galvanized after weaving . . . heavier line posts and rails keep Continental fence in perfect alignment. Easier-operating gates swing on improved pivot hinges, and you get more ties to secure the fabric for longer fence life. Continental fence engineers plan and erect your fence for most effective, low-cost property protection. Write Continental at Kokomo, Ind., or contact nearest sales office.

Planned and Erected to Fit Your Property



Continental's experienced fence engineers help you plan and lay out fence, tailored to fit your property.




Line posts are solidly set in concrete—fabric carefully stretched and secured for permanence.


* Trade Mark Reg. U.S. Pat. Off.




TERMINAL POSTS AND POST TOPS



NEW TOP RAIL COUPLING



TUBULAR OR H-SECTION LINE POSTS



SMOOTH-OPERATING GATES



MORE POST AND TOP RAIL TIES



CONTINENTAL STEEL CORPORATION

GENERAL OFFICES . KCKOMO. INDIANA

ODUCERS OF Manufacturer's Wire in many sizes, opes, tempers and finishes, including Galvanized,

KOKOTE, Flame-Sealed, Coppered, Tinned, Annealed, Liquor Finished, Bright, Lead Coated, and special wire.

ALSO, Coated and Uncoated Steel Sheets, Nails, Continental Chain Link Fence, and other products.

RAILS, TRACK SUPPLIES

			-	Ling	-		Joint			Irack		Screen	2000	-		lie Plate		Teach	Transfer J	
3.	7	75	4	. 2	5	4.	9;	25			١.			l.						
3.	7	75	4	2	5						1.			1.						
			4	.2	5				6	65				4		7	75			
3.	77	75	4	. 2	5						1.			4		7	75			
3.	7	75				4.	92	25	6	65				4		7	75			
			4	2	5						1.			1.						
			4	. 2	5	4.	92	25			1.			1.						
					.						1.			١,						
3.	77	75	4.	. 2	5	6.	92	25			1.			4		7	75			
					.1				6	65		,		١.						
3.	77	15	4.	.7	5	4.	92	25	6.	65				4		7	75	9	. 8	
					-															
					.1						١.	,		١.						
					.1							,								
					.				6.	65		,		l.						
					-									14		9;	25			
									7.	15				4		97	25			
3.	77	5			. 1	1.	92	25						4		7	75			
		. 1							6.	65										
					1				6.	65										
	3. 3. 3. 3.	3.77	3.775 3.775 3.775 3.775 3.775 3.775	3.775 4 3.775 4 3.775 4 4.4 3.775 4 3.775 4	3, 775 4, 2 3, 775 4, 7	3. 775 4.25 3. 775 4.25 3. 775 4.25 3. 775 4.25 4.25 3. 775 4.25 3. 775 4.25	3.775 4.25 3.775 4.25 3.775 4.25 3.775 4.25 4.25 4.25 4. 3.775 4.25 4.	3.775 4.25 3.775 4.25 3.775 4.25 4.25 4.25 4.91 3.775 4.25 4.91 3.775 4.75 4.91	3.775 4.25 3.775 4.25 3.775 4.25 4.25 4.925 4.25 4.925 3.775 4.25 4.925 3.775 4.75 4.925	6. 3.775 4.25 6. 3.775 4.25 4.25 6. 3.775 4.25 4.925 6. 4.25 4.925 3.775 4.25 4.925 6. 3.775 4.75 4.925 6. 6. 3.775 4.75 4.925 6.	3.775 4.25 6.65 3.775 4.25 6.65 3.775 4.25 4.925 6.65 4.25 4.925 3.775 4.25 4.925 6.65 3.775 4.75 4.925 6.65 3.775 4.75 4.925 6.65		3.775 4.25 6.65 3.775 4.25 4.925 6.65 3.775 4.25 4.925 6.65 3.775 4.25 4.925 6.65 3.775 4.75 4.925 6.65 6	6.65 3.775 4.25 6.65 3.775 4.25 4.925 6.65 4.25 4.925 6.65 4.25 4.925 6.65 3.775 4.25 4.925 6.65 3.775 4.75 4.925 6.65 6.65 4.95 4.95 6.65	6.65 3.775 4.25 3.775 4.25 3.775 4.25 4.925 6.65 4.25 4.25 4.25 4.25 4.25 4.25 4.25 4.2			6.65 3.775 4.25 4.25 6.65 4.775 3.775 4.25 4.25 4.25 4.25 4.25 4.25 4.25 4.25		4.75

TOOL STEEL

F.o.b. mill Add 4.7 pct

							Base
W	Cr	V	Mo		Co		er lb
18	4	1	-		-	\$1	.505
18	4	1			5	1	2.13
18	4	2	-		-	- 1	1.65
1.5	4	1.5	8		_	8	1.0€
6	4	2	6		-	- 9	6.5€
High-	carbon	chromiu	m			6	3.5€
Oil ha	rdened	mangan	ese .				35€
Specia	l carbon	n				3	2.5€
	carbon						27€
	ar carbo						23€
	rehouse						Mis-
sissipp	i are 3	.5¢ per	lb. h	igh	ier.	Wes	t of
	sippi, 5.						

CLAD STEEL

Add 4.7 pct

Stainless-carbon	Plate	Sheet
No. 304, 20 pct.	920.5	
Coatesville, Pa. L4	e20.5	
Washington, Pa. J2	# 29 DO	
Claymont, Del. C4	20.00	•27.50
Conshohocken, Pa. A2	830.77	
New Castle, Ind. 12	29.11	*26,24
Nickel-carbon	225	
10 pct Coatesville, Pa. L4	32.5	
Inconel-carbon		
10 pct Coatesville, Pa. L4	40.5	
Monel-carbon		
10 pct Coatesville, Pa. L4	33.5	
No. 302 Stainless copper stainless, Carnegie,		
Pa. A4		77.00
Aluminized steel sheets, hot dip, Butler, Pa.		
A7		7.75
* Includes annealing and pickling, or a	andblast	ing.

ELECTRODES .

Cents per lb, f.o.b., plant threaded

electrodes	40101	nippies,	unouzea
Dian. in 10.		Length in in.	Cents Per 1b.
	GRA	PHITE	
17, 18, 20		72	17.85
8 to 16	48,		17.85
7	48,	60	19.57
6		60	20.95
4 5	4.0	-	21.50
3	4.0		22.61
9.14	24.	30	23.15
8 to 16 7 6 4, 5 3 214	24.	30	25.36
		RBON	
60	100.	110	8.03
35	65.	110	8.03
10	65	84, 110	8.03
2.4	72	to 104	8.03
20	84.		8.03
17	60,	72	8.03
20 17 14	60.		8.57
10, 12	60		8.84
8	60		9.10

FLUORSPAR

Washed	1 8	re	13	VE	1.		1		0.	b		3	R	0	si	C	18	11	re,			11	1
Price, net	to	n;		E	iff	e	ct	i	V	0	0	a	ŀ	'n	1	36	110	it	en	t			,
70% or n	TOP	θ	0	0	0 0	0		0	0 1	0 -	0 0	0	0	0	0 1	,		0	2	3	3	U	1
80% or le	SB .		×		b. 18	*		8		8		8.	2							4	v	.0	1

BOLTS, NUTS, RIVETS, SCREWS

Consumer Prices

(Base, discount, f.o.b. mill, Pittsburgh, Cleveland, Birmingham or Chicago)

Nuts, Hot Pressed, Cold Punched-Sq.

	Pct O; Less Keg.	J List	Less Keg.	K
	Re	E.	H	vy.
½ in. & smaller.		28 1/2	15	283
9/16 in. & % in. % in. % in.	12	25	6 1/2	21
inclusive	9	9.9	1	1636
1% in. & larger.		22	1	16 1/2
			1	

Nuts, Hot Pressed-Hexagon

1/2 in.	& smaller.	26	37	22	34
9/16 in	. & % in to 1½ in.	16 1/2	29 1/2	6 3/2	21
	sive	12	25	2	173
1 % in.	& larger.	8 1/8	23	2	174

Nuts, Cold Punched-Hexagon

½ in. & smaller.	26	37	22	34
9/16 in. & 5% in.		35	17%	30 3
34 in. to 1 1/2 in.				
inclusive	19 1/2	31 1/2	12	26
1% in. & larger.	8 1/2	23	2	17%

Nuts, Semi-Finished—Hexagon

	R	eg.	H	vy.
½ in. & smaller.	3.5	45	281/2	29 14
9/16 in. & 5% in. % in. to 1 ½ in.	23	35	17 1/2	30 1/
inclusive	24	36	15	284
15 in. & larger.	13	26	8 1/2	23
7/16 in. & small-	L	ight		
	35	45		
14 in. thru % in. % in. to 1 1/2 in.				
inclusive	26	37		

Stove Bolts Pet Off List

Packaged, steel, plain finished 48—10
Packaged, plain finish 31—10
Bulk, plain finish 62 62°
*Discounts apply to bulk shipments in not less than 15,000 pieces of a size and kind where length is 3-in. and shorter; 5000 pieces for lengths longer than 3-in.
For lesser quantities, packaged price applies.

o Zinc, Parkerized, cadmium or nickel plated finishes add 6¢ per ib net. For black off finish, add 2¢ per ib net.

Riv	vet	5								B	0	18	36	p	e	9.	100	16	
1,6	In.	80	larger						0	0					0		\$7.	86	

Cap and Set Screws

∠481
54
48
46
41
35
16
34
5.3

Machine and Carriage Bolts

	Pet O	7 List
	Less	C.
1/2 in & smaller x 6 in & shorter	15	281/2
shorter	181/2	301/2
shorter	171/2 14	29 1/2 27 1/2
shorter	23	35
6 in.	21	33
Plow bolts	34	

REFRACTORIES

Fire Clay Brick	Carloads, per 1000
First quality, Ill., Ky., (except Salina, l'a.,	
No. 1 Ohlo	
No. 2 Ohlo	on, bulk (ex-
cept Salina, Pa., ade	d \$1.50) 13.75

Silica Brick

16. 17. 1 . 15. Th. 1 . 11.	
Mt. Union, Pa., Ensley, Ala	194.60
Childs, Pa	99.00
Hays, Pa	100.10
Chicago District	104.50
Western Utah and Calif	111 10
Western Utan and Cam.	111.10
Super Duty, Hays, Pa., Athens,	
Tex., Chicago	
Silica cement, net ton, bulk, East-	
ern (except Hays, Pa.)	
Silica cement, net ton, bulk, Hays,	
Pa	18.70
	10.40
Silica cement, net ton, bulk, Ensley,	
Ala	17.60
silica cement, net ton, bulk, Chic-	
cago District	17.60
Bilica cement, net ton, bulk, Utah	
and Calif	24.70
and Cam	24.10

Chrome Brick Per Net Ton Standard chemically bonded Balt., Chester\$82.00

Magnesite Brick

Standard,	Baltimore			. \$	104.00
Chemically	borded, Ba				

Grain Magnesite St. %-in. grains

Domes	tic.	-	1.1	U.	b.	H	38	a	lt	11	m	0	re	9										
in l																					6	2	7	Ę
Homes	tic.		f.	0.	.b		C	1	16	30	V8	al	a	h		V	7	a	3	h.				
in b	ulk																				3	16	3	e
in s	ack	55																			4	1	8	0

Dead Burned Dolomite

7.o.b. producing	points in Pennsyl-
vanta, West	Virginia and Ohio
per net ton.	bulk Midwest, add
10¢: Missouri	Valley, add 20¢ \$13.7

LAKE SUPERIOR ORES

51.50% Fe; natural content, delivered lower Lake ports. Prices effective July 26, 1952

, -		-					1	G	ro	as Ton
Old range, bessemer										
Old range, nonbesseme										
Mesabi, bessemer										
Mesabl, nonbessemer										9.05
High phosphorus										
After adjustments										
will be increased or d	00	27/	3.0	9.62	0	4	0.4		+1	0 00 00

Thei capa minu

Rey nace MR.

"We

G-E

neer


in a qual impo

SEVE the-c

will be increased or decreased as the case may be for increases or decreases after Dec. 1, 1950, in Lake vessel rates, upper Lake rail freights, dock handling charges and taxes thereon.

METAL POWDERS

Per pound, f.o.b. shipping point, in ton lots, for minus 100 mesh.
Swedish sponge iron c.l.f. New York, ocean bags 10.96
Canadian sponge iron, del'd. in East
Domestic sponge iron, 98+% Fe, carload lots 15.5¢ to 17.0¢
Electrolytic iron, annealed, 99.5+% Fe
Electrolytic iron, unannea ed, minus 325 mesh, 99+% Fe 60.0c
Hydrogen reduced Iron, minus 300 mesh, 98+% Fe. 63.0¢ to 80.0¢ Carbonyl Iron, size 5 to 10
Carbonyl fron, size b to 10 micron, 98%, 99.8 + % Fe. 83.0 ¢ to \$1.48 Aluminum Brass, 10 ton lots 30.00 ¢ to 33.25 ¢ Copper, electrolytic.10.75 ¢ plus metal value Copper, reduced 10.00 ¢ plus metal value Cadmium, 100-199 lb. 95 ¢ r us metal value Chromium, electrolytic, 99% min., and quantity, del'd \$3.50 Lead 7.5 ¢ to 12.0 ¢ plus metal value Manganese 57.0 ¢ Molybdenum, 99% \$2.75 Nickel, unannealed 88.0 ¢ Nickel, unannealed 92.0 c Nickel, spherical, unannealed 92.0 c Silicon 38.5 c Solder powder 7.0 ¢ to 9.0 ¢ plus met. value Stainless steel, 302 83.00 c Stainless steel, 316 \$1.10 Tin 14.00 ¢ plus metal value Tungsten, 99% (65 mesh) \$6.00



ELEVATOR FURNACE NEARS 10 YEARS SERVICE OF CONSISTENT, ACCURATE TREATMENT OF HIGH-QUALITY ALLOY SHEET.

Reynolds Metals Co. Says "G-E Furnaces Meet Heavy Schedule, Need Few Repairs"

Their Listerhill, Alabama, plant is now operating at full capacity to meet the ever-increasing demand for aluminum. And to meet this high production schedule, Reynolds depends on many types of G-E electric furnaces for annealing, aging and solution heat-treating.

.50

.60

00

MR. M. A. J. PHILLIPS, Reynolds Vice-president, says, "We are very pleased with the dependable service our G-E furnaces give with little downtime." One of his engineers adds, "Uniform heat distribution is very important in aluminum heat-treating, and the consistent high-quality work our G-E furnaces turn out proves the importance of properly locating heating elements and

SEVFN DAYS A WEEK this roller-hearth furnace works aroundthe-clock to heat and spray-quench bars and rods at 950 F.

designing the circulation equipment to fit the loads."

ALUMINUM FABRICATORS, as well as prime producers like Reynolds, can profit by using G-E furnaces for their heat-treating operations.


TAKE ADVANTAGE of G-E experience in heat-treating of aluminum. Call the nearest G-E sales office for the services and recommendations of their experienced Industrial Heating Specialist on your heat-treating problem. General Electric Company, Schenectady, N.Y. 12682

GENERAL 8



ELECTRIC

100 TONS PER CHARGE are annealed in this metal-lined truck furnace. Highest-quality stock results from uniform heating.



What's New in New Jersey



A DDED TO THE WEALTH of research facilities which are concentrated in New Jersey is the newly dedicated James Forrestal Research Center at Princeton University.

Today, at this 800-acre center, more than \$1,500,000 worth of research tasks are being investigated. Subjects of current experimentation include fluid mechanics, combustion, chemical reactions, thermo-dynamics, applied mathematics, nuclear fission and aeronautical and jet propulsion engineering.

More than 10 per cent of the nation's research operates in New Jersey, the Crossroads of the East. More than 400 firms are active in the capitol of scientific endeavor, spending more than \$150,000,000 annually in laboratory and development work.

Industrialists appreciate the advantages which these research facilities give to manufacturers in New Jersey. We can provide you with more information about the Crossroads of the East.



Want to know more about New Jersey? Write Box C, Public Service Electric and Gas Company, 70 Park Place, Newark, N. J. for your capy of the booklet, "An Industrialist's View of the Crossroads of the East."



How To Reach Them

The thousands of purchasing executives, production chiefs, and engineers, all potential BUYERS of your products are among the readers of Iron Age. Your advertisement here can pave the way for your salesmen throughout the metalworking industry.

For information write:

The Iron Age 100 E. 42nd St., NEW YORK 17, N. Y.

-Ferroalloy Prices

Formalisama
Ferrochreme Contract prices, cents per pound, contained Cr, lump size, bulk in carloads delivered. (65-72% Cr, 2% max. Sl.) 0.06% C. 30.50 0.20% C. 29.50 0.10% C. 30.00 0.50% C. 29.55 0.15% C. 29.75 1.00% C. 39.00 2.00% C. 28.76 28.76 55-69% Cr, 4-9% C. 22.00 22.00 62-66% Cr, 4-6% C, 6-9% Sl. 22.00
S M Forrachromo
Contract price, cents per pound, chromium contained, lump size, delivered. High carbon type: 60-65% Cr, 4-6% Si, 4-6% Mn, 4-6% C. Carloads 21.60 Ton lots 23.75
Carloads 21.60 Ton lots 23.76 Less ton lots 25.25 Low carbon type: 62-66% Cr, 4-6% St, 4-6% Mn, 1.26% max. C Carloads 27.75 Ton lots 30.05 30.05 30.05
Carloads 27.76 Ton lots 30.08 Less ton lots 31.88
High-Nitrogen Ferrochrome Low-carbon type: 67-72% Cr, 0.75% N Add 5¢ per lb to regular low carbon fer- rochrome price schedule. Add 5¢ for each additional 0.25% N.
Chromium Metal
Contract prices, per lb chromium contained, packed, delivered, ton lots, 97% min. Cr. 1% max. Fe. 0.10% max. C \$1.14 0.50% max. C 1.10 9 to 11% C 1.08
(Cr 34-41%, Sl 42-49%, C 0.05% max.) Contract price, carloads, f.o.b. Nlagara Falls, freight allowed: lump 4-ln. x down, bulk 2-ln. x down, 21.75¢ per lb of con- tained Cr plus 12.40¢ per lb of contained
SI. Bulk 1-in. x down, 21.90¢ per lb contained Cr plus 12.60¢ per lb contained SI
Contract price per lb of alloy, dum
delivered. 30-33% Ca, 60-65% Si, 3.00% max. Fe Carloads. 19.00 Ton lots. 22.10 Less ton lots. 23.60
Calcium-Manganese—Silicon
Contract prices, cents per lb of alloy lump, delivered. 16-20% Ca, 14-18% Mn, 53-59% St.
Carloads 20.00 Ton lots 22.36 Less ton lots 23.30
Contract price, cents per lb of alloy
delivered. Alloy 4: 45-49% Cr, 4-6% Mn, 18-21%
Alloy 4: 45-49% Cr, 4-6% Mn, 18-21% SI, 1.25-1.75% Zr, 3.00-4.5% C. Alloy 5: 50.56% Cr, 4-6% Mn, 13.50 16.90% SI, 0.75 to 1.25% Zr, 3.50-5.00% C. Ton lots
Contract price cents per pound of allow
Contract price, cents per pound of alloy delivered, 60 65% SI, 5-7% Mn, 5-7% Zr. 20% Fe, ½ In. x 12 mesh. Ton lots
V Foundry Alloy Cents per pound of alloy, f.o.b. Suspen- sion Bridge, N. Y., freight allowed, max St. Louis. V-5: 38-42% Cr, 17-19% Sl.
8-11% Mn. Ton lots
Graphidox No. 4 Cents per pound of alloy, f.o.b. Suspension Bridge, N. Y., freight allowed, max. St. Louis. Si 48 to 52%, Ti 9 to 11%, Ca 5 to 7%.
Ton lots to carload packed 19.05 Less ton lots 20.58
Ferromanganese 78-82% Mn, maximum contract base price, gross ton, lump size. F.o.b. Niagara Falls, Alloy, W. Va., Ashtabua, O
Briquets—Cents per pound of briquet delivered, 66% contained Mn. Carload, bulk



THE Cleveland-Cliff LIRON COMPANY
UNION COMMERCE BUILDING . CLEVELAND 14, OHIO

October 16, 1952

rloads

29.59 29.25 29.00 28.76 22.00 22.50

chro. d. 4-6%

21.60 23.75 25.25 % St.

27.75 30.05 31.85

% N fereach

\$1.14 1.10 1.08

gara own, contines

d Si

umi

Fe 9.00 2.10 3.60

illoy

lloy

21%

.50 6 C. 9.75 2.00

loy Zr

en SI

18

Spiegeleisen

Contract	prices	gross ton;	lump, f.o.b
		16-19% Mn	19-21% Mn
Par I		3% max. Si	3% max. Si
Palmerton,		\$84.00	\$85.00
Pah. or Ch	Cago	84.00	85.00

Manganese Metal

Contra pound of	ct	ba	sis	i,	2	ir	i.	re	d	de	01	N	n,		C	e	nt	8	per
96% III Si, 2.5%	in.	3	In.	. (0.						.2		C,	E.	1	0	%	n	ax.
Carload, Ton lots	pa	ck	ed															3	6.95

Electrolytic Manganese

F.o.b.	Kno:	K V	file	e,	7	e	ni	n.,	n	r	e	g	rh	it	all	lowed
Carloads																30.00
Ton lots Less ton	lots										3	4.	0	0	to	32.00

Low-Carbon Ferromanganese

ents per pound Mn con- del'd Mn 85-90%.
Carloads Ton Less
9/0
28.45 30.30 31.50
27.95 29.80 31.00
27.45 29.30 30.50
26.95 28.80 30.00
26.45 28.30 29.50
85% Mn.
23.45 25.30 26.50

Medium Carbon Ferromanagnese

Mn	80% to 85	%. C 1.25 to	1.50. Contract
price,	carloads,	lump, bulk	delivered, per
lb of	contained	Mn	21.35€

Silicomanganese

Cont	ract	t	as	18	١,	11	uı	np)	8	120	٥.		CE	en	ta	T	er	
pound	of	me	ta	1.		de	11	ve	Ге	d		6	5	-6	80	1/0	N	In.	
18-20%	SI.	1.1	5 %		m	an		C		F	or		20	%	m	18	X.	C.	
deduct																			
Carload	d bi	alk														1	11.	40	į
Ton lo																			

Briquet, contract basis carlots.	bulk	
delivered, per lb of briquet .		12.65
Ton lots packed		14 25

Silvery Iron (electric furnace)

Si 14.01 to 14.50 pct, f.o.b. Keokuk, lowa, or Wenatchee, Wash., \$95.00 gross ton, freight allowed to normal trade area. Si 15.01 to 15.50 pct, f.o.b. Niagara Falls, N. Y., \$93.00. Add \$1.00 per ton for each additional 0.50% Si up to and including 17%. Add \$1.00 for each 0.50% Mn over 1%.

Silicon Metal

taine	d S	act i, lu												
pack	S1.				*		×	×	,		6		1	8.00
970%	SI	10%	Fe										1	8 50

Silicon Briquets

briquet bulk. delivered, 40% Si. 2 lb Si briquets. Carloads, bulk	Contra	ct p	rie	ce	١.	0	e	n	t	g	1	04	ei	r	I	00	01	u	br	(of
Carloads, bulk 6.95	briquet	bulk.																			
		, bulk				 					6	*	,				*		6	.9	5

Electric Ferrosilicon

Contr	act r	rice	cents	per	nour	nd	con-
tained S							
35% S1		20.00	71	5% 5	1	1	4.30
50% SI		12.40	81	5% 8	1	1	5.65
99-95%	S1					1	7.00

Calcium Metal

Eastern pound of r				cents	per
pound of i	neum,	Cast	Turnings	Dieti	hall
Ton lots			\$2.95	\$3.7	
Less ton le		2.40	3.20	4.5	
TARRE FOR I	uus	8.10	0.00	7.6	

Ferrovanadium

25-55% cont				ad.
Openhearth			\$	3.00-\$3.16
Crucible High speed	steel	(Pri	mos)	3.10- 3.20 3.20- 3.20



O. K. Pete! From here on in shave at home. I know how razor sharp Clarite Tool Bits are!


COLUMBIA TOOL STEEL COMPANY . CHICAGO HEIGHTS, ILL.

Producers of fine tool steels—High Speed Steels Die Steels—Hot Work and Shock Resisting Steels Carbon Tool Steels.



Alaifer, 20% At. 40% St. 40% Fe.	
Alsifer, 20% Al. 40% SI, 40% Fe, contract basis, f.o.b. Suspen- sion Bridge, N. Y.	
Carloads	9.90
Ton lots Calcium molybdate, 46.3-46.6% f.o.b. Langeloth, Pa., per pound	11.10
f.o.b. Langeloth, Pa., per pound	\$1.15
contained Mo	****
ner pound contained Up.	
Ton lots	\$4.90 4.93
Ferro-Tantalum-Columbium, 20%	
basis, delivered, ton lots, 2 in. x D, per lb of contained Cb plus	
It	\$3.75
Ferromolybdenum, 55-75%, f.o.b. Langeloth, Pa., per pound con-	
tained Mo Ferrophosphorus, electrolytic, 23-26%, car lots, f.o.b. Siglo, Mt. Pleasant, Tenn., \$3 unitage, per	\$1.32
26%, car lots, f.o.b. Siglo, Mt.	
gross ton	\$65.00
10 tons to less carload Ferrotitanium, 40% regular	\$75.00
gross ton 10 tons to less carload	
ville, Pa., freight allowed, ton	** **
	\$1.35
Ferrotitanium, 25%, low carbon, 6.10% C max., f.o.b. Niagara Falls, N. Y., and Bridgeville,	
Pa., Ireight allowed, ton lots,	\$1.50
Less ton lots	1.55
per lb contained Ti Less ton lots	
N. Y., freight allowed, car- load per net ton	177.00
Ferrotungsten, standard, lump	
pound contained W5, ton lots,	\$ 5.00
Molybdic oxide, briquets or cans.	
Langeloth, Pa	\$1.14
bags, f.o.b. Washington, Pa., Langeloth, Pa.	\$1.13
bags, f.o.b. Washington, Pa., Langeloth, Pa	
Ohio, freight allowed, per pound	
Carload, bulk lump	14.50¢ 15.75¢ 16.25¢
Carload, bulk lump Ton lots, bulk lump Less ton lots, lump Vanadium Pentoxide, 86 - 89%	16.250
V _* O _* contract basis, per pound	
contained V ₂ O ₃	\$1.28
Zirconium, 35-40%, contract ba- sis, f.o.b. plant, freight al-	
sis, f.o.b. plant, freight allowed, per pound of alloy. Ton lots	21,000
Zirconium. 12-15%, contract ba- sis, lump, delivered, per lb of	
alloy. Carload, bulk	
Carload, bulk	1.000
Boron Agents	
Borosii, contract prices per lb of alloy del. f.o.b. Philo, Ohio, freight allowed. B, 3-4%. Si, 40-45%, per lb contained B.	
freight allowed, B, 3-4%, Si.	
40-45%, per lb contained B	\$5,25
Itoriam, f.o.b. Niegara Falls Ton lots, per pound Less ton lots, ner pound Corbortam, Ti, 15-21%, B, 1-2%, Sl, 2-4%, Al, 1-2%, C, 4.5-7.5%, f.o.b. Suspension Bridge, N. Y., freight allowed	45¢
Corbortam, Ti, 15-21%, B, 1-2%,	0.01
Sl, 2-4%, Al, 1-2%, C, 4.5-7.5%, f.o.b. Suspension Bridge, N, Y.,	
The least wed	10 00-
Ferroboron, 17,50% min. B, 1.50%	
max. S1, 0.50% max. A1, 0.50% max. C, 1 in. x D. Ton lots	\$1.20
F.o.b. Wash., Pa.; 100 lb up	95
Ferroboron, 17.50% min. B, 1.50% max. SI, 0.50% max. AI, 0.50% max. AI, 0.50% m.x. CI, 1.n. x D, Ton lots F.o.b, Wash, Pa.; 100 lb up 10 tc 14% B 14 to 19% B 19% min. B	1.20
WENTER I. O.D. DEIGERVILLE, FR.,	
freight allowed, 100 lb and over.	\$1.00
No. 1 No. 6 No. 79	68¢
Manganese - Roron 75 0000 Mn	
15-20% B. 5% max. Fe. 1.50% max. St. 3.00% max. C. 2 in. x	
D, del'd Ton lots Less ton lots	
Less ton lots	1.57

Nickel-Boron, 15-18% B, 1.00%
max. Al, 1.50% max. Sl, 0.50%
max. C, 3.00% max. Fe, balance
Ni, delivered
Less ton lots
Silcas, contract basis, delivered.
Ton lots



CHEMICAL PLANT HCL FUMES HAVE HAD NO EFFECT ON THIS PYROMETER'S ACCURACY; ABOVE, OPERATOR TAKES PYROMETER READING


"Extremely Corrosive Atmosphere— No Change in G-E Pyrometer Accuracy"

The calibrated accuracy of General Electric pyrometers is within ³4 of 1 per cent of full scale. And these instruments are built to take excessive punishment. A large eastern chemical manufacturer writes: "We use the HP-3 pyrometer to control the temperature of heat transfer oil. The surrounding atmosphere is extremely corrosive, due to hydrochloric acid fumes—yet there has been no sign of operational difficulty or failure."

CLOSE TEMPERATURE CONTROL. Any change in temperature, even as small as 0.1% full scale, starts immediate control action. All pyrometer models are available in a variety of temperature ranges in the 0-3000 F span.

HIGH FLUX DENSITY is provided by a 31₄-pound alnico magnet. It also allows large air gaps. The lightweight moving system effectively resists shocks and vibration.

FOR MORE INFORMATION, call your G-E representative or write for Bulletin GEC-713. General Electric also offers a complete line of thermocouples—described in GEC-714. Write Section 602–238. General Electric Company, Schenectady, New York.



FOUR TYPES AVAILABLE—indicating, protecting, two- and three-position control forms. Both flush and surface mountings can be supplied; wide variety of temperature ranges is available.

GENERAL 👺 ELECTRIC

.35

.00

.14

25

HEAVIER CONSTRUCTION

another reason why OHIO is the PREMIER mill magnet

In skull cracker service—or any use where magnets are subjected to hard knocks—you need the extra heavy construction of Ohio Magnets.

Take a look at this Ohio Basket Magnet, for instance. In addition to extra heavy top and bottom plates, hefty fenders project beyond magnet diameter . . . stave off and protect against damaging blows.


For extra magnet life, extra magnet value—specify Ohio Magnets. And remember, Ohio Magnets lift as much or more than other magnets of the same size.

A-5388

THE OHIO ELECTRIC MFG. CO. - 5900 MAURICE AVENUE - CLEVELAND 4, OHIO

CHESTER BLAND







"Our nation has grown great largely because opportunity is freely given. Only very few people actually make their own 'breaks.' Today, millions of Americans are providing for their personal financial security and at the same time helping in the building of our national defenses. The opportunity to do so is given by business management which affords employees the means of practicing systematic thrift through the Payroll Savings Plan for the purchase of U.S. Defense Bonds."

Nearly seven million employees of industry are "providing for their personal security and at the same time helping in the building of our national defenses."

- they are the men and women who availed themselves of the opportunity referred to by Mr. Hahn the opportunity to enroll in the Payroll Savings Plan for the systematic purchase of U.S. Defense Bonds.
- they represent a high percentage of their companies' employees—in plant after plant, the averages are climbing to 60%, 70%, 80%—even higher.
- their investment in Defense Bonds—and America add up to \$140 million per month.
- they constitute a large block of the men and women who on December 31, 1951, held Series E Bonds

amounting to \$34,727,000,000-\$4.8 billions more than the cash value of Series E's outstanding in August, 1945.

Not far from you is a State Director of the Savings Bond Division. He will be glad to tell you how easy it is to give your employees a Payroll Savings Plan. Or, if you already offer the Plan to your people, he will show you how to conduct a simple person-to-person canvass of your plant—a canvass intended to do only one thing—to put a Payroll Savings Application Blank in the hands of every man and woman on your payroll. Your employees will do the rest.

Phone or write to Savings Bond Division, U.S. Treasury Department, Suite 700, Washington Building, Washington, D. C.

The U.S. Government does not pay for this advertising. The Treasury Department thanks, for their patriotic donation, the Advertising Council and







YOU CAN'T LOSE--and We're Sure You'll Save Money!

See for yourself why Marathon Industrial Wipers are more efficient and economical than any other wipers. Try our wipers for 90 days. Send a description of the wiping jobs in your plant along with the order. We'll engineer the correct wiper for your purpose from our 70 grades. Then, if you don't save, tell us your costs for a typical 90 day use of your present wipers or shop towels, and we will promptly refund the difference.

But our experience with hundreds of industrial concerns indicates that you will save up to 25%! So send your order NOW!

WIPING MATERIALS, INC. . 2000 N. Main St. . St. Louis 6, Mo.

AFFILIATED WITH Richfer Warehousing Corp.
Madison St. Terminal Warehouse Corp.
Madison St. Terminal Warehouse Corp. of III. ASSOCIATE COMPANIES St. Louis * Omaha Oakland * Los Angeles

Wherever an ACORN NUT is indicated

-slash your fastening costs



OCKING NUTS

- Self-locking action holds tight under vibration
- Eliminates lockwashers
- · Priced lower than ordinary



ABERDEEN, S. D


ON light assemblies now using ordinary cap or ON light assemblies now using ordinary cap or accorn nuts, you save money and get a quick, secure fastening by changing to PALNUT Accorn Self-Locking Nuts. They are pleasingly dome shaped and have the famous PALNUT double-locking action that defies vibration. Very low in cost—light in weight—easily, speedily applied—cover rough, unsightly bolt ends, eliminate catching or scratching. Send details of application for free samples and further information.


The Palnut Co., 63 Cordier St., Irvington 11, N. . In Canada: P. L. Robertson Mfg. Co., Ltd., Milton, Ontario 63 Cordier St., Irvington 11, N. J.



There's a reason 71%

of all popularly-priced Tool and Cutter Grinders sold in 1951 were "Knock - Outs"





LIVERATURE

INDUSTRIAL RADIOGRAPHY


the LOW COST Way
... with Radioactive
Cobalt-60

FREE booklet covers sources, container, handler, survey and personnel protection instruments. Write TODAY for your copy.

• Tracerlab Cobalt-60 Radiography sources with their versatility, low cost and practicality, offer foundrymen, welders and fabricators the ideal means for the non-destructive inspection of metal objects. • For years such inspection has been carried out by X-ray machines or radium, but the cost has been prohibitive, particularly to the occasional user. NOW . . . with Cobalt-60 sources . . . even the smallest firm can radiograph their work to PROVE its quality.

BERKELEY . CHICAGO NEW YORK . WASHINGTON





Accurate Perforating Company can supply precision perforating for every purpose—industrial and ornamental—at the right price for every job! Accurate gives you these advantages: An unusually wide selection of perforating dies...FREE engineering consultation service which assures you that your most exacting requirements can be met...plus quick, dependable service. Write today for your FREE copy of our catalog.

SERVING THESE INDUSTRIES:

AIRCRAFT * AUTOMOTIVE * BUILDING CONSTRUCTION * COMMUNICATIONS * ELECTRICAL EQUIPMENT * FOOD PROCESSING * HEATING * MINING * RADIO AND RADAR * RAILROADS * SHIP BUILDING * STEEL * LAUNDRY EQUIPMENT * VENTILATING

IN THESE MATERIALS:

ALUMINUM * BRASS * BRONZE * COPPER * LEAD * MONEL METAL * STEEL * STAINLESS STEEL * MASONITE * PLYWOOD * PAPER * CLOTH

ACCURATE

perforating company 1101 S. KEDZIE AVENUE • CHICAGO 12, ILLINOIS





Œ

CONSIDER GOOD USED **EQUIPMENT FIRST**

BELT GRINDING UNIT

iill Clutch & Machine & Fdy. Co. Open Side Abrasive Belt Grinding Unit, Designed to accommodate slabs up to 1/2" thick x 30" wide x 30" long.

BRAKE-LEAF TYPE

16' x 1/4" Dreis & Krump Leaf Type Bending Brake, Motor Driven with 40 H.P. A.C. Motor. BUILDING

72'6" x 140" Steel Building—NEW—Designed for Corrugated Steel Siding and to carry load of 30 ton overhead electric traveling crane.

CHARGING MACHINE

6000 lb. Brosius Floor Type Gasoline Driven Charging Machine. Equipped with Peel, Gas-oline Engine, Rubber Tires.

CRANE

CKANE 6/2 ton Shepard-Niles Overhead Electric Travel-ing Crane 80' Span, Motors 440/3/60. Equip-ped with Z¹/₂ yd. Clamshell Bucket. CRANE-GANTRY

ton Whiting Two Leg Gantry Crane 52 Ft. Span Cab Control. Three Motors 220 v. 3 ph.

FLANGING MACHINE

"McCabe Pneumatic Flanging Machine, Pneumatic Holddowns, Circle Flanging At-

FORGING MACHINE

5" Ajax Forging Machine or Upse driven. Equipped with Air Clutch FURNACES—Melting Upsetter, Motor

driven. Equipped with Air Clutch.

FURNACES—Melting
400 lb. Moore Type "UT" Melting Furnace Top
Charge. Complete with Transformer. New
1943—Little Used.
15 ton Heroult Model V-12 Electric Melting
Furnace Top Charge hydraulically operated.
Complete with Transformer Equipment.
25 ton Moore Size "NT" Melting Furnace, with
7500 KYA Transformer 13,200 vo. 3 ph. 60 cy.

LEVELER—ROLLER

Aetna-Standard Roller Leveler, Metor ren. 17 Rolls 4%" Dia. Driv

PLANERS

PLANERS

48" x 48" x 20' Cincinnati, Four Head

48" x 48" x 12' Niles-Bernent-Pond, Four Head

60" x 40" x 12' Niles-Bernent-Pond, Four Head

72" x 72" x 12' Niles-Bernent-Pond, Four Head

PLATING MACHINE

Type "B" Crown Full Automatic, Nickel Chrome Plating Machine, Max. Work Si 16" wide x 36" deep x 4" thick. PRESS—KNUCKLE JOINT

1000 ton Bliss #27 Knuckle Joint, Embossing & Coining Press, 21/2" stroke, 18" Shut Height. ROLLING MILLS

OLLING MILLS
"x 10" Schmitz Single Stand Two High With
Friction Drive Rewinder.
2½" x 16" Philadelphia Two High Cold Rolling Mill. Complete with Pinion Stand, 75 H.P.
Motor 440/3/60. Starter and Controls, Incl.
Coller

Coller.

Y. 24" Waterbury Farrel Two Stand Two High Rolling Mill. Complete with Elec. Equip.

Y. x 40" Three High Roughing Mill. Complete with billet heating furnace and accessory equipment including electrical equipment. The Self United Two High Skin Pass Mill TRAJECTION.

STRAIGHTENERS

No. 3 Medart 3.Roll Straightening Machine Capacity 1" to 3½" Bars er 4½" O. D. Pipe or Tubing. NEW 1950. No. 4 Kane Roach 8-Roll Straightener Capac-ities 2" Rounds or Squares, 3x33½" Angles, 2½" Channels, set.

NO. 4 Kane Koach 6-Kall straightener Capacities 2" Rounds or Squares, 3x3x%" Angles, 2½" Channels, etc.

No. 18 Suthan Round Straightener, Motor Drive, Capacity 3/16" to 3%" O.D. Friction Drive complete with 1/3 H.P. A.C. Motor.

TESTING MACHINE

And It Sentiment Emery Halversal Hydraulic

20,000 lb. Southwark-Testing Machine, 300,000 lb. SOUTHW draulic Testing Mac TRIMMING LINE Southwark-Emery Universal Hydraulic SOUTHWARK-EMERY Universal Hy-

achine.

Rolls and Scrap Cutter. Capacity for steel or aluminum alloys 1/4" max. Trimmed width 22" min. 66" max. Scrap Length 3/4" min. 2/4" max.

UNIVERSAL IRONWORKERS

yerson Steel Frame Universal Iron Worker, M.D. Capacity Punch 1/4" thru 1/4", Shear I' Square 11/4" Round, 1/2" x 4" Flat, 4 x 4 x 1/4" April 1/4" Round, 1/2" x 4" Flat, 4 x 4 x

Square 11/4 Round, 1/2" x 4" Flat, 4 x 4 x 1/4" Anales.

No. 28U-30 Buffalo Armor Plate Universal Ironworker — Combination Punch. Shear & Bar Cutter. Motor Driven Capacities — Shear 3" Round, 2%" Square, 5x15/6" Flat, 5x5x5/6" Angles 12" — 311/2 # Beams, etc., Punch 11/2" thru 11/4".

RITTERBUSH & COMPANY, INC. 50 Church Street, New York 8, N. Y.

The Clearing House

NEWS OF USED, REBUILT AND SURPLUS MACHINERY

Tax Tape-Like most businessmen, used machinery dealers find the complexities of tax laws becoming increasingly involved.

To assist members with their tax problems, Detroit Chapter of Machinery Dealers National Assn. called in a tax specialist to address its first fall meeting. Using the income tax law, regulations, and case decisions as the basis for his talk, William B. Isenberg, of the Detroit accounting firm of Isenberg, Newman & Co., explained the conditions under which capital gains can be claimed and deductions allowed in typical dealer transactions.

Rentals-Gains on machinery, which constitute the stock in trade of a dealer, are taxed as ordinary income, Mr. Isenberg stated. However, the gain on sales of machines originally purchased and held for rental purposes only is regarded as a capital gain under Sec. 115 (j) of the tax law.

Mr. Isenberg next discussed the case of machinery dealer who had a motor which he originally intended to sell but subsequently used himself. He later sold the machine at a profit. Under these conditions, the profit made on the sale was also regarded as a capital gain.

Dual Operation-In another instance, a dealer was engaged in both renting and selling machines. He maintained separate inventories and sales records for each department. Under this arrangement, when the dealer sold machinery which he had previously rented, he received the benefit of the capital gains rate.

When certain property such as business real estate, machinery and equipment is used in a dealer's business for more than 6 months and is then sold, exchanged, or lost by fire or condemnation, a separate section of the law, Sec. 117 (j) becomes effective. The gain on property which qualifies under this section receives the benefit of capital gains limitations and losses are fully deductible.

If transfers of such property are made between related persons or between stockholders and a controlled corporation, the benefits of capital gains and deductions are denied under Sec. 117 (o).

Not Rent - Mr. Isenberg also cited the case of a manufacturer who acquired some machinery under a lease agreement. He made fixed monthly payments which were designated "rental" for 5 years. After paying a small additional amount, he acquired title to the machines. This transaction was challenged by the Bureau of Internal Revenue, and the Tax Court ruled that payments were not deductible as rent but represented the purchase of capital assets.

Ruling in the case was that the payments were large enough to exceed depreciation. Since they gave the payer an equity in the property, the "rent" must be treated as payments on the purchase price.

Longer Life?—As a rule, it is a generally accepted fact that the life of used machinery will be shorter than that of new equipment. However, the Bureau of Internal Revenue has often disputed this, and in one case the Tax Court sustained the Bureau's findings. When the taxpayer took the case to the Circuit Court of Appeals, the Tax Court decision was reversed, Mr. Isenberg stated.

MDNA Plans-Among the programs which the Machinery Dealers National Assn. is pushing through its chapters are local lumber pools, group insurance for members and their employees and an industry advertising program.

Idea behind the lumber pool is to cut dealer crating expenditures by having one firm buy all the lumber for dealers in a certain area. This would permit purchases to be made by carload lots at a considerable

MDNA Chicago Chapter has been the most active on this idea, though no details have as yet been worked out.

Liqu

0

THE CLEARING HOUSE-

CONSIDER GOOD USED EQUIPMENT FIRST

AIR COMPRESSORS

ul

d

e

e

19

e

r V-

V-

d

be

1e

r-

ìX

r

0-

rs

gh

ls, nd

d-

by

er is

de

le

28

a.

E

IN COMPRESSORS
14" x 12" Pennsylvania Air Compressor, 100 2 Pressure, Complete with 75 H.P. Syn. Motor
13" & 11" x 14" Sullivan W.J-3 Air Compressor 885
CFM, Driven by 150 H.P. Westinghouse Syn. Motor 440/3/60

BAR TURNING MACHINE

BAR TURNING MACHINE

Turning Machine, Capacity 1° to

Medart HF-2 Har Turning Machin 2%", Complete with Accessories BENDING ROLLS

8ENDING ROLLS
6' x %" Ryerson Pyramid Type Bending Roll
20' x 1" Southwark Pyramid Type Bending Roll
30' x 1" Southwark Pyramid Type, Motor Driven
BRAKES—LEAF TYPE
8' x %" Dreis & Krump Leaf Type Bending Brake
Motor Driven with 5 H.P. A.C. Motor
12" x 3/16" Chicago #226 Steel Apron Brake, M.D.
16' x %" Dreis & Krump Leaf Type Bending Brake,
Motor Dr. with 40 H.P. A.C. Motor

Motor Dr. With 30 Milling — NEW — Designed for 1726" x 140' Steel Building — NEW — Designed for Corrugated Steel Stilling—and to carry load of 30 ton Overhead Electric Traveling Crane

tom Overhead Electric Traveling Crane
SULLDOZER

\$9 Williams White Buildozer, Motor Dr. with 50

F.P. Motor, 440 volt, 3 phase, 60 cycle, Face of
Crosshead 20° x 90". Movement of Crosshead 24"

CHARGING MACHINE

DOOR IN MACHINE
1000 th. Broilus Floor Type Gasoline Driven Charging
Machine. Enuloned with Peel, Buda Gasoline Engine. Rubber Tires
ANES.—GANTRY

gine, Rubber Tires

CRANES—GANTRY

5 ton Whiting Two Leg Gantry Crans 52' Span Cab
Centrol, Motors 220 v. 3 nh. 60 ex.

15 ton P&H Two Leg Gantry Crans 45' Span With
13' Overhans one end. 10' other end 5 ton Auxillary,
The Trollers and 5 Motors, 410 volt 3 phase 60 evele

Two Trollers and 3 Motors, 410 volt 8 mbase 60 evelo

CRANES—OVERHEAD ELECTRIC TRAVELING

5 ton Robbins Myers

6% ton Shepard-Niles

80 Soan 440/3/60 AC

10 ton P & H

40 Snan 440/3/60 AC

10 ton Frie

60 Snan 230 Volt D C.

15 ton Niles

60 Snan 230 Volt D C.

15 ton Niles

60 Snan 440/3/60 AC

15 ton Niles

60 Snan 440/3/60 AC

15 ton Toledo

20 ton Redford

20 ton Morgan

10 Snan 440/3/60 AC

20 ton Morgan

10 Snan 440/3/60 AC

20 ton Morgan

10 Snan 220/3/60 AC

20 ton Morgan

20 Snan 220/

DIEING MACHINES
75 ton Henry & Wright High Sneed Dieing Machine
Double Roll Feed Seran Cutter, 3" Stroke
100 ton Henry & Wright Dieiny Machine, 4" Stroke,
13" Shut Height Complete Elecl. Equip.
DIE CASTING MACHINES
Model RA-12 KITV Die Casting Machine, Air operated, Pluncer Gooseneck Tyne for sinc, lead and
tin. Die snace between bars 12%" z 12%", Die
Separates 8" NEW 1919, never used
Pratt & Whitney Type RI-2418 Single Shindle 3Dimensional Keller Machine, with complete electrical equipment and accessories
FLANGING MACHINES

K" McChe Presumatic Flanging Machine, Presumatic

Holddowns Clock Planging Machine, Pneumatic FORGING MACHINES

4" National

4" National 14", 2", 3", 4", 5", Ajax 1", 2", 3", 5", Aome

17. 7. 37. 57. Acme

5 Alsx-Arr Chutch

FURNACES—HEATING

60 RW Leeds & Northrun Home Furnace \$9478-UB28. With controls Work space 23" dia x 23" deep

FURNACES—MELTING

400 lb, Moore Type "UT" Melting Furnace. Top

Charge. Complete with Transformer, New 1943—

Little Used

15 tem Heroult Model V-12 Top Charge Hydraulically

Operated, Complete with Transformer Equin.

26 tom Moore Size "NY" Melting Furnace With 7500

XVA Transformer 13,400/3/06

GEAR REDUCERS

500 R.P. United Combination Reduction Gear & Pinion

EAR REDUCERS
500 H.P. United Combination Reduction Gear & Pinion
Stand. Gear Ratio 8.581:1
600 H.P. Farrel Rirudingham, Size 18 Reduction Gear,
Ratio 720 to 244 RIPM
706 H.P. Falk Single Reduction Gear, Ratio 875 to
200 RPM.

Mesta Gear Reduction Unit. Ratio 19:1

GRINDER

No. 4 Cincinnati Centerless Grinder, Motor Driven.
Capacity standard work rest 3" to 6" dia., optional
work rest '4" to 3". Special fixtures will allow
work to be handled up to 9" dia.
GRINDER—CYLINDRICAL

GRINDER—CYLINDRIGAL

14 x 36" Norton Tyne C. Complete with Elecl. Equip.

HAMMERS—BOARD DROP

1200, 1800, 4000 lb. Model J2 Chambersburg

HAMMERS—BOARD DROP
1208, 1800, 4000 lb. Model J2 Chambersburg
1000 lb Rillines & Repenser
HAMMERS—STEAM POROF
1800, 4000 lb. Erie
HAMMERS—STEAM FORGING
1200 lb. Massition Single Frame
1800, 1800, 2000, 3000, 4000 lb. Chambersburg
600, 1500, 2500 lb. N.B.P.
600, 1300, 1300, 2000, 2500, 3500, 4000 Erie
28,000 lb. Massey Steam Foreing Hammer
HAMMERS—MISCELLANEOUS
No. 20, Maral Hammer, Geared Motor Drive

Liquidations - Bona Fide Auction Sales Arranged

| AMMERS-MISCELLANEOUS Ne. 6N Nazel Hammer, Geared Motor Drive 200 lb. Bradley Compact Hammer, Arr. for Motor Drive with 19 H.P. A.C. Motor 2000 lb. Chambersburg Paeumatic Hammer Complete with Elect. Equip. New 1951 | 3"12" Chambersburg Cecostamp Hammer, 18" stroke

WE OFFER A COMPLETE LIQUIDATION SERVICE ON ANY BASIS WHICH CIRCUMSTANCES INDICATE WOULD BE MOST BENEFICIAL, WHETHER BY AUCTION PRIVATE LIQUIDATION OR OUTRIGHT SALE

CONSULTANTS IN MANUFACTURING PROBLEMS FOR OVER A QUARTER OF A CENTURY

THERE IS NO SUBSTITUTE FOR EXPERIENCE CONTACT US IN CONFIDENCE WITHOUT COST OR OBLIGATION

LATHE—TURRET

Model 2L Glabolt Geared Head Turret Lathe, Spindle

Bore 4-1/16". Elect. Equipment and numerous
accessories incl. NEW 1951

LEVELERS—ROLLER

EVELERS - RUBLER St. M. Dia. Holls Delicon. Motor Drive Motor Drive 60" Asins Standard 17-Roll Leveler, 4%", Dia. Rolls Arr. Motor Drive

MOTORS ACTORS

1850 H.P. Westinghouse Induction Motor 6600 volt
3 phase 50 cycle 593 R.P.M.
2000 H.P. General Elec. Induction Motor 6600 volt
3 phase 50 cycle 500 R.P.M.
2500 H.P. General Floc. Direct Current Motor 6600
volt 175/330 R.P.M.

wolt 175/330 R.P.M.

MOTOR GENERATOR SET

140 H.P. General Electric Syn. Motor 4400 volt A.C.

with two generators 730 KVA 230 volt D.C., Complete with Panel Board, etc NAIL MAKING MACHINES

No. 1½ National—Sizes 10D, 12D, 10 No. 3 National—Size 6D No. 2 Glader—Sizes 6D, 7D, 8D, 9D Angell—Sizes 10D, 12D, 16D, roofing PLANER—PLATE EDGE 10D, 12D, 16D, 20D, 30D

au' x 1½ Southwark Plate Edge Planer, Motor PRESSES - HYDRAULIC No. 200 Milwaukee Port During Control of the Co

RESSES—HYDRAULIC

No. 200 Milwakke Briqueting Press, Complete with Pumps. Platon Load 118 tons. Hydraulic Operating Pressure 2100 lbs. psi.

75 ton Williams White Straightening Press, 27" Stroke, Red 8"x 16" 84" bla, Ram

200 ton Bliss Hydrodynamic 48" Stroke Bed Area

24" x 24". Hyd. Pump Incl.

500 ton Southwark Hydraulic 24" Stroke, 78" Daylight Platen 4" R to L x 32" F to B

500 ton Southwark Hydraulic 24" Stroke, 78" Daylight Platen 4" R to L x 32" F to B

Stroke Platen 58" x 56"

700 ton Elmes Forming Press 27" Stroke, 30" Dis-

restrict l'inten 36" x 36", 27" Stroke, 30" Dia. Ram, Platen 40" x 88" with overbang 40" x 129". Complete with Pump and Motor PRESS—HYDRAULIC WHEEL

tween Parallel Bars. Complete with Pump & Mo PRESS—KNUCKLE JOINT \$27 Billss Knuckle Leter.

#27 Bliss Knuckle Joint Embossing & Coining Press 1000 ton Caracity, 2 % Mtroke, 18" Shut Height PRESSES—STRAIGHT SIDE

RESSES—STRAIGHT SIDE

No. 87A Illias 250 Ton Capacity, Double Geared 32"

Stroke, 30" x 33" Bed Area, Air Cushion

No. 305 Bliss 9" Stroke 14" Shut Height Equipped with Marquette Air Cushion

No. 59 Toledo Double Geared Tie Rod Press 255 ton Friction Clutch 18" Stroke 36, "x 35" Bed Area

No. 3 Ferracute Super Speed Punch Press 30 ton Capacity. NEW 1946—never used No. 673B Bliss Single Geared 1½" Stroke, Double Roll Feed & Chopper, 10 ft.P. A.C. Motor

No. 620 Bliss High Production Press, 1½" Stroke Bl-40 Verson 200 ton Press, 30" Stroke Bed Area 40" x 44"

Roll recent No. 620 Bilas High Production.

81-40 Verson 200 ton Press, 30" Stroke Dec. 40" x 41"

No. 12 Zeh & Hahnemann Patent Percussion Press 150 ton 12" Stroke. 17" x 17" Bed Area. No. 10-E Biliss 800 Ton, 10" Stroke Bed Area. 60" x 126" 400 Ton 8" Stroke Bed Area. 48" x 108"

80" x 126"

No. 7 Bliss 100 Ton 8" Stroke Bed Area 48" x 108"
No. 1037-5/8 Hamilton 300 Ton 16" Stroke Bed Area 48" x 108" o. 1037-5/8 Hamilton 300 Ton 16" Stroke Bed Area 48" x 104" o. 93½C Toledo 175 Ton, 6" Stroke Bed Area 46" x 72" 46" x 72" total 115 10n, 8" Stroke Bed Area
No. 606'4 Hamilton 185 Ton, 11" Stroke Bed Area
36" x 60"

No. 365% Hamilton 165 Ton, 12" Stroke Bed Area 38" x 80".

No. 323% D Toledo 150 Ton, 8" Stroke Bed Area 88" x 54"
RESSES.—TRIMMING
Bliss 8.5. Trimming Press with Side Shear, 250 Ton Capacity. 8" Stroke 52" x 30" Bed Area
No. 3 Eric Flywheel Drive Trimming Press, 3%"
Stroke 13" Between Guides
No. 18 Eric Trimming Press, 100-150 Ton
UNCH.—BEAM
Long & Allatatter Double End Beam Punch, Capacity
Beam Punch End.—Punch flanges and web 24" 1beam and smaller PUNCH

PUNCH & SHEAR COMBINATIONS

PUNCH & SHEAR COMBINATION
Ryerson Steel Frame Universal Ironworker, M.D.
Capacity Punch, %" thru %" Shear 1" Square,
1%" Round, %" x 4" Flats 4 x 4% Angles
No. 28 U-30 Burfalo Armor Plate Universal Ironworker. Capacity Punch 1%" thru 1%" Shear 3"
Round 3%" Square, 5 x 1 %" Flat, 5 x 5%" Angles
Style EF Cleveland Single End Punch & Shear, M.D.
Capacity Punch 1" thru 1%"
RIVETER
125 ton Hanna Bull Riveter, Air Driven, 24" Gap, 15"
Reach, Capacity 1" rivets cold and 1%" rivets bet

ROLL-PLATE STRAIGHTENING

ROLL—PLATE STRAIGHTENING
7 Roll Bertisch Plate Straightening Machine, Capacity
10' x %". Complete Elect. Equip.
7%" Stockel Four High Rolling Mill. Max. Steel
Width 6". Work Rolls 2'%" x 7'%". Complete with
electrical equipment
8"x10" Schmitz Single Stand Two High
12"x18" Single Stand Two High, Coupp. with Elect.
Equip.

Equip.

Equip.

12"x34" Waterbury Farrel Two High

12"x34" Waterbury Farrel Two Stand Two High

20"x16" Poole Two Stand Two High

20"x16" Single Stand Two High

27"x56" United Two High Standpass Mill

28"x60" Single Stand Two High

18"x60" Three High Roughing Mill, Complete with

hillet heating furnace and accessory equipment inel-

ROLL—TAPER FORGING
No. 00 Williams White Taper Forging Roll. Rolls
24" Dia., Shaft 8" Dia.

SAWS

No. 3 Ryerson Friction Saw. 54" Blade Hydraulie Feed, Complete with Elect. Equip.

2" Ryerson Friction Saw 4.3 11 P. Motor Capacity Approx. 9" Round, 20" 1-beam. 12" H-beam SHEAR—ALLIGATOR

No. 7 Thomas Carlin Alligator Shear, 18" Blade, 39 H.P., D.C. Motor SHEARS—ANGLE

Billica & Jones No. 2 Double Angle Shear, M.D. Capacity 8" x 8" x %" Long & Alistatter Double Angle Shear, Model B, Capacity 6x0%," Complete with Elect. Equip.

SHEAR—BAR

No. LH Lewis Open End Bar Shear, Motor Drive.

No. LH Lewis Open End Bar Shear, Motor Drive.
Capacity 14" Round
10'x1" Cincinnet.

1" Cincinnati Model 10010 Gate Shear, New 1946 Little Used

Little Caed

HEARS—ROTARY
No. 60 Quickwork Rotary Shear, % "Capacity
No. 100 Kiling Rotary Shear, 1" Capacity
No. 30 Quickwork Rotary Shear, 5,16" Capacity
Quickwork Heavy Duly Circle Shear % "Capacity
Complete with Circle Cutting Attachment SHEARS

Complete with Circle Cutting Attachment
HEARS—SQUARING
12'x3'16' Stanco Steel Squaring Shear, Motor Dr.
8' x %" Drahert Model THZ 8'2500
8' x 3'16'' Cincinnati Series 1408, Motor Drives
6' x %" Long & Allstatter, Belted Motor Drive

LITTERS

81" Yoder Sheet Slitter No. 530, Capacity 8 cuts .194"
to 8 Cuts .156". Motor Dr.

72" Yoder Gang Slitter, Capacity 5 Cuts 20 Ga.

72" Yoder Gang Sittler, capacity 5 cuts 20 Ga.
STRAIGHTENERS
No. 3 Medart 3-Roll Straightening Machine Capacity 1" to 3%" bars or 4%" O.D. Pipe or
Tubing, NEW 1950
No. 4 Kane & Roach 8-Roll Straightener Capacities
3" Rounds or Squares, 3x3x%" Angles 2%"

9" Rounds or Squares, 3x3x% Angles 2\%" Channels etc.
No. 1\12 B Sutton Reund Straightener, Motor Dr. Capacity Tubing 5\16" to 2\%"—modified to handle up to 3\%" O.D. tubing
No. 1B Sutton Round Straightener, Motor Drive Capacity 2\16" to \%" O.D. Friction Drive complete with 1\3 H.P. A.C. Motor
Hilden 3 Roll Strip Straightener, Flying Shear & Cutting Machine, Capacity 14" wide 11 Ga. Sheet
Steel

dia, in lengths 12 to a.

SWAGING MACHINES

No. E4 Langeller, Capacity 1½" Tubing
No. 408 Etna Swager, Capacity 4" Tubing

NO. 408 Edna wwager, es TESTING MACHINES 300,000 % Southwark Emery Universal Hydraulia 60,000 lb. Olsen 4 Serew Rotating Nut Type Universal 20,006 lb. Southwark Emery Universal Hydraulic

20,006 lb. Southwark Emery Universal Hydraulic TRIMMING LINE #1049 Torrington Trimming Line, With Feed Rolls and Scrap Cutter, Capacity for steel or aluminum alloys '4" max. Trimmed width 22" min. 66" max., Scrap Length '4" min., 3 %" max.

TUBE MILL

WELDERS

2:0 KVA Progressive Model A-6 Flash Welder 4s volt 60 cycle. Mechanical Contactor Hi-Pressure Clamp Assembly—NeW 1949

McKay Tube or Pipe Welding Unit, Capacity 4%" to 7%" 0.D. Complete with all accessory equip-

WIRE DRAWING MACHINE
No. 0 Waterbury Farrel 7-Die Wire Drawing Machine,
Capacity ¾" rod to \$10 copper

RITTERBUSH & COMPANY, INC. 50 CHURCH ST., NEW YORK CITY 8

Telephone Cartianat 7-3437

Consulting Engineering Service Surplus Mfg. Equipment Inventories Purchased

Confidential Certified Appraisals

MILES' QUALITY

AUTOMATICS, OOG Brown & Sharpe AUTOMATIC, 8" Bulard Mult-Au-Matic, 6-spindle AUTOMATIC, 6-spindle Baird chucker BORING MILL, 4" Detrick & Harvey, horizontal. BORING MILL, 4" Detrick & Harvey, horizontal, toor type

BORING MILL, 51" Bullard Maximill

BORING MILLS, Two No. 50 Moline, 6-spindle cylinder boring

BROACH, No. 1 Foote Burt duplex surface

BROACH, 2-ton American horizontal hydraulic

BROACH, 2-ton American horizontal hydraulic

BROACH, 12-ton VU 12 LaPointe vertical hydraulic

34" Stroke, new 1948

BULLDOZER, No. 22 Williams & White

DRILL, No. 310 Baker, heavy duty

DRILL, 24" No. 25 Foote Burt

DRILL, 12-spindle No. 12 Mato

DRILL, 12-spindle No. 12 Mato

DRILL, 12-spindle No. 10 Dehance rail type

DRILL, 35-strindle Baush, adjustable spindle

GEAR HOBBER, No. 12H G&E

GEAR HOBBER, No. 3 Adams Farwell

GEAR HOBBERS, Two No. 12 Barber-Colman

GEAR HOBBERS, Two No. 12 Cincinnati:

with pressure lubrication

GRINDER 6" 30" Cincinnati two FR in feed with pressure lubrication with pressure junrication GRINDER 6"%30" Clincinnati, type ER, in feed GRINDERS, CYLINDRICAL, 10x18 Norton with hydraulic quick infeed GRINDER, CYLINDRICAL, 12"x36" Bath universal GRINDERS, INTERNAL, Nos. 16-28 and 24-36 GRINDERS, INTERNAL, Nos. 72A3 and 72A5 Heald GRINDERS, SURFACE, 12" and 16" No. 22 Healds GRINDER, THREAD, late No. 33 Excello, now ar-GRINDER, THREAD, late No. 33 Excello, now arranged for groove grinding HAMMER, Nos. 5N & 6B Nazel oneumatic HAMMER, No. 5 Acme universal LATHE, TURRET, No. 5 Acme universal LATHE, TURRET, No. 6 W&S, G. H., motor-in-base Millers, Two No. 2 Cincinnati plain MILLERS, Two No. 2 Cincinnati plain MILLERS, Two No. 1, 2 and 3 Kent Owens hand MILLER, 18" Cincinnati automatic duplex MILLER, 24" Cincinnati automatic duplex MILLER, 30/2" x 21" x 12" Ingersoll 4-spindle planer type planer type MILLER, 48" x 20" x 20' Ingersoll planer type, 3 vertical heads MILLER, 48" x 36" x 12' Ingersoll planer type, MILLER, 84" Ingersoll 6-spindle retary continuous MILLER, THREAD, Type C Hall planetary MILLER, THREAD, Nos. 4, 6 and CT 36 Lees Bradner
PLANER, 28"x28"x8' Gray Double housing one head
PLANER, 36"x36"x8' Cleveland openside
PLANER, 48"x48"x12' Gray
PRESSES, Nos. PO1, P1, P2, P3, PA4, p5 and PRESSES. Nos. PO1, P1, P2, P3, PA4, p5 and CA4 Ferracute PRESS. 50 fon Warco OBI, 1947 PRESS, No. 61 Cleveland OBI PRESSES, No. 56½, 57½ and 77½ Bliss a.s formula for the pressure of the pre trimming
PRESS, No. 245½ Hamilton s.s. tierod frame
PRESS, No. EG54 Ferracute knuckle joint
PRESS, 800 ton No. 665 Toledo knuckle-joint coining
PRESS, No. DAB411 Hamilton double action topple draw
PRESS, 100 ton HPM hydraulic
RIVETERS, large variety
SLOTTER, 16" Bement Miles crank
SAWS, Three 8165 Kalamazoo metal cutting band, SAW, 7" No. 14 Higley cold-cutting SAW, 7" No. 14 Higley cold-cutting SAWS. three L-W (Toledo) power hack, new SHAPER, 27" Morton draw cut SHEAR, 38" throat No. 17F New Duty STRAIGHTENER, No. 0 Sutton for bars TAPPER, 3½ Sausch lead screw, radial TAPPERS, Two No. 71 Ettco TAPPER, 19" Hammond sensitive drilling & tapping TESTER, 230,000 inch-pound Tinius-Olsen No. 2 torsion TESTER, 230,000 inch-pound finds-vises for son threaders, 2" Landis pipe threading and cutting THREADERS, 2" Dandis double spindle THREADERS, 2" Oster rotary head UPSETTER. 3" National air clutch UPSETTERS. Two 4" Ajax heavy duty, twin-gear WELDER, 200 KVA Federal flash butt WELDER, 100 KVA Thompson automatic spot WELDERS, 12" and 14", 12 KVA American Electric Fusion Co. spot

WRITE FOR CATALOG NO. 193 FOR COMPLETE LISTING

MILES MACHINERY CO.

2025 E. Genesee Ave. SAGINAW, MICHIGAN

REAL BILT ELECTRIC POWER EQUIPMENT

		D.C.	MOTORS		
Qu.	H.P.	Make		Volta	RPM
	2200	G.E.	MCF	600	400/509
	1750	White		600	550 700
Y	1500	Whae		5.25	600
	940	Whie	1435	250	140/170
1	600	Al. Ch.		250	400 800
	500	Witte.	CC-216	600	300/900
T.	450	Whise.		550	415
	400	G.E.	MCF	550	300/1050
	350	6 m 8875	CCM-151H	230	1100
	335	Whse.	MQ MPC	250	300/900
	100.300	GE.	MPC.	230	360/920
	200	Rel.	1970T	230	720
1	150	GE.		600	250/750
	150	Cr. Wb.	85H	230	1150
	150	Cr. Wh	83 H - TEFF	230	960
2	150	W has	SK151B	230	900/1900
	150	White.	SK-201	230	360/950
	50 120	G E.	MCF	230	250/1000
	100	W. Dag	SK-181	230	450/1000
1	100	GE.	CD-175	230	365/730
	100	G.E.	CDF-115	230	1758
		MILL	& CRANE		
6	50	G.E.	CO-1810	230	725
	33	White.	K-8	280	505
1	36	G.E.	MD-104% AA	550	700
	20	Whae	K-5	236	973
1	15	Whse.	K-5	230	630
4	10		SCM-AH		1150
	10		MD-104	230	400/800
3	6 25	Whee	16 3	230	686
Na sas 10	8	C.W.	SCM-FF	230	1750
2	3	Whae.	HK-2	230	935
	24	Whee.	K-1	230	835

A.C. MOTORS

3 phase—60 cycle

		SLI	P RING		
Qu	Hp.	Make	Туре	Volts 5	Speed
1	1800	G.E.	MT-498	2300	360
1	1500	ABB		2300	720
1	1200	G.E.	7115	2300	275
1	500	Whee	CW	550	350
1 2	500	G.E.	IM	440	900
2	500	GE.	31-574-Y	6600	900
1	500	G.E.	113	559	595
1	400	Whee.	CW	440	514
1	850	G.E.	MT-442Y	2200/4000	258
1	800	Al. Ch.		440	695
1	250	G.K.	MT-424-Y	4868	257
1	250	G.E.	MT-5598	2200	1800
1	256	Al. Ch.		550	600
1	200	Cr. Wh.	28QB	440	505
9	200	G.E.	IM17	350	585
9	200	G.E.	1M-17	440	800
1	200	G.E.	IM	440	485
1	200	G.E.	MTP	440	1170
1		sed) Whee.	CW	2300	485
	125	Al. Ch.	C. 44	440	730
1 8	125	G.E.	MT-566Y	440/2200	435
9	100	G.E.	IM	440	808
- 8	100	A.C.	ANY	440	695
1 500	100	G.E.	131-16	2200	485
i	100	Whse	CW-868A	440	780
•	100		REL CAGE	440	100
3	850	G.E.	FT-559BY	440	8570
2	450	Whee.	CB-1420	2800/4150	
i	200	Al. Ch.	4 14-1470	2200	385
i	288	G.E.	1K-17	440	380
1	200	G.E.	16	440	865
n	200	G.E.	KT-557	440	1800
i	150	Whae.	CS-8568	440	880
i	150	Whee.	CS-engs	440	580
1	150 /75	G.E.	IK	440 90	
8	125	Al. Ch	ARW	2200	1750
i	125	G.E.	KF-6328-Z	440/2200	
i	125	Whise.	118	448	485
,	2 8 47	SYNC	HRONOUS	440	489
2	8590	G.E.	TH	2300	257
	2100	G.B.	ATI	2300	251
0	1750	G.E.	ATI	2300	3600
	2006	Whae.	A 11	2300	120
20 01 80 80	785	G.E.	ATI	3200/12000	
1	450	Whee.	411	2200	450
-	858	G.E.	TR	2200	150
	994	Cr. m.	1.19	1200	100
	M-6	G Sets -	- 3 Ph. 6	60 Cy.	

	M-G	Sets -	- 3 Ph	. 60 C	y.
				D.C.	A.C.
Qu.	K.W.	Make	RPM	Velta	Velta
2	2000	G.E.	588	660	11000°
1	2086	G.E.	514	600	6600/13200
1	1500	G.E.	514	250	6600/13200
1	1800	G.E.	720	609	6609/13200
1	1500	G.E.	360	275	4400
1	1500	Whae.	608	608	4180
2	1006	Whse.	900	600	4180
1	1000	G.E.	900	260	0000
1	1000(SU)	G.E.	900	250	2200
1	750	Whse.	900	275	41/60
1	500	G.E.	720	125	2300
1	500	Whas.	900	125/250	440
1	500	Whee.	900	250	6600/13200
1	500	Whee.	1200	125/250	23/10
1	400	Whae.	1200	250	2330
1	400(SU)	Cr. Wh.	1200	125/250	2300
1	350	G.E.	900	125	2300/4160
1	300	Al. Ch.	1200	125/250	9300
1	150	Whee.	1200	275	.300
1	140(SU)	Cr. Wh.	690	125/250	440 - 2356
1	100	Delco	1200	120/240	2300
1	100	G.E.	1170	125	220 146
* 25	Cycle				

FREQUENCY CHANGER SETS

Qu.	KW	Make	Freq.	Voltages
1	3000	G.E.	25/40	2309/2300/4000
2	2500	G.E.	25/62.5	2300/2300
1	1000	GE.	25/58.3	4400/2300
1	500	Al. Ch.	2566	11000/2300

BELYEA COMPANY, INC.

47 Howell Street, Jersey City 6, N. J.

GUARANTEED TOOLS

60"x20" NILES-BEMENT-POND Geared Head Engine Lathe, rapid traverse

27"x12" MONARCH Geared Head Engine Lathe, taper attachment, AC-MD

24" x 72" centers BOYE & EMMES Heavy Duty Geared Head Engine Lathe, chuck, AC-MD.

No. 3L GISHOLT Universal Saddle Type Turret Lathe, bar feed, chucks, collets, tooling, hardened ways, rapid traverse, new 1943. Perfect Condition. Immediate

No. 28 FOSTER Geared Head Turret Lathe, rapid traverse, AC motors

42" BULLARD New Era Type Vertical Turret Lathe, AC-MD

36" BULLARD Vertical Turret Lathe con verted to Spiral Drive, AC-MD

11/2" LANDIS Double Head Bolt Threader, with leadscrews, MD

No. 1 DOUGLAS Plain Horizontal Mill, table 8"x32", power feeds, motor in base, No. 40 taper, new 1942.

No. 2 VAN NORMAN Plain Horizontal Mill, power rapid traverse, No. 50 taper, new 1942

No. 3-24 CINCINNATI Plain Hydromatic

5-13" column CARLTON Radial Drill AC motor on arm, 15 to 1500 RPM

4' AMERICAN High Speed Sensitive Radial Drill 9'' column, AC motor on arm

3 Spindle FOSDICK Drill Press, Individual AC motors for each spindle, 1942

No. 6 TOLEDO O.B.I. Press, 56 Tons

10" x 24" NORTON Hydraulic Surface Grinder, 1942

25A HEALD Rotary Surface Grinder, 24" diameter, magnetic chuck

36" OHIO Dreadnaught Shaper, AC-MD

75 Ton HENRY & WRIGHT Double Crank Dieing Machine, roll feed & Scrap cutter

No. 22 MURCHEY Threader

No. 136 CLEVELAND Rigidhobbers



#32 Lucas Precision Horizontal Boring Mill— Serial #32-18-21. 6¹ American Radial Drill—Serial #55592 #51A Fellows Gear Shaper—Serial #21252 #3 Gisholt Turret Lathe—Serial #2807-1 16¹ Gould & Eberhardt Shaper #72A Heald Sizematic Internal Grinder—Serial #24498 50¹ Hanchett Face Grinder Lodge & Shipiey Lathe—Serial #29051 #2 Norton Tool & Cutter Grinder—Serial #3355 6D Potter & Johnston Automatic Chucker—Serial #70393 72¹ King Heavy Duty Vertical Boring Mill Serial No. Lot 38—#175


#70393 72" King Heavy Duty Vertical Boring Mill Serial No. Lot 38—#175 Rowbottom Cam Miller—Serial 135/49. Rebuilt & guaranteed 20" Knight Rotary Table

Hazard Brownell Machine Tools, Inc. Providence 6, R. I. 350 Waterman St.

PL

THE CLEARING HOUSE

An Exceptional Stock of **PRECISION MACHINE TOOLS**



ESTABLISHED 1905

J. L. LUCAS & SON, Inc. MACHINE TOOLS

BRIDGEPORT 5A, CONN.

TEL. FAIRFIELD 9-3393 CABLE-"LUCASTOOLS"

VERTICAL BORING MILLS

- 24" Bullard Spiral Drive Vertical Turret Lathe—Serial 15656 36" Bullard Spiral Drive Vertical Turret Lathe—Serial 20926
- 42" Bullard New Era Vertical Lathe converted to spiral drive

- 10" x 36" Landis Type C Plain Hydraulic-1941
- 10" x 36" Cincinnati Model EA Plain Hydraulic-1939
- 14" x 36" Norton Type C Plain Hydraulic—1943 10" x 24" Landis Type C—1939 12" x 36" Cincinnati—1940

12" x 36" Norton Type L-1941

LATHES

- 13" x 18" Monarch Mona-Matic—1949 14" x 30" Centers Reed Prentice—1939
- 14" x 54" Lodge & Shipley High Speed—1941 16" x 48" Bradford Quick Change—1940
- #1-16" x 15" Lodge & Shipley Duomatic-1938 20" x 54" Centers Reed Prentice-1939

MILLERS

- # 000 Brown & Sharpe Plain—1942 #4 Cincinnati Plain—1942
- #4K Kearney & Trecker Plain-1942
- #2H-24" Kearney & Trecker Knee Type-1940 #1-18 Cincinnati Harizontal-1941
- #12-18 Milwaukee Simplex Horizontal-1940 #18-54 Milwaukee Duplex Horizontal-1942

 - #2 Cincinnati Vertical—1942
 - #4 Cincinnati Vertical—1942

TURRET LATHES

- #3 Gisholt Ram Type-Bar Feed-1941
- #4 Gisholt Ram Type—1939
- #5 Gisholt'Ram Type—Bar Feed—1942
- #1L Gisholt Saddle Type-1942
- #2L Gisholt Saddle Type-1941
- #2 Warner & Swasey All Geared Head—1939
- #3 Warner & Swasey Universal—1938
- #4 Warner & Swasey Universal—1940
- # IA Warner & Swasey Saddle Type—Bar Feed

Castern Rebuilt Machine Tools THE SIGN OF QUALITY-THE MARK OF DEPENDABILITY

HAND MILLING MACHINES

No. 1 U.S. Hand Miller, m.d.

MANUFACTURING TYPE MILLING MACHINES

No. MM-1-6 U.S. Multi-Miller, m.d. Rowbottom Cam Milling Machine Model 1403 Milwaukee Simplex Production Milling

Model 1403 Milwaukee Simplex Production Milling Machine, m.d.
AS Sundstrand Copy Rigidmill, m.d.
Type P Chio Mfq., m.d.
4" Pratt & Whitney Spline, m.d.
No. 33 Kempsmith, s.p.d.
18" 24" Cincinnati Plain Automatic, m.d.
24" Cincinnati Plain Automatic, m.d.
24" Cincinnati Duplex Automatic, m.d.
No. 21 Brown & Sharpe Automatic, s.p.d.
48"x48"x20" Ingersoll Fixed Rail Milling Machine, for tank work

Tori tank work Carter & Hakes, m.d. 48 x16 Newton Slab Miller, m.d. 54 x30 x17 Inaersoll Slab Miller, m.d. Taylor & Fenn 2 spindle Spline Miller, m.d.

PLAIN MILLING MACHINES

D Brown & Sharpe, cone 18 Milwaukee, m.d. 1M Cincinnati, m.d.

300

ial

rial uilt

. 1. GE

|4"x16" U6 Automatic Hob, m.d. Hall Planetary, m.d. 5"14", 620", 6x48", 6x20" Pratt & Whitney 10x24" Hanson Whitney, m.d., latest

3 Van Norman Duplex, s.p.d. 38 Milwaukee, m.d. 2 Rockford, m.d. 20 LeBlond, beited m.d. 4 Ohio, cone

THREAD MILLING MACHINES

UNIVERSAL MILLING MACHINES

No. 2A Brown & Sharpe, s.p.d. No. 3 Kempsmith, cone

VERTICAL MILLING MACHINES

Sundstrand Rigidmill, m.d., vertical spindle
No. 08 Cincinnati, m.d., late
No. 3V Toledo, s.p.d.
No. 6 Becker, cone
Newton Vertical Miller, rotary table
54' Ingersol! Single Spindle Adjustable Rotary
Mill, m.d.

MILLING MACHINE ATTACHMENTS

16" Cincinnati Circular Milling Table, p.f. Kearney & Trecker Attachment for Milling Bridge Reamers, 62" long x 24" wide 11/4" Cincinnati Rack Mill. Attach, for No. 3 Dial

cal Attachment for Millwaukee Mfg. Type

Miller
Cincinnati Vertical Attach, for use an latest type
No. 2L or 2MH rectang lar overarm Millers
16" Kearney & Trecker Rotary Table, p.f.
16" Cincinnati Rotary Table, p.f.
20" Rotary Table for 4H Milwaukee Vertical Miller
Rack Cutting Attachment for No. 4 Cincinnati
High Power Miller, s.p.d.
26" Cincinnati Power Feed Rotary Table

PIPE MACHINES

2" Bignall Pipe Machine, cone 2" Forbes Type Curtis & Curtis Pipe Machine,

PRESSES

PRESSES
Chambersburg 30 fon Hypro Pneumatic
Springfield No. 1 Straightening Press
No. 4 Verdin, Kappes & Verdin O.B.I. Press

Fast Feed O.B.I. Punch Press, #19081, 10 ton, 2" stroke Niagara O.B.I. #A2 Punch Press, 18 ton, 134"

stroke No. I Robinson O.B.I., flywheel vee belt m.d. No. 4 Johnson O.B.I., flywheel vee belt m.d.

PUNCHES & SHEARS

No. 2 Hilles & Jones Horizontal Punch, m.d.
No. 6 Long & Allstatter Single End, m.d.
No. 7 Thomas Vertical, latest
Pedrick & Ayer Pneumatic, 5" throat
#10 King Single End Punch, 48" depth of throat,

Robinson Punch, lever type, 13" throat, hand

operated lo. 6½ Hilles & Jones Punch & Shear, single end, type G leveland Shear, 72" gap, 18" blade, will shear 1910—1" plate ?" gap Cleveland Plate Punch

RAILROAD MACHINERY

93" Niles-Bement-Pond Car Wheel Barer, m.d. 52" Betts Car Wheel Borer, late 90" Niles Balanced Quartering & Crank Pin Turning Machine, late burnished Rollers for use on above machine 90" Niles Journal Lathe, including 2 inside Journal Turrets and 31/2" spinale double quartering attachment, m.d.

tering attachment, m.d 90" Niles Driving Wheel cathe, m.d., late Niles-Bement-Pond Quartering Machine, m.d., new



We carry an average stock of 2,000 machines in our 11 acre plant at Cincinnati. Visitors welcome at all times.

MACHINERY COMPANY EASTERN HE

1002 Tennessee Avenue. Cincinnati 29. Ohio

MElrose 1241

HOT STRIP ROUGHER OR PLATE MILL

Heating furnaces and mills to roll 90" wide plate or break down slabs for 90" continuous hot strip mill.

This installation is capable of rolling 60,000 tons of steel per month and consists of:

SOAKING PITS.

2-HIGH 30" x 100" REVERSING SLABBING MILL WITH TABLES. HYDRAULIC SLAB SHEAR, 6" x 60" CAPACITY, WITH TABLES. SLAB CONVEYOR TO CHARGING PLATFORM OF FURNACES. TWO CONTINUOUS SLAB HEATING FURNACES. 27" x 90" FINISHING SCALE BREAKER. 3-HIGH PLATE MILL, 34" & 22" x 100", WITH VERTICAL EDGER; TILTING TABLES ON ENTERING AND DELIVERY SIDES.

Further Details Upon Request

FRANK B. FOSTER, INC.

2220 Oliver Building, Pittsburgh 22, Pa.

Cable: "Foster Pittsburgh"


Telephone ATlantic 1-2780



1114-16 Frankford Avenue GArfield 5-0681

Philadelphia 25, Pa.

FROM STOCK
No. 1L GISHOLT TURRET LATHES
Seriol No. 635-50
With: Hardened ways, antifriction bearings, coolant pump, work light, air cylinder and controls less chuck, 2 multiple tool holders, 1 slide tool, 1 flanged tool holder, overhead pilot bar bracket and pilot bar, square turret, 7½ H.P. 60 cycle 220-440 volt 1165 RPM AC motor and controls.



Serial No. 612-7
With: anti-friction bearings, steel ways, cross sliding turret, power feed to carriage cross slide, compound rest with hand feed, taper attachment to front carriage, thread chasing attachment, with selective gear box, 9 leaders for thread chasing attachment, 5 short flange tool holders, 12" 3-jaw chuck, chuck guard and 7½ H.P. 60 cycle 220-440 volt 1200 RPM Motor.

Both machines are reconditioned and available for immediate shipment, subject to prior sale.

The Above Machines, Plus Many Others, Can Be Inspected Under Power in Our Warchouse

WRITE-WIRE-PHONE

· EVERY BUYER A BAUER BOOSTER ·-

Boring Mills, 48" and 72" Gisholt.
Header or Upsetter, 3" Ajax, M. D.
Grinder, Thompson, 10 x 36 Univ. M. D.
Lathe, 60" x 25' c. Mackintosh-Hemphill.
Millers, Plain, Nos. 3, 4, and 5B.
Planer, 48" x 48" x 12" Gray, Spur Gear Drive.
Press, Trimming No. 6 W&W, and #73-1/2 Bilss.

WEST PENN MACHINERY COMPANY 1210 House Bldg. Pittsburgh 22, Pittsburgh 22, Pa.

FLANGERS, %" & 1/2" McCabe (2) RADIAL DRILL, 5" 15" Col. Amer. Trl. Purp., M. cn arm
RADIAL DRILL, 5' 14" Cel. Amer. Trl. Purp., Gear
RADIAL DRILL, 3½" Merris, 9½" eol.
LATHE, 46" x 20" Bed Amer., 1"A., M.D.
LATHE, 14" x 6" Bed Amer., 1"A., "Sw., T.A., M.D.
SLOTTER, 20" Bement Miles, M.D.

LETCHER W. BENNETT & SONS P. O. Box 544 CLIFTON, N. J. PHONE-PRESCOTT 9-8998

6000 Lb. Chambersburg double frame Steam Forging Hammer.

2000 Lb. Erie Steam Drop Hammer, late

Multiple Punch No. 30-A W. W. 600-tons. Multiple Punch No. 6 Cleveland 750-tons. Multiple Punch Size G. L. & A. 940-tons. 300 Ton Oil Geared High Speed 2-Column Hydraulic Press, Stroke 18", ram 27"

750 Ton Williams White Self-Contained Down Moving Hydraulic Press, Bed 36"

Down Moving Hydraulic Press, Bed 36" x 42", practically new.
Nipple Threading Machines (3), New 1950, 1/2", 11/4", 2". Roller Pipe Cutter.
H. & J. Straightening Rolls 5/6" x 48".
Kane & Roach #24 Angle Bender, Capacity 6 x 6 x 1".
5" Ajax Upsetting & Forg. Machs. twin gears, twin flywheels, susp. slides.
National Upsetting & Forg. Machs. 2", 4".
Ajax and Acme Upsetting & Forg. Machs., not susp. slides. sizes from 1" up.

not susp. slides, sizes from 1" up.
Williams White Horizontal Bender &
Straightener, Capacity 15" beams.
W.W. Bulldozers, #22, #3, #4, #29
Speed; #29-U type, reversing clutch.

Chambersburg Board Drop Hammers, 800 lb., 1200 lb., 2000 lb., 3000 lb. Niagara Shear, Capacity 3 ft. 3/16". Nazel Air Forg. Hammer #6-B, 7" sq

Nazel Air Forg. Hammer # 6-8, 7 sq.
Bradley Hammers, Cushioned Helve, Upright & Compact.
Bar Shear #12 B. C. Buffalo 5" Rd.
Bar Shears, Open End., Table cost on Slant; also Guillatine 11/2" to 3".
Knuckle Joint Press 200-ton, 6" str.; EG-54

Ferracute 400-ton.

600-ton R. D. Wood Incl. Hydr. Locomo-tive Wheel Press, 96" betw. bars. #50-A Quickwork Whiting Rotary Shear

74 .

BOLT, NUT & RIVET MACHINERY, COLD HEADERS, THREAD ROLLERS, THREADING MACHINES, TAPERS, COLD BOLT TRIMMERS, SLOTTERS, HOT HEADERS AND TRIMMERS, COLD AND HOT PUNCH NUT MACHINES, POINTERS.

DONAHUE STEEL PRODUCTS CO. 1913 W. 74th Street, Chicago 36, III.

Flexible Rubber Hose Assemblies

For Machine Tools and Equipment of Every Make and Description

VARI-PURPOSE HOSE ASSEMBLIES HYDRAULIC HOSE ASSEMBLIES PAINT SPRAY & AIR HOSE ASSEMBLIES LUBRICATION HOSE ASSEMBLIES

For use with the following:

Acids
Air
Acotylene
Beverages
Chemicals
Cutting Oil
Distillates
Fuel Oil

Gasoline
Grease
Grinding Oll
Hydraulic
Lacquer
Lubrication
Oil
Oxygen

Paint
Pneumatic
Solvents
Spray
Steam
Thinners
Water
Welding

R

JO

23th

Oct

Deliveries Immediately from Stock!

COMPLETE CATALOG AVAILABLE UPON REQUEST

CARLYLE RUBBER CO., INC. 64 PARK PLACE NEW YORK CITY 7, N. Y.

PRESS BRAKE

14'-1/2" cap. All Steel 500 ton Cap. Hydraulic. Must move from plant. Good buy.

BALCHER MACHINERY COMPANY

1884 S. Compton Road Cleveland Heights 18, Ohio Telephone: Fairmount 1-1186

RAILROAD EQUIPMENT — FOR SALE

USED

RECONDITIONED

STANDARD GAUGE FREIGHT CARS

Box, Double Sheathed, 40-Ton Capacity Box, Single Sheathed, 50-Ton Capacity Flats, 40 & 50-Ton, Steel Underframe, 40'0" long Gondolas, Composite, 40-Ton Capacity Gondolas, Composite or All-Steel, 50-Ton

Hoppers, Covered, All-Steel, 70-Ton Hoppers, Twin, All-Steel, 50-Ton, Cross Dump Hoppers, All-Steel, 70-Ton, Cross Dump Tank, 3,000-Gallon, High Pressure Tank, 8,000-Gallon, Coiled and Non-Coiled

EXTRA LONG FLAT CARS

40 & 50-Ton Capacity, Length 70' and 74'

CABOOSE CARS

Eight Wheel, Cupola Type

STANDARD GAUGE AIR DUMP CARS

Side Dump, 20-Yd., 40-Ton, Lift Door End Dump, 20-Yd., 50-Ton, Drop Door End Dump, 10-Yd., 30-Ton, Lift Door

OTHER EQUIPMENT

Locomotive Cranes Overhead Cranes Railroad Track Scales

STANDARD GAUGE DIESEL-ELECTRIC ROAD SWITCHING LOCOMOTIVE

1500 H.P., 120-Ton, Type 0-4-4-0

Send us your inquiries

We Buy Freight Cars for Dismantling

Send us your offerings

IRON & STEEL PRODUCTS, INC.

"ANYTHING containing IRON or STEEL"

. REPAIR PARTS For All Types of Freight Cars


General Office 13496 S. Brainard Ave. Chicago 33, Illinois Phone: BAyport 1-3456

New York Office 50-b Church Street Phone: BEekman 3-8230 New York 7, N. Y.

STORAGE TANKS 6.000 Gallon 8,000 Gallon 10,000 Gallon

WORLD'S LARGEST STOCK STAMPING PRESSES

BLISS . CLEARING . CLEVELAND FERRACUTE • HAMILTON • L & J NIAGARA • TOLEDO • V & O



SOUARING SHEARS . PRESS BRAKES REBUILT and GUARANTEED

JOSEPH HYMAN & SONS

TIOGA, LIVINGSTON & ALMOND STS. PHILADELPHIA 34, PA. Phone REGENT 9-7727

MACHINE TOOLS:

NEW - USED - REBUILT OVER 1000 MACHINE TOOLS 'IN STOCK'

Horiz, Millers, #3 Cincl., #4 and #5, High Power Vert. Mill, #4 Cincl., High Power, Timken Bearing, M.D. Vert. Mill, No. 5C Becker Die Sinker, M.D. Radial Drill, #19 Cincl. Blekford, M.D. Radial Drill, #19 Cincl. Blekford, M.D. Radial Drill, Cincinnatt Blakford, 5'x 13" column Lathe, 32" x 16' Bridgeford heavy pattern grd. ad Lathe, 26" x 14' Lodge & Rhipler, 9' c.c., mt. drive Boring Mill, 120" Cincinnati Vert., 2 swivel heads

Boring Mill, Betta 60", 2 swivel honds
Sering Mill, Bullard 24" Vertiral Turret Lathe
Boring Mill, Lucas Horizontal, 3" Bar, M.D.
Hammer, Bradley 2002 Rubber Helve
Punch, Hilles & Jones 25, single end 46" throst
Press, 278'y Bliss S.S., M.D.
Rolls, Bertsch 18' x 1%" cap. Late, M.D.
Shear, 28E Ningars, 8' x 3/16" Cap. M.D.
Welder—Spot, Federal 200 KVA, 60 cye.

FALK MACHINERY COMPANY

16 WARD ST.

BAKER 5887

ROCHESTER, N. Y.

ATTENTION Production Pipe People ALL NEW

3 Stamets Pipe Threaders 4½"-14" Capacity 4 B.&O. Crop End Cut Offs up to 14½". 4 B.&O. Crop End Cut Offs with Roller Feeds up to 14½". 1 B.&O. Coupling Blank Cut Off up to 14½".

All new in original export boxes with loads of tooling. Prices and details upon request. One Lot Buyer Preferred.

KINGS COUNTY MACHINERY EXCHANGE

408 Atlantic Ave., Brooklyn 17, New York

FORGING PRESS

No. $1\frac{1}{2}$ National—350 ton Bed 16" x 23"—Air Clutch

LANG MACHINERY COMPANY

28th St. & A.V.R.R.

alic.

IY

AGE

Pittsburgh 22, Pa.

KNOX

AIR COMPRESSORS FULLY GUARANTEED

EARLE E. KNOX COMPANY ERIE. PA.

COMPRESSORS and VACUUM PUMPS NEW and GUARANTEED RESULTS

Electric - Steam - Gas - Diesel SALE . RENT . BUY

Since 1902

AMERICAN AIR COMPRESSOR CORP.
OILL AVENUE & 40% STREET HOSTEN SEGEN, N. J.
Tripping Wines SARN

THE CLEARING HOUSE



FOR SURPLUS STEEL PLANT EQUIPMENT

1-30" Dia. x 54" Face 2-High Balance Sheet Breakdown Mill, complete with ±0". Pinion Stand, Motor Operated Screwdown, Couplings, Spindles, Spindle Carriers, Bed. Plates, etc.

1-6000 H.P. General Electric Motor, phase, 60 cycle, 2300 volt, 90 RPM, Type TSM-80.

1-2000 H.P. General Electric Slip Ring Mill

Write for the Curry List of available steel plant

Type Motor, 236 RPM, 3 phase, 60 cycle lator, in and out plugging, and all other etrals for mill type operation.

1-114" x 48" Lewis Plate Shear, complete 3/60/220 valt Mater

1-84" x 514" Diameter 17 Roll Leveller.



941 OLIVER BUILDING . PITTSBURGH 22, PENNA. Phone ATlantic 1-1370

complete with 40 H P DC Motor, Capacity 1/32'' to $1/32'' \times 84''$.

1-72" Hydraulic Stretcher Leveller, complete with Motor, hydraulic Pump, and Controls. Excellent condition

1-Scrap Baller (Never Used), 21" diameter x 35" face roll, hydraulically ret mandrel, 10 H.P. Motor required.

1-712" 4-High Reversing Cold Reduction Mill, complete with Coiling and Uncoiling Equipment, Motors, Motor Generator Set, and all Electrical Equipment.

Cable Address: CURMILL-PITTSBURGH

SALE

The following Used Wide Flange Beams and Plate Girders with existing attachments used only a short time in temporary bridge work:

PLATE GIRDERS:

QUAN.	LBS. WT. EA.	LENGTH	B TO B	WEB THICK- NESS	FLANGE ANGLES	SECTION MODULUS (in 3)
2	9,981	35'01/2"	861/2"	7/16"	4-6x6x3/8"	1,180
2	9,315	34'63/4"	751/2"	3/8"	4-6x6x7/16"	1.050
2	9,240	34'11"	751/2"	3/8"	4-6x6x7/16"	1.050
6	9,205	34'11"	751/2"	3/8"	4-6x6x7/16"	1.050
4	9,206	34'11"	751/2"	3/8"	4-6x6x7/16"	1.050
2	9,243	34'11"	751/2"	3/8"	4-6x6x7/16"	1.050
2	9,957	34'71/2"	861/2"	7/16"	4-6x6x3/8"	1,180
20	9,946	34'71/2"	861/2"	7/16"	4-6x6x3/8"	1,180
2	10 288	35'113/4"	861/2"	7/16"	4-6x6x3/8"	1,180
1	6,443	Ap. 25'	411/2"	3/8"	4-6x6x1/2"	510
1	7,504	26'41/2"	751/2"	3/8"	4-6x6x7/16"	1,050
1	6,783	Ap. 25'	751/2"	3/8"	4-6x6x7 16"	1.050
1	7,372	Ap. 25'	751/2"	3/8"	4-6x6x7/16"	1,050

CHANNELS:

330 pcs.—15" Channels @ 33.9#—6'4"

Write, wire or 'phone

KLINE IRON AND METAL COMPANY

P. O. Box 1013, Columbia, S. C.

Telephone 4-0301

BLISS No. 55 Double Action Toggle Draw Press, Bed Area 38" x 33", Stroke of Blankholder 10". Stroke of Plunger 21", Air Clutch. New in 1945. BLISS No. 88 Straight Side Single Crank Press, Capacity 255 ton, Bed Area 30" x 29", 18" Stroke of Slide, Marquette Air Cushion. TOLEDO Dauble Cranks, Nos. 91-42, 92C, 931/2C, 931/2E.

CLEVELAND Double Cranks 65-G-72, 45-D-60.

CLEYELAND Double Cranks 65-G-72, 45-D-60.
NIAGARA Double Cranks, 67C, 68C, 612C.
BLISS No. 25K Knuckle Joint 600 Ton Capacity.

National Machinery Exchange
128 Mott St.
Canal 6-2470 ************************

Foote-Burt 3-way Drill. Heald No. 72 Internal Grinder, M.D. Heald No. 25 Rotary Grinder, 16" chuck. 30" P & W 2-spin. Vert. Profiler.

D. E. DONY MACHINERY CO. 47 Laurelton Road Rochester 9, N. Y. Grinder, Suríace, Sx12x12'' Taft Peirce, MD. Grinder, Thread, #33 Excello, MD. (1942) Hack Saw, 10x10'' Rasmussen, MD. (1943) Lathe Converter, Versamill, 34 HP. 1/60/115 V.

(new)
Lapping Machine, ±7 Ultra, MD. (1943)
Miller, Vertical, 08 Cin, MD. (1942)
Nibbler, Gray, 36" tht., cap, 1", MD. (1948)
Pipe & Nipple, 2" Landis D.H., MD. (1950)
Press, Reducing, ±156 Niagara B.G., MD., 56Tan

Ton Shear, 52"x12 ga. W. & M., MD. (1946) Thread Grinder, #33 Excello, MD. (1942) Thread Miller, 12x30" Morey-Shields, MD. (1942) Turret Lathe, #1 W. & S. 5½", B.F., MD. (1941)

GALBREATH MACHINERY CO. 306 Empire Bldg. Pittsburgh 22. Pa.

FOR SALE

1 Economy No. 112F Mechanical Briquetting Machine

SIPI METALS CORP.
1720 North Elston Avenue Chicago 22, Illinois

LATE TYPE MACHINERY

LATE TYPE MACHINERY

AUTOMATIC, 1/4,"—4 Spin. Gridley Model G
BOLT THREADER, 2" Landis, 2 Nds. M.D. (2)
BOLT THREADER, 1/2" Reliance Williams
VERT. Attach, for Boring Mach, for 3307 G. & L.
Mill & Outer Support
BORING MACH, 5" Bar, Lettes, Table Type
BORING MACH, 3" Bar, Lumbert Table Type
BORING MACH, 3" Bar, Lambert Table Type, M.D.
BORING MILLS, 100" Cinci., Heavy, 2 Heads, M.D.
BORING MILLS, 100" Cinci., Heavy, 2 Heads, M.D.
BORING MILL, 4" II" Col. Cinci. Bick., M.D.
RADIAL DRILL, 4" II" Col. Cinci. Bick., M.D.
RADIAL DRILL, 6" 15" col. Amer., M.-On-Arm, Tri.
Putp.

AUTOMATICAL DRILL, 6" 15" col. Amer., M.-On-Arm, Tri.
Putp.

AUTOMATICAL DRILL, 5" 15" col. Amer., M.-On-Arm, Tri.
Putp.

AUTOMATICAL DRILL, 5" 15" col. Amer., M.-On-Arm, Tri.

86

1

Ca

RADIAL DRILL TABLES, 30" x 20" (10)
RADIAL DRILL, 6' 15' col. Amer., MonaArm, Trl.
RADIAL DRILL, 5' 15' col. Amer., MonaArm, Trl.
RADIAL DRILL, 5' 15' col. Amer., MonaArm, Trl.
RADIAL DRILL, 5' 14" Col. Amer., M.On. Arm, Trl.
RADIAL DRILL, 5' 14" Col. Amer., M.D.
RADIAL DRILL, 3' 5' Niles, No. 10, M.On.Arm, Late
RADIAL DRILL, 3' 5' Niles, No. 10, M.On.Arm, Late
RADIAL DRILL, 3' 2' Morris, 9'/s' col. Gear Box
M.D.
RADIAL DRILL, 3' 5' 8' & 2'2' (New)
DRILL, 10, DRILLS, 3' 5' & 2'5' Capty.
DRILL, No. 13 6 Baker, 24", 3" capty.
DRILL, No. 15' Baker, 24", 3" capty.
DRILL, No. 16' Sellors, 18' Sellors, 1945
GEAR CHAPER, No. 6: 6. 75' Fellows
GEAR SHAPER, No. 6: 6. 4' 5' Fellows
GEAR SHAPER, No. 6: 6. 4' 5' Fellows
GERINDERS, CYL. 16" x 48" Cincl., M.D.
GRINDERS, CYL. 16" x 48" Cincl., M.D.
GRINDER, UNIV. 12" x 38" Thompson, M.D.
GRINDER, W. 11" X 5' Baker, 26" x 4" capty.
LATHE, 80" x 40' cen, Mackintosh, Hemphill, 1942
LATHE, 36" x 40' cen, Planam, 2 cen, T.A.
LATHE, 26" x 46" x 24' Sed, McCabe, Dbl. Spla.
LATHE, 26" x 48" x 24' Sed, McCabe, Dbl. Spla.
LATHE, 26" x 48" x 24' Sed, McCabe, Dbl. Spla.
LATHE, 26" x 48" x 24' Sed, McCabe, Dbl. Spla.
LATHE, 18" x 8" Sed, L. & S. Select Grd. Hd., M.D.
LATHE, 14" x 30" Cen, Monarch, M.D.
TURRET LATHE, No. 28 Foster, Univ. 3", capty.
TURRET LATHE, No. 3 Gisholt, Bar & Chuek
THEAD MILLER, No. 20 Foster, Univ. 2" capty. (2)
TURRET LATHE, No. 3 Gisholt, Bar & Chuek
THEAD MILLER, No. 20 Foster, Univ. 2" capty. (2)
TURRET LATHE, No. 3 Gisholt, Bar & Chuek
THEAD MILLER, No. 2 Van Norman, Duplex, M.D.
MILLER, No. 2 Van Norman, Duplex, M.D.
MILLER, No. 2 Van Norman, Duplex, M.D.
MILLER, No. 2 Van Norman, Duplex, M.D.
MILLER, No. 2 Van Norman, Duplex, M.D.
MILLER, No. 2 Van Norman, Duplex, M.D.
MILL

BENNETT MACHINERY CO.

375 Allwood Rd., Clifton, New Jersey Phone: PRescott 9-8996 N. Y. Phone LOngacre 3-1222


TURBO COMPRESSOR

We offer Lamson Turbo Compressor 2000 CFM 16 oz pressure, in first class condition, with 15 HP GE Type K Motor 3/60/220 volt, 1750 RPM and Cutler Hammer Control.

Northern Equipment & Supply Co. Sault Ste. Marie, Ont., Can.

THE CLEARING HOUSE-

EMERMAN Offers from STOCK



STRAIGHT SIDE, DOUBLE CRANK, DOUBLE ACTION

LATE TYPE PRESSES

(2) Hamilton, No. DA 8411

Double Action, Toggle Drawing, 650-tons capacity Area of bed 62" FB x 74" RL Stroke of plunger slide 39" Stroke of blankholder slide 28" Shut height, 75" 60 HP Driving motors, Complete with all electrical equipment Weight approx.: 188,000 lbs.

THESE PRESSES ARE OFFERED IN UNUSUALLY FINE CONDITION!



(3) Bliss Gap Frame-No. 2-EG-315-132

> Fully Enclosed Two Point Overhanging Single Action 375-tons capacity Area of bed 48" RB x 156" RL Stroke of slide 12" 40 HP Driving motors, Complete with all electrical equipment Weight approx.: 123,000 lbs.

EMERMAN MACHINERY CORP.

2)

222

G

CHICAGO 43, ILL.

BORING MILL—84" (New)
BORING MILL—200" (New)
DRILLS, Radial—4', 5', 6', up (New)
FURNACE (2)—Tocco, Jr. 20KW, 2 Sta. FURNACE--Roller Hearth, I.D. 15'8" x 3'6" x 11"
GUN BORING LATHE-64" x 65'0"

LATHE—32" x 21' c/c Bridgeford G.H.
MILLER VERT.—28" x 72" and
36" x 118" (New)

36" x 118" (New)

PRESS—2000 Ton, Knuckle Joint

PRESS—Plate Bending, 2000 Ton for forming cyl. shells, 14' W x 21/2" Thick

PRESSES—Hydraulic, 1000-4000 Tons

PRESSES—Hyd. 100-2800 Tons for 105 mm shells

RIVET HAMMER-68 Hi-Speed STRAIGHTENING PRESS-2000 Tons (Plate)

NUT-TAPPERS—¾", 6 Spindles (2)
UPSET & FORG, MACHINE—10"

MAXWELL MACHINERY CORP. 1775 Broadway New York 19, N. Y. Plaza 7-3471

FOR SALE

1 Detroit Electric Furnace, type CC-600 K.W. 3000 lb. capacity. Two linings. Two shells. New. Original crate. No transformer.

Price \$14.500.00

ADDRESS BOX 8-835 Care The Iron Age, 100 E. 42nd St., New York 17

#407-A BLISS, Double Action, Toggle, 18" draw stroke, 60" bed.

500 TON CLEARING, Hydraulic, 20" stroke, 40" bed.

125 TON BLISS, Double Crank, 14" stroke, 83" bed.

100 TON HENRY & WRIGHT, High Speed, Double Roll Feed, Scrap Cutter.

#305 B1 ISS, Single Crank, Tie-Rod, Geared, 6" stroke.

PRESS SALES CORP. 225 LAFAYETTE ST. NEW YORK 12, N. Y. BArclay 7-4430

I—15" x 30", 2-hi Rolling Mill, water cooled bearings, complete with drive and 100 HP motor, AC.

I—20" x 30", 2-hi Rolling Mill, water cooled bearings, complete with drive, control panel and 500 HP motor.

I—MacIntosh-Hemphill Alligator Shear, cap. 2½" squares or I" x 8" slabs. No motor.

1—#9 Williams & White Bulldozer, crosshead 90" Ig., stroke 30"—die space 43"—61" between dies open, 30" closed.

Lou F. Kinderman Box 182 - Niles, Ohio - Phone 2-2589

LATE TYPE MACHINE TOOLS

Model RA-4 11%" Acme Gridley Automatic. Late Type.
HP-100 La Pointe Horizontal Hydraulic Broach. 1945.
3'11" Archdale Radial Drill. 1947.
No. 7 Gleason "Revex" Gear Rougher.
1943.
14" x 168" Norton Plain Type C Grinder. 1942.
24 - 36 Bryant Hydraulic Internal Grinder.

24-36 Bryant Hydraulic Internal Grinder.
No. 72A3 Heald Plain Hydraulic Internal Grinder.
No. 72A3 Heald Plain Hydraulic Internal Grinder.
1941.
27" x 192" Niles "Timesaver" Engine Lathe. 1940.
No. 3FU Foster "Fastermatic" Platen Type Lathe. 1942.
No. H5 Libby Universal Saddle Type Turret Lathe. 1939.
No. 3R Gisholt Universal Saddle Type Turret Lathe. 1942.
No. 4R Gisholt Universal Saddle Type Turret Lathe. 1943.
8" x 84" Lo-Swing Semi-Automatic. 1941.

1941.
3A Sundstrand Copy Mill.
650 Ton Verson Double Action Eccentric Press. 1940.

Ask for Current Stock List

INDIANAPOLIS MACHINERY & SUPPLY CO. 1983 S. Meridian St. INDIANAPOLIS 6, IND.

THE CLEARING HOUSE

BULLARD

54" SPIRAL DRIVE VERTICAL TURRET LATHE SERIAL 23000 **NEW 1944** PRACTICALLY NEW IMMEDIATE DELIVERY



STAINLESS STEEL ROUND BARS

JANDRU STEEL CORP.

OVERHEAD ELECTRIC TRAVELING CRANES: 2-Shepard Niles 61/2 tan, 80° span, 4 motor, backet operating, cage control, 440 volt, A.C., with or without 21/2 or 3 yd. clam shell bucket. Now operating, 30 day delivery, condition guaranteed.

131 BRUCKNER

equipment.

RUCKNER BLVD., NEW YORK 54, N. Y. PHONE: Cypross 2-5617

AUTOMATIC CAR DUMPER: Link Belt, will dump standard R.R. Gondola Cars up to 90 tons capacity, transfer table 54 ft. Specifications and photos available. COMPRESSOR: Worthington DC2, 29/18-1/2 x 21, 600 H.P., synchronous motor, 440 volt, with all auxiliary

A. J. O'NEILL

LANSDOWNE, PA.

Phila. Phones: MAdison 3-8300-3-8301

5 TON KRANE KAR

MODEL "AX" Solid Tires, Gas Engine, 180 Deg. Swing, 14/20' Boom, Good Condition, \$3,000.00.

S. M. DAVIS 510 LaSalle St. St. Louis 4, Mo.

FURNACE TRANSFORMER

3000 KYA—Westinghouse, H.T. 26400/13200V LT—200/150V. and 115/87V. 3 ph. 60 cy. vit 345 KVA H.T. Reactor; Motor operated H.T.-O.C.B. and 2-37K.V.—160/80—Samp. C.T.S

BELYEA COMPANY, INC.
well St. Jersey City 6, N. J. 47 Howell St.

FURNACES

ROLLER HEARTH:

Surf. Comb. 84" x 29' Radiant Tube Surf. Comb. 47" x 35' Radiant Tube Elec. Furn. Co. 24"x13' Elec.-170KW Elec. Furnace Co. 57" x 20' Gas Fired Elec. Furn. Co. 54"x13' Radiant Tube General Elec, 16"x12' Elec.-127 KW Elec, Furn. Co. 29"x17' Radiant Tube

PUSHER (Gas Carburizers):

Holcroft 72" x 29' Continuous Holcroft 36" x 45' Continuous

CONVEYOR:

Holeroft 20" x 12' Gas Fired

THE JOE MARTIN COMPANY

19256 John R. Street Detroit 3, Mich. Phone: TW 2-9400

FOR SALE

10000' 2" IPS. New Seamless Steel Tubing Hat Finish ASTM A-83 20/22" 12500# .060 Rd. Brt. Basic Wire Seft ceils 14000# .060 Rd. Brt. Basic Wire ½ Hd ceils 2000 # .070 Rd. Brt. Basic Wire Seft ceils 2000 # .120 Rd. Brt. Basic Wire ½ Hd ceils 18000# .080 Sq. Extra Brt. Basic Wire Seft ceils

Send for our Steel & Machinery Lists Seaboard Steel Company, Inc.

New Haven, Conn.

LIFTING MAGNETS

A complete magnet service. Magnets, new & rebuilt, generators, controllers, reels, etc. Magnet specialists since 1910

Goodman Electric Machinery Co. 860 Broad St. Newark 2, N. J. 1060 Broad St.

WE BUY AND SELL USED OVERHEAD TRAVELING CRANES STRUCTURAL BUILDINGS

Your Offerings and Inquiries Solicited BENKART STEEL & SUPPLY CO. CORAOPOLIS, PA.

FOR SALE

1948 Invoice Price

Unused 90 inch Cupola, Skip Hoist Charger, Blower with Automatic controls all in original container. Purchased as a unit.

UNITED STATES STOVE CO. South Pittsburg, Tennessee



ASH FOR SURPLUS

800 H.P. MILL MOTOR

800 HP, 870 RPM Westinghouse Slip Ring. Type CW, 2200/3/60.
Complete with semi-automatic control panel & flexible coupling.

F. H. CRAWFORD & COMPANY, INC. Church Street New York 7, N. Y. 30 Church Street

15 TON HEROULT **ELECTRIC**

Manufactured by American Bridge Co., with side charge. Complete with 5000 KVA Westinghouse Transformer, Reactor, Winches, Masts and Motor. Furnace match-marked and tagged for erection. All parts are in excellent operating condition. Immediate Shipment.

For inspection, contact-

HEAT & POWER CO., INC. 70 PINE ST. HANOVER 2-4890 NEW YORK S

ELECTRIC FURNACE to 1850°

8 x 12 x 15 inside with Aute. Temperature Coetrel 4.5 K.W. Sliding door, cheap to eperate. Substantial, Dependable for Machine Shop—Toel Room. New. \$250.

E. H. WILLIAMS, Box 9042 Huntington, W. Va.

LOOKING FOR . . .

BUSINESS **OPPORTUNITIES?**

NEED . . .

CONTACTS or CAPITAL?

Read the Classified Section of

THE IRON AGE

MOTORS - M. G. SETS - TRANSFORMERS

ENGINEERED AND REBUILT BY SPECIALISTS IN OUR MODERN

	CRANE A	ND MILL	MOTORS-230	-VDC
i to	HP	Make	Type	RPM
1	265/200		MDP-420	350/410
Spa	re armature	& anti-	riction bearings	for above
7111.6	tori			
1	150/200	Whise.	MCB-100 MT-5	370/300
1	150	Whise.	MT-5	350
1	100/140	Whae.	MCB-90	500/415
40	100/140	G. E.	M1DA-108	430/500
3	100/130	G. E.	CO-1831 K-10 K-10 CK-19	675/690
1	85/65	Whas.	K-10	635/790
1	75/60	Whae.	K-10	425/470
7.0	75/108	Whae.	4 K-10	500 875
5	70/90	Whise.	281.74 - 1.0	4,111/198
2	70/90	White.	MCB-70	4107406
1	50/80	C. W.	FW	575/480
1	50	G. E.	CO-1839	750
1	50/65	Whee.	MCLA-121	500/450
43	50/65	Whse.	MCA-80	475/420
1	5.0	G. E.	CO-1810 CO-1830	725
1	65/85	G. E.	CO-1830	700/650
1	65 / 85	G. 12	CO-1811	600/500
4	45/57	Whise.	Dr 19	323/211
Ĩ.	45/57	Whise.	KG-9	515/476
2	35/45	G. H.	CO-1810	500/450
10	35	G. E.	MDA-1043a	650
1	30	C. W.	EH	750
T	25/35	G. B.	CO-1820	750/450
1	27%	Whse.	K-6	1050
2	25/38	G. E.	MD9-408	575/306
3	23/30	G E.	MIDP-408	600/417
70	20/28	Whee.	MCA-40	600/470
6	19/15	Whee.	K-5	630 /560

Qu	HP	M	ake	Туре	RPM
3	16/19	C.	W.	BW	620/560
1	16/13		EG.	MDS-408	615/700
1	15	43.	E.	CO-2505	700
1	15/19	G.	E.	CO-1807	600/525
1 .	13/17	G.	F.	MDA -103	645/725
1*	13/17	G.	E.	MDB-103	645/725
All	motors	series	wound	except those	marked (*)
which				rnish these for	
21(20)					

SYNCHRONOUS MOTORS -60-Cycle

Qu HP		Make	P.F.	Velts	RPM		
1	600v	G. E.	100	2300	90		
1	4350	C-W	100	13.200/6000	514		
1	3000	Whise.	80	4800/2409	7.20		
2	2100	G. 10.	100	2300	360		
2	1750	G. E.	100	2300	3600		
1	1000	El. Mchy.	100	440	1200		
1	750	G. E.	80	2300	450		
1	700	G. E.	80	2300	720		
1	250	G. E.	100	2300	514		
W				al, semi or full	mag-		

Motor Generators of modera design, complete with control—still on their original foundations—available for immediate shipment.
(3)—G.E. 1500-KW, 250-VDC, 514 R.P.M., cpd., interpole, pole face windings, 2100-HP syn. motors, 8-PF, 13,200-V, 3-p, 60-cy, will reconnect to 6600 V, or 4160-V.

SLIP RING MOTORS-CONSTANT DUTY

		2 . 6 11.007	00.0	A die			
Qu	HP	Make	Туре	Velte	RPM		
100	1800	G.E.	MT-498	2300	351		
1 **	1200	G.E.	M 3-26	2200	277		
200	1000	Al. Ch.	ANY	2200	285		
1	800	G.E.	FCL	3200	440		
100	600	G.E.	MT-20	2200	360		
2	500	G.E.	1-16-M	2300	430		
100	400	Al. Ch.	ANY	2300	814		
2	400	G.E.	MT-413	2200	450		
1	250	Whse.	CW-937	440	1200		
Fre	om mir	stock we ca	n furnish	bus lauran	magnette		

primary and secondary centrols up to 3500-HP.

MOTOR GENERATOR SETS

Qu	KW	Make	RPM	Volts	Volts
1(3-U)	2400	Whse.	720	600	2400/4800
3	1000	Whse.	514	600	11000/6660
4	1000	G.E.	514	600	11000/6600
1	1000	G.E.	514	600	2300
1	500	C.W.	730	275	2200/440
1(3-U)	500	Whise.	1200	250	440
2	500	C.W.	720	575	2300/410
2	250	Whie.	1200	125/250	2300
1	200	Ridgway	900	375	2300
1	155	G.E.	7:30	250	2300/440
9	158	When	1200	950	2300

We can furnish any of these sets with exciters and VARIABLE VOLTAGE CONTROL engineered and rebuilt to your requirements.

ELECTRIC TRAVELING GANTRY CRANE

10-ton Champion 100' span between ground rails, 31' overhang one end, 23'9" other end, 45' lift, with 1200' of 100# rail. Now 550-VAC, will arrange for 220/440-VAC or 230-V.D.C. AVAILABLE FOR IMMEDIATE INSPECTION AND SHIPMENT. In excellent condition. The kind of crane that is seldom on the market.

C CABE COMPA

4302 CLARISSA STREET

CABLE ADDRESS "MACSTEEL" PHILADELPHIA, PA. PHILADELPHIA 40, PENNA.

PHONE **DAVENPORT 4-8300**

FOR SALE

Overhead Electric D. C. Traveling Cranes

> 2-25 ton 50' span Cab Controlled

720' Crane runway 36" Beams and 75 lb. Rails

I—10 ton Whiting 40' A.C. span floor controlled

ADDRESS BOX 8-854 Care The Iron Age, 100 E. 42nd St., New York 17

FOR SALE

Morgan Continuous 24" Billet Mill with Vertical Edger built new in 1937—cooling bed, shear, approach and runout tables. This mill was used to roll 4" and 5" billets from an 8 x 8 bloom, also rolled some slabs. This mill is complete except for the main drive motor which was a 6000 H. P. Motor. Available now. Roll Leveller with drive and oiling system 7-rolls 61/2" dia. x 20" face. Maximum opening 31/2". Norton Roll Grinder—For small rolls up to 14" dia. between centers 52". Size of wheel 20". Has 16 speed automatic traverse feed and reverse. Waterville Slab Milling machine. Spiral cutter

Waterville Slab Milling machine. Spiral cutter 434" dia. x 12" face.

Non Ferrous Rolling Mills:

Non Ferrous Rolling Mills:

1—Mossberg No. 9 Rolling Mill 15" x 30"—2-high Ryertex brgs. Incl.

10—V Belt drive. Reducing gear box and electricals. 100 H. P. 550 volts, 3-phase, 60 cycles.

1—Twin rolling mill 20 x 30", two high, Ryertex brgs. center drive control panel and motor 500 H. P., 514 RPM, 2300 volts, 3-phase, 60 cycle. Miscellaneous rolls for both above mills.

ROBERT C. YOCUM MOUNT UNION, PENNA

Just Purchased

350-230v. D.C. Motors Over 6200 Total H.P. G.E.-WEST.-RELIANCE, etc Speeds 500 to 1750 RPM

2-150 HP 6-40 HP 75-10 HP 1—125 HP 2—30 HP 78— 7½ HP

12-100 HP 1-25 HP 21-3 HP

10- 75 HP 29-20 HP 22- 2 HP 2- 60 HP 55-15 HP 31-1 & 11/2 HP

Please Send Us Your Inquiries

L. J. LAND, INC.

Established 1910 CAnal 6-6976

150 GRAND STREET, NEW YORK 13, N. Y.

OFFERING

BRIDGE CRANES

ARNOLD HUGHES COMPANY

765 Penobscot Bldg. Detroit, Mich. WOodward 1-1894

LOCOMOTIVES

4—100 TON G.E. DIESEL ELEC.
1— 65 TON G.E. DIESEL ELEC.
1— 65 TON WHITCOMB DIESEL ELEC.
1— 20 TON WHITCOMB GAS

DARIEN CORP., 60 E. 42nd St., N. Y. 17, N. Y.

40 ton SHAW BRIDGE CRANE

40 ton Shaw 34'6" span with 3/60/440 mtrs. cab control. Can be inspected under power. Also available with above crane a 20 ton extra

available with document co.
ALLSTATES EQUIPMENT CO.
Chicago 343 So. Dearborn St. Chicago 4, III. Phone: Harrison 7-1821

. . . DON'T HIDE YOUR LIGHT UNDER A BUSHEL .

Have something new on the market or do you just want to tell why your product does the job better? Either way, your advertisement in The Iron Age carries more weight and reaches more of your prospects.

C

FOR SALE

Freight car repair parts Relaying rails Steel storage tanks Freight cars and Locomotives

Also

Contracting Equipment Cranes—Tractors Ditchers—Compressors **Diesel Engines** and Generating Sets

THE PURDY COMPANY

8754 S. Dobson Ave. Chicago 19, Illinois

Empire State Bldg. New York 1, N. Y.

RAILS New and Relaying



TRACK MATERIALS AND ACCESSORIES CARRIED IN STOCK

SWITCH MATERIAL . SPIKES & BOLTS - TRACK TOOLS - TIES - TIE PLATES - BUMPERS -COMPLETE SIDE TRACKS

BUILDERS STEEL SUPPLY CO.

RAILS New and Relaying



SPIKES & BOLTS FROGS & SWITCHES TIE PLATES CREOSOTED TIES

HYMAN-MICHAELS CO. 122 S. MICHIGAN AVE., CHICAGO 3, ILL.

M. K. FRANK New RAILS Relaying

We carry frogs, switches, spikes and bolts in stock and most all sections of rails and track accessories, 480 Lexington Ave., New York, N. Y. Park Building, Pittsburgh, Pa. 105 Lake St., Reno, Nevada

RELAYING

Your exact trackage needs filled "Faster From Foster" Track Tools & Accessories are properly matched and fabricated to meet all re-quirements and shipped from a reliable source.

"FASTER from FOSTER"

RENT STEEL SHEET

PILING All Lengths, Sections, all standard makes your job requires. Also Rent Pile Ham-mers, Pile Extractors.

TRACK ACCESSORIES . PIPE . WIRE ROPE 1.11.11.11. CO.

Pittsburgh 30, Pa. New York 7, N.Y. Chicago 4, III. Houston 2, Tex.

FOR SALE DIE STEEL

SAF-10100

We have for immediate shipment 150,000 # of 1-13/16" Round-Hot Rolled-Shallow Hardening Cold Heading Die Steel - Full analysis and sample on request.

GLOBE TRADING COMPANY

1815 Franklin Street

Detroit 7, Michigan

FOR SALE IMMEDIATE SHIPMENT FROM WAREHOUSE STEEL TUBING

1. Half Inch Tubing. .5 inch O.D. x .027'' wall, carbon steel tubing. C.D. welded, SAE 1010, 1,800,000 feet available. Lengths 16 and 18 feet. Price 3½ cents per foot in 100,000 foot quantities.

2. 34 inch oval tubing. .54 x .84 0.D. (oval), 16 gauge carbon steel tubing, C.D. welded, hollow ground, SAE 1010. 500,000 feet available. Length 16 feet. Price 4 cents per foot in 100,-

WAGNER & GROBAN

270 Park Avenue, New York 17, New York

Plaza 8-1485

EVERYTHING FOR THE TRACK FROM SWITCH TO BUMPER

NEW & RELAY RAILS

in stock

12# THRU 130# SECTIONS

ACCESSORIES & SWITCH MATERIALS INQUIRIES SERVICED PROMPTLY

ORRISON RAILWAY SUPPLY CORP.

New RAILS Relaying

Railway Track Accessories

STANDARD IRON & STEEL CO. Office & Yards: Knoxville, Tennessee



Keep'em rolling ... not rusting

FOR SALE

New-Used-Reconditioned railroad freight cars • car parts • locomotives • tank cars • steel storage tanks

MARSHALL RAILWAY EQUIPMENT

Corporation

50 Church St., New York 7, N. Y. COrtlandt 7-8090 Cable MARAILQUIP

FOR SALE STAINLESS STEEL **TYPE 304**

10 gauge 36" x 96", 20,000 lbs. 11 gauge 36" x 96", 2,000 lbs. Material is HRAP #1 finish. Original mill packing on skids. Mill test reports available.

SHALLAND CORP.

131 Breckner Blvd., N. Y. 54, N. Y. PHONE: CYPRESS 2-5617

3-10-ton Shaw Overhead Cranes, 67' 1" span, 230 VDC, box girders, structural end trucks, cage type Shaw motors and control, mechanical and electrical brake on hoist — heavy type — good condition — stored inside — ready to ship. PRICE f.o.b. Pittsburgh, Pa.

\$9,500.00 each SEND ME YOUR CRANE INQUIRIES -200 other cranes, various tonnages, spans and current.

JAMES P. ARMEL — Crane Specialist 710 House Bldg. Pittsburgh, Pa. Telephone: Grant 1-4449

SALE OR RENT

-D6 Front-end loader
-TD-9 Front-end loader, 1950
-25-Ton Link Belt MC-90 Fruck Crame 120' Beam
-20-Ton Lorain 414 Truck Crame
-2 Yd. Keehring 803 Crame
-355 P. & H. Dragline
-35 Ton Davenport Diesel Electric Loco.
-No. 6 and 80-D Northwest Shovels
-10-Ton Link Belt Mcdel 55 Wagon Crame
-Northwest 25 Shovel Attachment
-10-Ton Stiff Leg Derrick
-40-Ton Orton Diesel Loco. Crame
-40-Ton Industrial Brownhoist Oil Fired Loco.
Crame. New 1943.

B. M. WEISS CO.

Girard Trust Co. Bldg., Phila. 2, Pa. Rittenhouse 6-2311

23 NEW STEEL TANKS

9—10.000 GAL. CAP. ½ IN. SHELL 5—15.000 GAL. CAP. 5/16 IN. SHELL 9—20.000 GAL. CAP. ¾ & 5/16 IN.

SHELL LESTAN CORP., ROSEMONT, PENNA.

FOR SALE Good Used Equipment

Every type of machine available. Find the equipment you need in the CLEARING HOUSE SECTION of THE IRON AGE

00

EQUIPMENT AND MATERIALS WANTED

WEISS STEEL CO. INC.

600 WEST JACKSON BLVD. CHICAGO &, ILLINOIS Duyers of Surplus Steel Inventories 32 Years of Steel Service

WANTED SURPLUS STEEL WALLACK BROTHERS

7400 S. Damen Ave.

Chicago 36, Illinois

WANT TO BUY 3-AIR COMPRESSORS 3-2000 to 3000 FT. CAP. OR 6-1000 to 1500 FT. CAP. DARIEN CORP., 60 E. 42nd St., N. Y. 17, N. Y.

WANTED BRIDGE CRANES

ARNOLD HUGHES COMPANY 765 PENOBSCOT BLDG. DETROIT, MICH. WOodward 1-1894

WANTED

#1 High Speed Hamilton Gear Hobber Small Pfauter or Schuchardt & Schuette Gear Hobbers

ADDRESS BOX S-SGO Care The Iron Age, 100 E. 42nd St., New York 17

TRADE WITH BAUER BUY - SELL - TRADE

COMPRESSOR VACUUM PUMP 205 ESSEX AVE

BLOOMFIELD, N. J

Try the WANTED SECTION

for "Hard-to-Find" Materials or Equipment

WANTED TO BUY

Straightening machine for either 41/2 or 6" rounds. Gag press for straight-ening 8" squares or 16" x 4" slabs. ROBERT C. YOCUM

Mount Union, Pa.

Phone 504R3

BUSINESS OPPORTUNITIES

for . . .

n

T.

N

١d

GE

THE BUSINESS OPPORTUNITY

YOU

MAY BE LOOKING FOR

READ

THE CLASSIFIED SECTION of

THE IRON AGE

THE PORT OF NEW YORK AUTHORITY LINCOLN TUNNEL THIRD TUBE MANUFACTURE, STORAGE AND DELIVERY

BOLTS, NUTS AND WASHERS
CONTRACT LT-160.002

Sealed proposals for the manufacture, storage and delivery of bolts, nuts and washers for the lining of the Third Tube of the Lincoln Tunnel will be received at the office of the Chief Engineer of The Port of New York Authority, Room 1100, 111 8th Ave., New York 11, until 2:30 P.M. Friday, November 7, 1952, at which time and place said proposals will be opened and read.

Contract documents may be seen at the office of the Engineer of Materials, Room 1110, and copies will be furnished upon deposit of \$25 per set. Deposit to be delivered to the Treasury Department, Room 1001, where a receipt in duplicate will be issued. A copy of the receipt should then be delivered to the Engineer of Materials who will furnish the contract documents. The deposit will be remitted if the documents are returned in good condition, not later than 30 days after the opening of proposals.

THE PORT OF NEW YORK AUTHORITY

ening of proposals.
THE PORT OF NEW YORK AUTHORITY
Howard S. Cullman, Chairman

PUMPS, ELECTRIC MOTORS, ETC. CONTRACT 413

SEALED BIDS will be received by the Board of Water Supply, at its offices, thirteenth floor, 120 Wall Street, New York City, until 11:00 A.M., Eastern Standard Time, on Tuesday, October 28, 1952, for Contract 413, for furnishing, testing and delivering deep well turbine pumps and deep well plunger pumps, electric motors and appurtenances for the Neversink intake chamber, the Downsville release water chamber and the intake and outlet chambers of the East Delaware tunnel, of the Delaware system, all as set forth in the specifications.

No bid will be received and deposited unless accompanied by a certified check upon a National or State bank, drawn and made payable to the order of the Comptroller of the City of New York, in the amount of four thousand dollars (\$4,00.00), for the proper execution of the contract.

At the above place and time the bids will be publicly opened and read. Pamphlets containing information for bidders, forms of bid and contract, specifications, contract drawing, requirements as to surety, etc., can be obtained in Room 1311, at the above aidress, upon application in person or by mail, by depositing the sum of five dollars (\$5.00) in cash or its equivalent for each pamphlet. Within 20 days following the award of contract or rejection of bids, the full amount of such deposit will be refunded for each pamphlet submitted as a bid and a refund of four dollars (\$4.00) will be made for each other pamphlet returned in acceptable condition. For further particulars, apply at the office of the Chief Engineer at the above address. above address

IRVING V. A. HUIE, President, RUFUS E. McGAHEN, EDWARD C. MAGUIRE, Commissioners, Board of Water Supply: RICHARD H. BURKE, Secretary.

NEED A MANUFACTURER FOR PRODUCTS OR PARTS?

See the

Contract Manufacturing Section of the IRON AGE

1st & 3rd ISSUES of the MONTH ONLY

CONTRACT MANUFACTURING DIRECTORY

The directory of production services. (This section appears in the first and third issues of each month.)



Nepsco

NEW ENGLAND

PRESSED STEEL COMPANY

Contract Manufacturers since 1914

METAL STAMPINGS

SPECIALTIES - APPLIANCES

For Industrial and Domestic Users

P. O. BOX 29 MASSACHUSETTS

HNDTANA

QUALITY STAMPINGS

STEEL, BRASS, BRONZE, COPPER
ALUMINUM and ZINC



Parts or complete assemblies produced to exact specifications and on time. Modern facilities; sound financing; speedy dependable service. Send us samples or drawings for quotations.

INDIANA PRESSED STEEL CO., INC. 400 S. Ohio Ave. — Phone 3-3364 MUNCIE, INDIANA

STAMPINGS

STAMPINGS - ASSEMBLIES

To drawing or sample

Drilling Blanking Riveting Forming Tapping Welding

DESIGN & DEVELOPMENT

Toolmaking of course

HUEBEL MFG. CO., INC.

763 Lexington Avenue Kenilworth, N. J.

STAMPINGS

Steel—Brass—Aluminum
Fabricating
Assembly
Painting

Parts made to specifications

GGG METAL STAMPING CO., INC. STARBRICK Station Warren, Pa.

STAMPINGS-PUNCHINGS



NATICE

WASHERS

made to your

STA-FAST WEDGES made of stamped steel SELF-ALIGNING BELT FASTENERS — BOTH HAVE GREAT HOLD-ING POWER

SALING MANUFACTURING CO. Standard Belt Fastener Div. UNIONVILLE, CONN.

Intricate Assemblies Our Specialty

Over 60 years of precision manufacturing; Stamping, tools, dies, jigs, screw machine products.

100,000 sq. ft. floor space Modern Equipment

"Greater Savings With Greist"

GREIST MFG. CO.

GREIST MFG. C

646 Blake Street New Haven, Connecticut

ALUMINUM

Industries STAMPINGS - DRAWINGS - SPINNINGS Dies and Tools

AMERICAN ALUMINUM WARE CO.

OPEN TIME

In metal plant with the most modern equipment for fabricating Miscellaneous items in all metals to either light or heavy assemblies. Quotations promptly furnished, send us your requirements.

NATIONAL BENT STEEL CORP. 53-01 Nurge Avenue Maspeth, L. I., N. Y.

METAL STAMPINGS



 Over 20 years of shop practice combined with designing and engineering skill enables us to create dependable dies for your intricate metal stampings. Let us produce your parts in large or

mall quantities.

Send Us Your Blue Prints and Specifications

THE THE DIE and STAMPING CO.

STAMPINGS

Light and Medium
Electric Spot Welding and
Assembled Units

We specialize in designing stampings to substitute castings. Dies designed and built for quantity production.

Eastern Tool & Stamping Co., Inc. 39 Ballard Street, Saugus, Mass,

METAL

STAMPINGS

LARGE FACILITIES

AREA LIMIT—36 SQ. IN. THICK-NESS, 020 to 125. WILL BUILD TOOLS OR USE YOURS.

Send drawings or samples for prices.

J. H. SESSIONS & SON

270 RIVERSIDE AVE. BRISTOL, CONN.

Special Washers

We carry in stock Silicon killed Steel specially suited for case-hardening Stock dies for producing washers from .0015 to ½" thick.

Thomas Smith Company 294 Grove St., Worcester, Mass.

Contract Machine Work

Parts and Complete Machines, Heat Treating and Grinding, Mail Blue Prints for Quotations.

GENERAL MACHINE WORKS

CONTRACT MANUFACTURING



OVER 35 YEARS EXPERIENCE Steel Castings—5 to 15,000 lbs. Careful Workmanship-Top Quality Write for "Atlantic Axioms" ASC

STEEL CASTINGS COMPANY Sixth and Lloyd Streets Chester 3-4181 Chester, Pa.

FORGINGS DROP

Special Forgings of Every Description. We solicit your prints or model for quotation.

Wilcox Forging Corporation Mechanicsburg

ions

CO.

HIO

q

S.

n-

ic.

D

N

eat

ue

S

G

Penna.



ALL METALS Also special screw ma-chine products to order EASTERN MACHINE SCREW

CORPORATION New Haven, Cenn. Makers of H & G DIE HEADS

NEED COMPONENT PARTS FOR YOUR PRODUCT?

Find the plant which can supply them in the

CONTRACT MANUFACTURING SECTION

FORGINGS - HY-GRADE

To your Blue Prints — Any Analysis Weldness Rings — Discs — Bars and Miacellaneous Forgings — Rough Turned or Heat Treated — Also Stainless Steels.

PATERSON STEEL & FORGE COMPANY Stratford, Connecticut

SPECIAL MACHINERY

DIAMITE Abrasive Resistant Castings NI-RESIST Heat & Corrosion Resistant Castings P M G BRONZE High Strength Acid Re-sistant Castings

Fully Equipped—Pattern Foundry & Machine Shop Facilities—Castings to 15 tons. Weatherly Foundry & Mfg. Co., Weatherly, Pa.

Which casting will serve YOU best?

NON-GRAN SAND CASTING **NON-GRAN** CENTRIFUGAL





Send your prints for prompt quotation

American Non-Gran Bronze Co. Berwyn, Pa.



PLATE SHEARING

Capacity up to 3/8" x 12 feet We will do your shearing Economically — Efficiently

MORGAN STEEL CORP.

Brooklyn 22, N. Y. 430 Morgan Ave. Telephone-EVergreen 8-0202-3-4

GRAY IRON CASTINGS

MACHINE TOOL CASTINGS-UP TO 20 TONS EACH

THE SESSIONS FOUNDRY CO.

81 W. Farmington Ave. Bristol, Connecticut Telephone 4168

for REAL SERVICE

Screw Machine Products

Made to your specifications and tolerances. From smallest up to 258" diameter in steel, brass and aluminum.

OLSON MANUFACTURING CO. Worcester, Mass 100 Prescott Street.



MILLING SERVICE ... JIG BORING ... SPOT WELDING ... CON-

JOB SPOT

TRACT PRODUCTION ... EXPERIMENTAL DEVELOPMENT

WELDING We Solicit Your Inquiries. EISLER ENGINEERING CO., Inc. 737 So. 13th St. Newark 3, N. J.

GREENE ARC FURNACES

Up to 15 tons per hour For steel mills and foundries

GREENE ELECTRIC FURNACE CO. 2702 6th Ave. So. Seattle 4, Wash.

EMPLOYMENT EXCHANGE

EMPLOYMENT SERVICE

SALARIED PERSONNEL \$3,000-\$25,000— This confidential service, established 1927, is geared to needs of high-grade men who seek a change of connection under conditions assuring, if employed, full protection to present position. Send name and address only for details. Personal cor-sultation invited. JIRA THAYER JENNINGS, Dept. K, 241 Orange St., New Haven 10, Conn.

EMPLOYMENT SERVICE

ELECTRICAL ENGINEER—for design and development of small, fractional, sub-horsepower motors—salary commensorate with experience. Other openings for electrical engineers. Write Elyria Placement Service, 30 Century Block, Elyria, Obio, confidential, ethical, private employment service Openings for Chief Design engineer, inquiries on other openings invited. Personnel request from employers welcomed.

ROLL TURNER

Wanted: Roll Turner. Experienced on bar mill and special shapes. Please

ADDRESS BOX S-839

Care The Iron Age, 100 E. 42nd St., New York 17

HELP WANTED

SALESMAN

Steel Warehouse handling Hot-Rolled Steel seeking salesman. Salary basis. Good prospects. Must have following, especially industrial accounts, Greater New York or New Jersey.

CONCORD STEEL CORPORATION 120 Wall Street New York 5, N. Y.

DESIGN ENGINEER

10 to 15 years practical experience in designing. Open-Hearth Furnaces. Write giving details to Employment Office.

BETHLEHEM STEEL CO.

501 E. Third St.

BETHLEHEM, PA

SALARIED POSITIONS \$3,500 to \$35,000. We offer the original personal employment service lestablished, 42 years). Procedure of highest ethical standards is individualized to your personal requirements. Identity covered; present position protected. Ask for particulars, R. W. BIXBY, NC., 274 Dun Bldg., Buffalo 2, N. Y.

October 16, 1952

EMPLOYMENT EXCHANGE

The meeting place for employers and men qualified for positions in the metalworking industry.

Help Wanted Rates Employment Service Rates Representatives Wanted Rates **Accounts Wanted Rates**

Set	Solid-50 words or less
	Each additional word 25c
All	capitals—50 words or less
	Each additional word
AII	capitals, landed—50 words or lass\$19.50
	Each additional word

Situation Wanted Rates \$2.50 \$3.75

\$5.00

COUNT SEVEN WORDS FOR KEYED ADDRESS

HELP WANTED

SALESMAN

Experienced in sale of Steel Pipe and Tubing or related items, to follow-up leads by telephone. Attractive starting salary with opportunity to build a real future for man who qualifies. Location in Midwest. Write in detail, giving complete information in first letter.

ADDRESS BOX S-825 Care The Iron Age, 100 E. 42nd St., New York 17

SUPERINTENDENT SHEET METAL PRODUCTION SHOP

Excellent opportunity with substantial and growing concern for man thoroughly experienced in handling production; quality control, tools, dies, equipment and personnel. Submit complete resume in confi-

ADDRESS BOX 8-859 Care The Iron Age, 100 E, 42nd St., New York 17

INDUSTRIAL SALES EXECUTIVE Between the age of 45 and 60. Must be familiar with steel mill requirements.

ADDRESS BOX P-206

814 Park Building

Pittsburgh 22, Pa.

"METALLOGRAPHER or Junior Metallurgist in Manufacturing Plant Metallurgical Department, experienced in Metallographic studies of terrous and non-ferrous metals and alloys. Foundry experience desired. Salary open. State qualifications, references, age, and salary expected in the first letter." Address Box S.857, care The Iron Age, 100 E. 42nd St., New York 17.

HELP WANTED

WANTED

Assembly Yard Superintendent

Fully experienced on shop and yard assembly of structural steel tabrication for all types of bridges.

Excellent opportunity for man of experience — attractive salary and bonus.

ADDRESS BOX S-850

Care The Iron Age, 100 E. 42nd St., New York 17

GENERAL FOREMAN—Sheet Metal. Require experienced man capable managing Metal Fabrication Department approximately (75) men. Loction Southern Virginia. Strong background department management and complete knowledge machine set up, sheet metal production and assembly operations. Medium size Company growing fast offers real opportunity. Send resume with recent earnings first letter. Replies confidential. Address Box S-858, care The Iron Age, 100 E. 42nd St., New York 17.

ACCOUNTS WANTED

MANUFACTURERS AGENT

Accounts wanted by reliable sales firm with Pittsburgh office and covering Western Pennsylvania, Upper New York Stale, Eastern Ohlo, and West Virginia. Call: Atlantic 1-2779.

ADDRESS BOX P-205 Care Iron Age, 814 Park Bldg., Pittsburgh 22, Pa

DETROIT-AUTOMOTIVE MANUFACTURERS' AGENT

Having wide and close acquaintance with buyers and engineers of all of the automobile manufacturers and who has highly successful record. Is desirous of recresenting manufacturer, making any production item or accessory which would be of interest to the ear makers.

ADDRESS BOX E-51 Care Iron Age, 103 Pallister Ave., Deti Detroit, Mich.

SITUATIONS WANTED

ENGINEERING EXECUTIVE, Vice President, General Manager, Works Manager, Capable administrator with ability to handle comprehensive manufacturing and management problems desires manufacturing and management problems desires permanent association with medium size firm binancially sound. Twenty-five year's manufacturing and management exterience including labor relations. Thorough knowledge of modern manufacturing techniques coupled with outstanding Washington contacts. Sound reason for change. Address Box S-855, care The Iron Age, 100 E. 42nd St., New York 17.

VICE PRESIDENT sales past fourteen years to industrial trade desires to represent reputable manufacturer of heavy machinery equipment on manufacturing agency basis. Address Box S-838, care The Iron Age, 100 E. 42nd St., New York 17,

MACHINE SHOP SUPERINTENDENT with wide experience in both Production and Jobbing Shops would like connections with a growing and progressive company. Address Box S-842, care The Iron Age, 100 E. 42nd St., New York 17.

SALES EXECUTIVE dealing with industrial trade has proven record of successfully building two husiness's from its inception on percentage hasis. Only interested in a sound proposition. Address Box S-837, care Tle Iron Age, 100 E. 42nd St., New York 17

MASTER MECHANIC OR MECHANICAL SUPT., integrated steel mill or foundry, 30 years steel mill experience. Address Box S-816, care The Iron Age, 1016 National City Bank Bldg., Cleveland 14, Ohio.

ENGINEERING EXECUTIVE - Chief designer for prominent producer of gear manufac-turing machinery desires similar position with progressive organization. 30 year background of engineering and administrative experience. Age 50. Address Box S-862, care The Iron Age, 100 E. 42nd St., New York 17.

... DON'T HIDE YOUR LIGHT UNDER A BUSHEL . . .

Have something new on the market or do you just want to tell why your product does the job better?

Either way, your advertisement in The Iron Age carries more weight and reaches more of your prospects.

DO YOU HAVE . . . A JOB FOR THE RIGHT MAN? ARE YOU . . . THE RIGHT MAN FOR THE JOB?

> Employers and men qualified for positions in the metalworking industry get together in the

EMPLOYMENT EXCHANGE of The IRON AGE

ADVERTISERS IN THIS ISSUE


ADVERTISERS	IN THIS ISSUE
A	Continental Steel Corp
Abbott Ball Co. 118	Crowford, F.H., & Co., Inc. 160
Accurate Perforating Co	Crucible Steel Co. of America 22
Acheson Colloids Co	Curry, Albert, & Co., Inc. 153
The 62	
Ajax Electric Co., Inc. 4 Ajax Electric Furnace Corp. 4	
Ajax Electro Metallurgical Corp. 4	D
A ax Electrothermic Corp. 4	Darien Corp. 161, 163 Davis, Samuel M. 160
Ajax Engineering Corp. 4	Davis, Samuel M. 160
Alliance Machine Co., The 23 Allstates Equipment Co	Delco Products Div., General Mo- tors Corp. 71
Alter Company 125	Diamond Manufacturing Co. 169
American Air Compressor Corp. 158	Donahue Steel Products Co. 156
American Aluminum Ware Co. 164 American Chain Div., American	Dony, D. E., Machinery Co. 159 Dreis & Krump Mfg. Co. 168
Chain & Cable Co. 76-77	The state of the s
American Chain & Cable Co. 76-77	
American Non-Gran Bronze Co. 165 American Optical Co. 20	
American Pulverizer Co 42	E
American Smelting & Refining Co. 93	Eastern Machine Screw Corp., The
American Steel & Wire Div., United States Steel Co. 26-27	165, 168
American Wheelabrator & Equip-	Eastern Machinery Co., The 155
Anti-Carrosive Metal Products Co	Eastern Tool & Mfg. Co
Inc. 118	Inc. 164 Edison, Thomas A., Inc., Edison
Armco Steel Corp 6	Edison Thomas A., Inc., Edison Storage Battery Div. 94
Armel, James P	Eister Engineering Co., Inc. 165
Atlantic Steel Castings Co. 165	Electric Equipment Co. 160
	Elyria Placement Service 165 Emerman Machinery Corp. 159
	Espen-Lucas Machine Works, The 163
	Ex-Cell-O Corp. 120
B	
Baird Machine Co., The 90	
Baker & Co., Inc	F
Balcher Mchry. Co	
Bauer, L. W	Falk Machinery Co. 157 Foote Bros. Gear & Machine Corp 32
Bauer Mchry, Co 156	Fort Pitt Bridge Works 47
Beaird, J. B., Company	Foster, Frank B., Inc
Belyea Co., Inc	Foster, L. B., Co
Bennett, Letcher W., & Sons 156	Frank, M. K 162
Bennett Machinery Co	
Bethlehem Steel Co. 1 Bixby, R. W., Co. 165	
Board of Water Supply 163	6
Bolling, Stewart & Co., Inc. 161	
Brad Foote Gear Works, Inc. 138 Bristol Brass Corp., The	GGG Metal Stamping Co., Inc. 164 Galbreath Machinery Co
Brownell, Hazard Machine Tools	General Electric Co., Apparatus
Inc. 154	Dept
Browning, Victor R., & Co., Inc. 169 Builders Steel Supply Co. 162	General Machine Works
Bundy Tubing Co	Globe Trading Co
	Goodman Electric Machinery Co. 160
	Goss & DeLeeuw Machine Co. 163 Great Lakes Steel Corp
	Green, A. P., Fire Brick Co. 83
C	Greene Electric Furnace Co 165
Carborundum Co., Refractories	Green Instrument Co. 82
Div. 74	Greer Stop Nut Co
Carlyle Rubber Co., Inc. 156 Carpenter Steel Co., The 122	Griffin Manufacturing Co. 169
Carpenter Steel Co., The Webb	
Wire Div. 168 Cincinnati Bickford Tool Co., The 12	
Claymont Steel Corp., Subsidiary	
of The Colorado Fuel & Iron Corp. 85	Н
Cleveland-Cliffs Iron Co., The 145	H and P Die & Stamping Co., The 164
Cleveland Steel Tool Co., The 168	Harper, H. M., Co 89
Cleveland Worm & Gear Co., The Inside Front Cover	Hayward Company, The 163
Clyde Iron Works, Inc. 8	megr & rower Co., Inc.
Cold Metal Products Co., The 36	Hubbard, M. D., Spring Co. 169
Columbia Geneva Steel Div., United States Steel Co. 26-27	Huebel Mfg. Co., Inc. 164
Columbia Too! Steel Co. 146	Hughes, Arnold, Co. 161, 163
Cone Automatic Machine Co., Inc. 31	Hyman, Joseph, & Sons 157 Hyman Press Sales Corp. 157
Continental Foundry & Machine Co. 137	Hyman-Michaels Co. 162

(Continued on Page 168)



"WHITEHEAD WILL HAVE DIES FOR THESE WASHERS"

Washers are "big business" with Whitehead. Production is fast, economical. Big runs from automatic presses. U. S. Air Corps Standard washers, U. S. and S.A.E. Srandards, etc. WRITE FOR CATALOG



WHITEHEAD STAMPING CO.



1669 W Lataverre . Detroit 16, Mich

· Detroit 10, Mich

YOCAR ESTAB.

YOUNGSTOWN STEEL CAR CORPORATION

NILES, OHIO

Large scale producers of . . . big weldments on a production basis — die pressed channels for bus, truck and trailer chassis — railway cars, repairs and parts — miscellaneous heavy presswork.



ABRASIVE CUTOFF MACHINES 3-H.P. line—wet and dry cutting, bevel or rt. angle. Capacity: 34" solids; 2" tubing; 2" x 6" lt. sheet formed sections; ½" x 1" flats.

10-H.P. line—wet cutting, rt. angle or bevel. Capacity: 2½'' solids, 3'' x ½'' angles, 4½'' tubing; ¾' x 3'' flats. Write for literature. Specify shape, size and material to be cut.

TABOR MANUFACTURING CO.

6222 Tacony Street, Phila. 35, Pa.

MATHEWS

Since 1905. Engineers and manufacturers of Conveyers and Conveyer Systems for the Metal-Working Industries.

Three modern plants. Engineering Offices in All Principal

Cities. There's an Engineering Sales Office near you.



MATHEWS CONVEYER CO.

ELLWOOD CITY . . . PENNSYLVANIA SAN CARLOS CALIFORNIA PORT HOPE . . ONTARIO, CANADA

WEBB WIRE



NEEDLE
and
STAINLESS =



THE CARPENTER STEEL CO.

Webb Wire Div.
NEW BRUNSWICK, N. J.



I amous for accuracy and straightness of threads, low chaser costs, less densities, more pieces per day



THE EASTERN MACHINE SCREW CORP., 21-41 Barelay Street, New Haven, Conn. Pacific Coast Representative: 4. O. Behinger, \$35 N. Sen Pedro St., Lee Angeles, California. Canada: F. F. Barber Machinery Co., Torento, Canada.

JISCO A

SILVERY

A Blast Furnace Product made from Only Virgin Ores

THE JACKSON IRON & STEEL CO. - JACKSON, OHIO

OHIO LOCOMOTIVE CRANES



DIESEL . GASOLINE . ELECTRIC . STEAM

THE OHIO LOCOMOTIVE CRANE CO.

THE

CLEVELAND STEEL TOOL

Co.

Punches, Dies, Chisels, Rivet Sets 660 E. 82nd St., Cleveland, O. If it's RIVETED you KNOW it's safe

PRESS

43 Standard Sizes

Forming for All Makes and Sizes of Press Brakes.



DHELS & KHUMP MANUFACTURING COMPANY 7430 S. Leomis Blvd., Chicogo 36, Illinois



ADVERTISERS IN THIS ISSUE

(Continued from Page 167)

1	Mathews Conveyer Co. 167
Indiana Pressed Steel Co., Inc 164	Maxwell Machinery Corp 159
Indianapolis Machinery & Supply	Metal Carbides Corp
Co 159	Metalwash Machinery Corp 11
Inland Steel Co 96	Miles Machinery Co
Iron & Steel Products, Inc 157	Monsanto Chemical Co 66
	Morgan Construction Co
	Morgan Steel Corp
	Morrison Rallway Supply Corp 162
J	Mundt, Chas., & Sons
Jackson Iron & Steel Co., The 168	
Jandru Steel Corp	
Jennings, Jira Thayer 165	N
	National Acme Co., The 21
	National Automatic Tool Co 33
K	National Bent Steel Corp 164
Kalamazoo Tank & Sile Co 82	National Machinery Exchange 158 National Steel Corp
Kaplan, M. S., Company 131	National Steel Corp. 53 New Departure Div., General Mo-
Kearney & Trecker Corp 45	tors CorpFront Cover
Kidde, Walter, & Co., Inc 13	New England Pressed Steel Co 164
Kinderman, Lou F 159	Northern Equipment & Supply Co. 158
Kings County Mchry, Exchange 157	Norton Company 28-29
Kline Iron & Metal Co., The 158	
Kling Bros. Engineering Works 51	
Knox, Earl E., Co 157	
	0
1	O'Connell Machinery Co 154, 160
	O'Neil-Irwin Mfg. Co 9
Land, L. J., Inc	Ohlo Electric Mfg. Co., The 148
Lang Machinery Co 157	Ohio Locomotive Crane Co., The 168
Lansing Stamping Co 52	Olson Manufacturing Co 145
Latrobe Steel Co	O'Neill, A. J
Lee, K. O., Co 150	Ottemiller, Wm. H 169
Leland-Gifford Co 169	
Leschen, A., & Sons, Rope Co 14-15	
Lestan Corp 162	
Lucas, J. L., & Son, Inc 155	,
Luria Bros. & Co., Inc 129	Palnut Co., The
	Paterson Steel & Forge Co 165
	Peterson Steels Co
M	Pittsburgh Lectromelt Furnace
M	Corp
MacCabe, T. B., Co	Port of N. Y. Authority 163
MacLeod Co., The 25	Public Service Electric & Gas Co. 144
Marshall Railway Equip, Corp 162	Purdy Company, The 162
Martin, Joe, Co., The	Pusey and Jones Corp., The 116

(Continued on Page 170)



Cutting Off
Machines for
Sawing All Kinds
of Metals

THE ESPEN-LUCAS MACHINE WORKS FRONT AND GIRARD AVE., PHILADELPHIA, PENNA.



HAYWARD BUCKETS

Use this Electric Motor Clam Shell for rehandling bulk materials in Industrial Plants THE HAYWARD CO., 40-50 Church St., N.Y.



GOSS and DE LEEUW

CHUCKING MACHINES

Four, Five, Six, Eight Spindles - Work and Tool Rotating Type GOSS & OF LEEUW MACHINE CO., KENSINGTON, CONN. Gears, Chain and Pulleys 8000 Stock Items



59

51

66

45

150

33

164

53

158

165

165

84

163

162

E

Vartical baring mills to 80", Lucas baring mills to 334", Planers to 4' and 12', Radial drills to 6', Lathes to 52" and Grinder 10" D x 144" SPUR — SPROCKETS
SPLINES — BEVELS — WORMS
RACKS SECTORS — HELICAL

Jigs, Fixtures, Gauges Welded Fabrications

Wood and Metal Patterns and Models

. MACHINE REPAIR PARTS . BREAKDOWNS A SPECIALTY

• ROUND THE CLOCK SERVICE Job and production machining, including lathes, turrer lathes, screw machines, mills, grinders, all types; broaching and gear equipment. OVER 400 MACHINES TO SERVE YOU

OVER 400 MACHINES TO SERVE YOU

Ask for our equipment list and complete catalogue of over 8000 stock items—gears, chain, spiines, and sprockets.

UNIVERSAL GEAR WORKS INC.
1309 E. McNICHOLS

SINCE 1910
FOrest 6-2280

DETROIT 3, MICHIGAN

70 Your SPECIFICATIONS

GRIFFIN COLD ROLLED STRIP STEEL




WM. H. LEONORI & CO., Inc., 30 Howard St., New York 13, N. Y.; CHARLES L. LEWIS, 1355 Market St., San Francisco 3, Cal.; J. J. LAMBERT, 323 Huntington Ave., Buffale, N. Y.; CENTRAL STEEL & WIRE COMPANY, 13400 North Mt. Elliott, Detroit 2, Mich.; 3000 West 51st St., Chicago 80, Ill.; Box 148 Annex Station, Cincinnati 14, Ohso.

GRIFFIN MANUFACTURING CO. . ERIE, PA.





VICTOR R. BROWNING & CO., INC., WILLOUGHBY (Cleveland), OHIO





COP-R-LOY PIPE-SHEETS

A BELLE CUT NAILS

WHEELING STEEL CORPORATION

COPPER—BRASS—BRONZE

TO YOUR REQUIREMENTS
SEND US YOUR DRAWINGS FOR PRICE

PERFORATED METALS

FOR ALL INDUSTRIAL USES
ALL SIZE AND SHAPE HOLES—ALL METALS
ARCHITECTURAL GRILLES

DIAMOND MFG. CO.

BOX 28 Write for Catalog 35 WYOMING, PA.

. .

•••••

GOOD NEWS for the grinding department





Production up! That's the bulletin board's big news...good news that started when Simonds Abrasive Company wheels went to work in the grinding department. Simonds complete line includes wheels accurately specified for top results on *your* jobs . . . grinding wheels, mounted wheels and points, segments and abrasive grain . . . all made under complete quality control by Simonds Abrasive Company, a major manufacturer of grinding wheels for almost 60 years. Write for free data book and your distributor's name.



SIMONDS ABRASIVE CO., PHILADELPHIA 37, PA. BRANCH WAREHOUSES: CHICAGO, DETROIT, BOSTON DISTRIBUTORS IN PRINCIPAL CITIES

Division of Simonds Saw and Steel Co., Fitchburg, Mass. Other Simonds Companies: Simonds Steel Mills, Lock-port, N. Y., Simonds Canada Saw Co., Ltd., Montreal, Que. and Simonds Canada Abrasive Co., Ltd. Arvida, Que.

ADVERTISERS IN THIS ISSUE

(Continued from Page 168)

R
Reliance Electric & Engineering Co 24
Republic Steel Corp. 17
Ritterbush & Co., Inc
Russell, Burdsall & Ward Bolt & Nut Co 55
Ruthman Machinery Co., The
Ryerson, Jos. T., & Son, Inc
Saline Manufacturing Co.
Saling Manufacturing Co. 164 Seaboard Steel Co. 160
Sessions, J. H., & Son
Sessions Foundry Co., The
Shalland Corp. 162
Signode Steel Strapping Co 72
Simonds Abrasive Co
Sipi Metals Corp. 158
Smith, Thomas, Co
Square D Company 79
Standard Iron & Steel Co
Steel & Tube Div., Timken Roller Bearing Co. Back Cover
55.5
T T
Tabor Manufacturing Co., The 167
Tennessee Coal & Iron Div., United States
Steel Co
Timken Roller Bearing Co., The Back Cover
Torrington Co., The 119
Torrington Manufacturing Co
Trabon Engineering Corp Inside Back Cover
Tracerlab, Inc
Transue & Williams Steel Forging Corp 56
U Union Ban & Banca Core
Union Bag & Paper Corp
United States Steel Co
United States Stove Co
Universal Gear Works
Vanadium Alle Steel Co.
Vanadium-Alloys Steel Co 95
W
Wagner & Groban
Wallack Bros. 163
Wean Equipment Corp. 18-19
Weatherly Foundry & Manufacturing Co
Weiss Steel Co., Inc., 163
Wellman Bronze & Aluminum Co., The 80
Wendt-Sonis Co
West Penn Machinery Co
Wheeling Steel Corp 169
Whitehead Stamping Co. 167
Wilcox Forging Corp. 165
Williams, Edward Hale, Mfg. Engr 160
Williams-White & Co. 46
Wiping Materials, Inc.
Wisconsin Steel Co.
Y
Yocum, Robert C

CLASSIFIED SECTION

Youngstown Steel Car Corp.

Business	Ор	port	unities					,		. ,						16	d
Clearing	Ho	use												I	52-	16	í
Contract	M	anufo	cturing	1				 						1	64-	16	Š
Employm	ent	Exc	nange			,	,						 		65-	16	N
Wanted																	



cost you hard maintenance dollars if they're not properly lubricated.

All these bearings can be automatically lubricated with a Trabon system. When you install a Trabon system, you don't need to worry about whether the proper amount of oil or grease is being delivered at the proper time.

Completely sealed against dirt.

E

60

67

Size, type, motion or location of a bearing make no difference to a Trabon lubrication

Our patented progressive feature guarantees that no bearing will be short-changed. Operation of each measuring valve depends on the previous valve having operated first.

Get your metalworking bearings on a Trabon Lubrication System . . . complete engineering data or general information in Bulletin 529 are yours for the asking, from our representative near you, or the address below.

(Manifold and Reversible Systems)

Trabon Automatic Lubrication Fits Any Bearing Situation



MOST STABLE GAGE STEEL EVER MADE!

...and outwears others 3 to 1!

NEVER before has a tool steel offered gage users and gage makers so many advantages! Graph-Mo* tool steel is a different kind of tool steel. And the difference is so real you can see it—in the form of tiny, scattered, parallel marks barely visible on the surface of a piece of polished Graph-Mo.

These marks are the result of free graphite in the steel's structure. And this free graphite, together with diamond hard carbides, enables Graph-Mo to outwear other tool steel an average of 3 to 1. Reports from dozens of gage users prove it! (Details on request.)

Tests prove Graph-Mo is also the most stable gage steel

ever made. After a 12-year period a typical Graph-Mo steel master plug gage showed less than 10 millionths of an inch change from its original measurement.

And constant pressure machinability tests show Graph-Mo machines 30% faster than other tool steels. (Machinability test data on request.)

You can always tell Graph-Mo by its "graphitic look". This built-in "trade-mark", the result of the free graphite in its structure, can't be duplicated in other steels. Look for it, insist upon it, next time you buy gages. The Timken Roller Bearing Company, Steel and Tube Division, Canton 6, Ohio. Cable address: "TIMROSCO".

YEARS AHEAD-THROUGH EXPERIENCE AND RESEARCH

TIME Alloy

STEEL

SPECIALISTS IN FINE ALLOY STEELS, GRAPHITIC TOOL STEELS AND SEAMLESS TUBING